NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Suroj Buildcon
Bungalow No. 3, Liberty Society Phase-I, North Main Road,
Koregaon Park, Pune 411 001, Maharashtra, India.

Date : 05.11.2020
Quote NO : SQT.20.21.2799
Kind Attn : Prashant Patil
Email Id : pspatil@suroj.in
Contact No: 7447459207

Project, Location : Kimberly Clark, Sanasanwadi, Pune

Subject : Quotation for Sectional Doors, High Speed Doors, Dock Shelter, Dock Lever and Motorized Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2 , 3
C.	General Conditions	4
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**NIHVA Make Sectional Door (Vertical Lift)**	3000	3000	3	215,000	645,000	20,000	60,000
2	**NIHVA Make High Speed Door**	3000	3000	13	350,000	4,550,000	20,000	260,000
3	**Retractable Dock Shelter**	3200	3250	13	75,000	975,000	20,000	260,000
4	**Dock Leveler (6 Ton)**	2000	2500	9	190,000	1,710,000	20,000	180,000
5	**Motorized Rolling Shutter**	3000	3000	17	85,000	1,445,000	20,000	340,000
6	**Motorized Rolling Shutter**	3000	5000	3	110,000	330,000	20,000	60,000
7	**Truck Guide (Standard Size)**			17 set	14,000	238,000	4,000	68,000
8	**Dock Bumber Guards (Laminated Bumper Guards)**			17 set	6,000	102,000	4,000	68,000
	Total			**58**		**9,995,000**		**1,296,000**
9	P&F Charges			3%		299,850		
	Total Without Taxes					10,294,850		1,296,000
	GST Extra @ 18%			18%		1,853,073.00		233,280
	Total With Taxes					**12,147,923**		**1,529,280**
10	Transportation Charges					Extra at atcual		
11	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA Sectional Door

Sr. No	Specification	Sectional Door
1	**Vision Windows**	2 Nos at central panel
2	**Opening Direction & Mounting**	Vertical lift
3	**Opening/Closing Speed**	CDM9 0,28 m/s
4	**Door Material**	GI Steel
5	**Panel Thickness**	42 mm Square Grid, steel sheet
6	**Filling**	CFC-free polyurethane
7	**Panel colour**	RAL 9002 Grey White Powder coated
8	**Door sealent**	All door sealants made of EPDM rubber, temperature resistant - 30/+70
9	**Panel Flame Retardent standrad**	Flame retardant polyurethane foam according DIN4102-class B2.
10	**Water Penetration**	EN 12425 class 3
11	**Air Permealibity**	EN12426 class 3
12	**Wind Load**	EN21424 class 3
13	**Thermal Transittance**	EN 12428 1.10W /m2K
14	**Bottom sealing**	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
15	**Door saftey**	Doors equiped with spring break device
16	**Incase of Power failuer**	Doors to be equiped with quick release fuction
17	**Operator power conumption**	Operator to have a maximum power consumption of 0,37kW and a standby consumption of
18	**Drive Unit & Mounting Type**	Single phase 230V direct drive on shaft
19	**Emergency Operation**	by Disengagement rope manual
20	**Operating Switch**	Up/Down Keypad + stopbutton
21	**Locks : Lock bolt**	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible
22	**Environmental Green Product Declaration**	As per ISO 14025 and EN 15804

NIHVA Make High Speed Door

Sr. No	Specification	NIHVA Make High Speed Door
1	**Area of use:**	Inside
2	**Material:**	Galvanised steel
3	**Colours:**	8 standard colors - white, yellow, green, orange, red, gray, black, blue
4	**Vision Window**	Single row with 400 mm Height
5	**Opening Direction**	Vertical
6	**Control System**	TS-970 GFA
7	**Openi/Closing Speed**	0.9 m/s
8	**Wind load resistance:**	EN 12424 Class 2
9	**Control Voltage**	24 V DC
10	**Motor Power /kW**	0,45 kW
11	**Safety:**	Photocells in side columns
		Flexible soft bottom edge including wireless edge activator
		Break-away and self-repair function

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Retractable Dock Shelter

Sr .No.	Specification	Dock Shelter
1	**Top Curtain**	1000 mm
2	**Side Curtain**	600 mm
3	**Curtain colour**	Black
4	**Parking Guides**	White, Yellow
5	**Wall Fixings**	Concrete, Sandwich light Concrete, Load house cavity, insulated panel
6	**Top & Side Curtains**	Double Layer High Quality Polyester
7	**Thickness**	3.0 mm
8	**Weight**	Approx 3400 g/m2

Dock Leveler

Sr .No.	Specification	Dock Leveller
1	**Capacity**	6 Ton
2	**Dock operation mode**	AC power pack hydraulically operated
3	**Lip operation mode**	Hydraulic
4	**Operation control**	Through panel
5	**Loading platform height from road**	1250mm
6	**Travel above & below dock level**	(+) 300 / (-) 250 mm
7	**Platform Size (W x L)**	2000 mm x 2500 mm
8	**Lip size (W x L)**	2000 x 400 mm
9	**Shut Height**	480 mm
10	**Overall length**	2000mm x 2500mm + Lip Length (400mm)
11	**Maximum slope can be achieved**	0.1
12	**Clear Pit dimensions (W x L x D)**	(W) 2050mm x (L) 2550 mm x (D)485 mm
13	**Hydraulic power pack**	Standard
14	**Driver type**	Direct by electric Motor
15	**Motor Ratings**	1 H.P
16	**Pump design flow**	2.5 LPM
17	**Pump pressure**	120 bar Operating 200 bar Max.
18	**Safety valve set pressure**	120 Kg/cm²
19	**Pump Type**	Gear
20	**Volume of oil receiver**	7 Lit
21	**No Of Deck cylinder**	2 No
22	**Lip Cylinder**	1 No
23	**Yellow and Black Strips for Side Guide**	Included
24	**Dock Bumper**	Pair of Dock Bumper
25	**Dock Bumper steel Gard**	Steel Support Plates
26	**Operation**	not stopping automatic while any truck movement

Motorized Rolling Shutter

Sr .No.	Specification	GI Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick GI.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S. profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 1.2 mm GF mm.
12	**Surface finish**	PU paint or Powder coated
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd