WORK ORDER

Client:	
Suroj Buildcon Pvt. Ltd.	
Address:	
Bungalow No.03, Liberty Society P-I, North Main Road, Koregaon Park, Pune - 411 001, Maharashtra.	

PO Number:	ICP-PO-HO-221011001	**W. O. No-**	SO/22-23/049
PO Dated :	11-10-2022	**W. O. Date**	11-10-2022
PO Received Date:	11-10-2022	**Sales Co ordinator**	Pradeep Shinde
Ref. Quotation:	SQA.22.23_0215 R2,	**Front Sales Person**	Yogesh Kulkarni

Dispatch Address:

C/o Ideal Chemi Plast Pvt. Ltd.,
Plot E2, Supa Industrial Estate, Supa,
Dist.-Ahmednagar,, -, Maharashtra (India) 414301

Contact Details : MrAppa Dhatrak - 7774081375

A Technical Terms:

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	**Motorised Single Leaf Sliding Gate W 12500 mm X H 1800 mm**	**Sheet 2**	**Nos**	**2**			-	**Pending**
2	**Manual Wicket gate W 1200 mm X H 1800 mm**	**Sheet 2**	**Nos**	**3**			-	**Pending**
						Total		-

Non standard items/extra requirement, if any:	

B	**Commerical Terms:**			
1	**Payment Terms:**	20% advance along with purchase order, 70% after receival of material @ site within 7-10 Days & balance 10% after successful commissioning & certification by project team.		
2A	**Delivery Date as per PO:**	On Or Before 10-Nov-22	**2B. Required Delivery Date:**	
3A	**Transportation Scope:**	Inclusive	**3B. Transportation Charges:**	
4	**P&F Charges:**	NIL		
5A	**Loading Scope:**	NIHVA Scope	**5B. Loading Charges:**	
6A	**Unloading Scope:**	CLIENT Scope	**6B. Unloading Charges:**	
7A	**Lifting Equipments Scope:**	NIHVA Scope	**7B. Available Lifting Equipments:**	
8	**Warranty:**	12 months from the date of supply.		
9A	**Height arrangement Scope:**	CLIENT Scope	**9B. Available Equipments for working at Site:**	
10	**Electricity Supply:**	CLIENT Scope		
11	**GST:**	18%		
12A	**Installation Scope:**	NIHVA Scope	**12B. Installation required date:**	
13	**Mode of import:**	NA		
14	**HSS:**	NA		
15	**Documentation Required:**	Standard Handover Documents		
16A	**Total site visits required:**		**16B. Site visit charges:**	

Certified that the above work order finalised in presence of:

GM	SALES		Operation	PROJECT	DESIGN	Date & Time
A.K.	V.T.		S.B.	C.C	Sujata	

Motorised Single Leaf sliding Gate

Sr .No.	Specification	Motorised Single Leaf sliding Gate
1	**Door type**	Motorised Single Leaf sliding Gate
2	**Opening Direction**	Horizontal - from left to right or reverse
3	**Mounting Location area**	Inside area
4	**Design Pattern**	Standard Tubular Design Pattern
5	**Outer Tube**	122 x 61 x 4.5 mm MS SQ. TUBE
6	**For Post**	122 x 61 x 4.5 mm MS SQ. TUBE
7	**Innear Tube**	80 x 80 x 4 MS SQ. TUBE
8	**CD Between Inner Tubes**	165 mm
9	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	**Guide Rollers supporter**	Nylon Rollers with Bearings both side mounted on column for support smooth
12	**Painting**	1 coat 60 micron primer & 2 coat (30 micron each) QD paint
13	**Operation**	By Electric Motor (100% Imported)through Rack & Pinion
14	**Spike**	Spike On the Top - As per drawing
15	**Inclusive Accessories**	Flashing Lamp
		Remote
		Limit Switch
		Photocell

Manual Wicket Gate

Sr .No.	Specification	Manual Wicket Gate
1	**Door type**	Manual Wicket Gate
2	**Opening Direction**	90 Deg angle -Outside or inside
3	**Design Pattern**	Standard Tubular Design Pattern
4	**Outer Tube**	122 x 61 x 4.5 mm MS SQ. TUBE
5	**Innear Tube**	80 x 80 x 4 MS SQ. TUBE
6	**CD Between Inner Tubes**	125 mm
7	**Painting**	1 coat 60 micron primer & 2 coat (30 micron each) QD paint
8	**Accessories**	Aldrop & operated by heavy duty hinges