NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Landsky Engineers Pvt. Ltd
35-69,GK Colony,Sainikpuri PO,
Secunderabad:500 094

Date : 20.06.2022
Quote NO : AS_22.23.0014
Kind Attn : Mr. Subrahmanyam
Email Id : purchase@landskyindia.com
Contact No: 9951001949

Project Name & Location: Landsky Engineers Pvt. Ltd., Secunderabad

Subject : Commercial Offer for Manual Scissor Lift Trolley

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size	Qty	Supply Charges in INR		Installation Charges in INR	
		Working Platform (in mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**SS Manual Scissor Lift Table** • Capacity 100-150 Kg • Lifting Height: 2100 mm • Close height: 600-700mm	1900 L mm X 1000 W mm	1	6,60,000	6,60,000	35,000	35,000
			Total		**6,60,000**		**35,000**
		Total without Taxes			**6,60,000**		**35,000**
2	GST Extra @ 18%		18%				**Extra At Actual**
3	P&F Charges on Total Supply Value		3%				**Extra At Actual**
4	Transportation Charges						**In Client Scope**
5	Unloading Charges @ Site						**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

SS Manual Scissor Lift Table

Sr. No	Description	Specifications
1	**Capacity**	100-150 Kg
2	**Platform size**	(L) 1900 mm X (W) 1000 mm
3	**Shut Height**	600-700 mm
4	**Lift Height from ground level**	2100 mm
5	**Type of platform**	SS PLAIN SHEET With Perforation
6	**Operation**	Manual - Foot Pedal
7	**No of platform**	2no- Both Platforms table surface (double decker)

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 After 1 year warranty, Non comprehensive AMC will be provided by NIHVA which is at an additional cost.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material.
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required.
5	All structure support required.
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8-9 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.

Payment : 70% Advance along with Confirmed Purchase Order.
20% Along with Approval of Drawing and before start a Production.
5% Against completion of Installation, Testing and Commissioning.

Validity : Validity of Offer is 7 days from the date of quotation

Warranty : 12 months from the date of supply.

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd