**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**SCON Projects Pvt. Ltd**
Office No.1A, Harshal Corner, Plot No.5, Survey
No.78, Left Bhusari Colony, Paud Rd., Kothrud
Pune - 411038 .

**Date :** 04.03.2020
**Quote NO :** SQT/19-20/2477
**Kind Attn :** Mr. Kamlesh Bhagade
**Email Id :** kamleshb@sconprojects.com
**Contact No:** 8308809561

**Subject : Quotation for Sectional Door and High Speed Door. ( Project Location - Innovatec india pvt. Ltd. ).**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**


| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 4 |


**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | Scetional Door - Vertical Mounting | 5000 | 4000 | 1 | 295,000 | 295,000 | Included | |
| 2 | Scetional Door - Horizontal Mounting | 3500 | 2500 | 2 | 258,000 | 516,000 | Included | |
| 3 | Nihva Make High Speed Door | 6500 | 4000 | 1 | 419,000 | 419,000 | Included | |
| 4 | Nihva Make High Speed Door | 5000 | 4000 | 2 | 382,000 | 764,000 | Included | |
| | | | | **Total** | | **1,994,000** | | - |
| 5 | P&F Charges | | | 3% | | 59,820 | | |
| | **Total Without Taxes** | | | | | 2,053,820 | | - |
| | GST Extra @ 18% | | | 18% | | 369,687.60 | | - |
| | **Total With Taxes** | | | | | **2,423,508** | | - |
| 6 | Transportation Charges | | | | | In Client Scope | | |
| 7 | Unloading Charges @ Site | | | | | In Client Scope | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B)** **TECHNICAL SPECIFICATION -**

| Sr .No. | Specification | Sectional Door -Crawford - NIHVA Assaabloy | |
|---|---|---|---|
| 1 | Door type | 1042P | |
| 2 | Door produced Based on which certificatio | Doors produced according to ISO 9000 or ISO 14000 certified processes | |
| 3 | Opening/Closing Speed | 0.25 m/s | |
| 4 | Door Material | GI Steel with PUF inside | |
| 5 | Panel Thickness | 42mm | |
| 6 | Panel colour | RAL 9002 Powder coated | |
| 7 | External surface of the panel | diamond grid design with a glossy finish at the section joints. | |
| 8 | inside surface of the panel | Monolithic surface on the inside of the door | |
| 9 | Broken cold bridge | Section joints with broken cold bridges | |
| 10 | Door sealent | All door sealants made of EPDM rubber. | |
| 11 | All Panel height | All panels should be 545mm high | |
| 12 | Panel Inside insulation metrial | Insulation material to be CFC free polyuretane foam. | |
| 13 | Panel Flame Retardent standrad | Flame retardant polyurethane foam according DIN4102-class B2. | |
| 14 | Steel component Material | All steel components to be electro galvanized | |
| 15 | Hinge Material | Glass fibre reinforced Polyamide | |
| 16 | Panel Thickness | 42 mm | |
| 17 | Spring Material surface finish | Powder coated | |
| 18 | Water Penetration | EN 12425 | class 3 |
| 19 | Air Permealibity | EN12426 | class 2 |
| 20 | Wind Load | EN21424 | class 3 |
| 21 | Thermal Transittance | EN 12428 1.10W /m2K | |
| 22 | Bottom sealing | Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber | |
| 23 | Door saftey device 1 | Doors equiped with spring break device | |
| 24 | Door saftey device 2 | Door equiped with pneumatic safety edge | |
| 25 | Door saftey 3 | Having hinges flush with the inside door surface is a safety feature that eliminates the risk of things or people getting caught by parts protuding | |
| 26 | Incase of Power failuer | One can operate the Door manually | |
| 27 | Operator power conumption | Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W | |
| 28 | Drive Unit & Mounting Type | Single phase 230V direct drive on shaft | |
| 29 | Emergency Operation | by Disengagement rope manual | |
| 30 | Operating Switch | Up/Down Keypad + stopbutton | |
| 31 | Environmental Green Product Declaration Certification | as per ISO 14025 and EN 15804 | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**HIGH SPEED PVC ROLL UP DOOR**

| Sr. No | Description | Specifications |
|---|---|---|
| 1 | Use | Internal Door |
| 2 | Speed | Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking |
| 3 | Opening speed | 1 m/s |
| 4 | Closing speed | 1 m/s |
| 5 | Control Panel | 4 Push Button operated |
| 6 | Security Features | EN 13241-1 Standard |
| 7 | Resistance to wind load | EN12424 upto class 1 |
| 8 | Curtain | Fabric Transparent PVC section |
| 9 | Guide Material | Aluminum |
| 10 | Hood Cover | GI |
| 11 | Motor Cover | GI |
| 12 | Operator & Control | German Make Motor |
| 13 | Connecting Voltage | 220V , 1Ph , N |
| 14 | Open-Stop-Close Button | Standarad |
| 15 | Protection Category | IP 54 / IP 65 |
| 16 | Power Consumption | 0.75 kw Motor |
| 17 | Emergency Off Button | Standard |
| 18 | Closing Zone Monitoring | Optical Safety edge |
| 19 | External Route Monitoring | Photocell |
| 20 | Emergency Opening | Crank Handle |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 8 - 9 weeks for High Speed Doors and 12 -13 weeks for Sectional Doors from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd