NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad. Pune – 411019

An ISO 9001:2015 Certified Company
GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Institute Of Animal Nutrition
Tamil Nadu Veterinary and Animal Sciences University,
Kattupakkam - 603 203,Chengalpattu District.

Project, Location : Institute Of Animal Nutrition, Chennai

Date : 30.05.2022
Quote NO : AS_22.23.0004R
Kind Attn : Dr. Murgeshwari
Email Id : drmuruann@gmail.com
Contact No: 90474 27561

Subject : Quotation for Automatic Bi-Parting Sliding Glass Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Automatic sliding Glass door Size		Qty	Supply & Installation Charges in INR	
		Clear Width (m)	Clear Height (m)	(Nos)	Unit Price	Total Amount
1	**Automatic Bi-Parting Sliding Glass Door along with Fixed top glass frame size (w5.00m x h1.00m) + MS structure for glass door. Overall size: w5.00m x h3.00m (Fixed frame: w2.50m x h1.00m & Sliding frame: w2.50m x h2.00m)**	2.5	2	1	5,25,000	5,25,000
2	**Automatic Bi-Parting Sliding Glass Door along with Fixed top glass frame size (w3.00m x h2.50m) + MS structure for glass door. Overall size: w3.00m x h4.50m (Fixed frame: w1.50m x h2.50m & Sliding frame: w1.50m x h2.00m)**	1.5	2	1	4,70,000	4,70,000
	Total			**2**		**9,95,000**
3	GST Extra @ 18%					Extra at atcual
4	P&F Charges @ 3%					Extra at atcual
5	Transportation Charges					Extra at atcual
6	Unloading Charges @ Site					In Client Scope

B) Technical Specification

Sr .No.	Specification	
	POWER DRIVE	
1	**Motor**	High performance and heavy duty DC motor with integrated encoder and gearbox
2	**Power Supply**	170-260 V AC 50-60 Hz
3	**Power Consumption**	170 W
4	**Protection Class**	IP22
5	**Carrying Capacity**	170 Kg for single leaf, 240 Kg for double leaves
6	**Clear Opening**	2,400 x 3,000
7	**Operator Chassis Size**	125 x 168 mm , Aluminium
8	**Carrier Assembly**	Two carrier assembly for each leaf, (2 main and 1 balancing wheel for each carrier assembly)
9	**Trigger Belt**	Special trigger belt design for maximum safety and endurance and minimum noise level
	MICROPROCESSOR	
10	**Working Temperature**	- 20* C + 50* C
11	**Position Selector**	Digital , 6 user positions, LCD touch screen
12	**User Modes**	Auto , Open , In , Out , Locked , Half Opening
		Opening Speed, Closing Speed, Hold Open Time, Half Opening Distance, Opening, Direction, Installer
13	**Installer Settings**	Password, User Password
14	**Obstacle Detection**	Permanent obstacle detection in both opening and closing cycles.
15	**Energy Saving**	Short braking distance during opening and closing cycle for energy saving
16	**Interlocking**	2 doors can be operated using interlocking mode
17	**Resetting**	Can be performed using digital position selector without opening operator cover
18	**Compatibility**	Compatible with fire alarm and access control systems
19	**Fault Monitoring**	Error codes are shown on the digital position selector screen.
	SENSOR	
20	**Safety**	3D infrared curtain photocell
21	**Opening**	Radar
22	**Combiner (Opening + Safety)**	Opening radar with integrated 3D infrared curtain photocell, Energy saving, EN16006
	DOOR LEAF	
23	**Frameless**	With 2 point fittings per door panel
24	**Operator Mounting**	On glass panel provided by others

NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad. Pune – 411019

An ISO 9001:2015 Certified Company
GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune
Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.
Validity : Validity of Offer is 15 days from the date of quotation
Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Vijay Tarak on 8551093333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd