NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/17-18/0064R **Date : 06-11-2017**

Max speciality films ltd
Bhai Mohan Singh Nagar Rail Majra
Nawanshahr Punjab 144533

Kind Attn : **Mr.Sreejith**
Email : sreejith@msfl.in
Contact No : 9878746565

Subject : Quotation for Conveyor System

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	Conveyor 1				
1	Telescopic Conveyor ; Length - 18 meter	1	No	16,03,000	16,03,000
2	Fixed Conveyor ; Length - 8650 mm	1	No	3,85,000	3,85,000
B.	Conveyor 2				
1	Take Down Conveyor ; Length - 2850 mm	1	No	5,50,000	5,50,000
2	Fixed Conveyor ; Length - 9500 mm				
C	Installation Charges For Above	1	No	50,000	50,000

GST PUNE:	27AAECN0437H1ZM
HSN Code	84289090

Amount in Words	Total Amount	25,88,000
	Rupees Twenty Five Lacs Eighty Eight Thousand Only	

Technical Specifications :-

SR NO.	Describtion	Specification
A	Conveyor 1 Includes	
1	Telescopic Conveyor Make - Nihva	
	Total Length	18 meter
	Fixed Length	6 meter
	Extended Length	12 meter
	Conveyor width	800 mm
	Height	1200 mm
	Control Panel	A fixed main panel with emergency stopper sensor bar, Led lighting
	Speed Of Conveyor	0-30 meter per minute
	Rated Voltage	415 V, 50HZ
	Rated Power	3 HP (Max)
	Belt Material	PVC
	Belt Thickness	6 mm
	Weight Capacity	50 kg/m
	Colour	Standard Blue
2	Fixed Conveyor Make - Nihva	
	Length of conveyor	8600 mm
	Width of conveyor	650 mm
	Control Panel	For one motor
B	Conveyor 2 Includes	
1	Take Down Conveyor Make - Nihva	
	Length of conveyor	2850 mm
	Width of conveyor	650 mm
	Control Panel	For one motor
	Motor Rating	0.5 HP
	Max Rpm	250-300 mm/sec
2	Fixed Conveyor Make - Nihva	
	Conveyor length	9500 mm
	Width of conveyor	650 mm
	Control Panel	For one motor
	Motor Rating	1 HP
	MOC for both Conveyor A & B	MS Painted
	Temperature	Ambient

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel.

Client Scope

1 Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2 All structure support is in client scope
3 NIHVA Will provided structure drawing only if required
4 Existing Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	3% Extra
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	8-9 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% advance along with confirm Purchase Order & balance before dispatch
6	**Insurance**	:	Extra if applicable
7	**Tax**	:	GST: 28% on total supply value
8	**Validity**	:	Validity of Offer is 15 days from the of quotation
9	**Warranty**	:	12 Months from the date of supply

Please feel free to Contact **Mr. Mayur Derle** on **7709209333** For any further Clarification /Information in this Concern.

With Best Regards

Pooja Badre

7709586333

For Nihva Technologies Pvt Ltd