NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Cushman wakefield Pvt.ltd
Pune

Date : 08.06.2020
Quote NO : SQT.19.20.2480R
Kind Attn : Mr. Koushal Inani
Email Id : Koushal.inani@cushwake.com
Contact No: 9900385943

Project Name & Location: Nashik

Subject : Quotation for High Speed Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2 , 3
C.	General Conditions	4
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**High Speed Door HS8010P**	1950	3500	2	7,98,000	15,96,000	15,000	30,000
2	**High Speed Door HS8010P**	3050	5000	5	9,18,000	45,90,000	15,000	75,000
				Total		**61,86,000**		**1,05,000**
3	P&F Charges			3%		**1,85,580**		
	Total Without Taxes					**63,71,580**		
	GST Extra @ 18%			18%		11,46,884		18,900
	Total With Taxes					**75,18,464**		**1,23,900**
4	Transportation Charges					**Extra at Actual**		
5	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

HS8010P

Sr. No	Description	Details
		High Speed Door HS8010P
1	Door construction:	The HS8010P is designed for exterior openings in medium-sized heavy-duty operations
2	Side Frames	Made up with Galvanised Steel Profiles. Unique side column technology provides excellent seal on all 4 sides thereby reducing heat loss
3	Door Curtain	• Door curtain 900 g/m² colored PVC, material thickness: 0,8 mm • Flexible door curtain without ridged parts. • The door curtain is available in 8 standard colors
4	Thermal transmittance:	(EN 12428) 6,02 W/(m²K)
5	Wind resistance:	(EN 12424) Class 4 (1000 Pa (N/m²))
6	Drive Unit :	1,5 KW. 400V, 3 Phase
7	Temperature range :	-20°C to +40°C
8	Operator protection:	IP65
9	Control system:	Control unit with display, impulse Up and Down buttons, an emergency stop mushroom button and a mechanical main switch
10	Speed:	Opening / closing up to 2,4 / 1,2 m/s. Depends on Door Size
11	Safety device:	• Flexible soft bottom edge including wireless edge activator. • Break-away and self-repair function. • Photocells in side columns.
12	Manual activation :	by releasing the brake at ground level. Partly opening by means of the pre-stressed tension springs.
13	Motor and Hood Cover	GI 0.8mm thick

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 11-12 Weeks for Sectional Door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd