NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

AllTech Biotechnology Pvt Ltd.
Chakan Pune

Date : 24.01.2022
Quote NO : **MHE_21.22.0056**
Kind Attn : Mr. Avinash Parkale
Email Id : abhagwatparkale@alltech.com
Contact No: 9108498001

Project Name & Location: AllTech Biotechnology Pvt Ltd. Chakan Pune

Subject : Quotation for Telescopic Truck Loader/Unloader Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Telescopic Truck Loader/Unloader Conveyor** • Total Length- 14.5mtr (Fixed-5.5mtr, Extended-9mtr) • Capacity- 15-20 bags/min • Belt Width - 600 mm • Light infront of the conveyor	**1**	**15,60,000**	**15,60,000**	**75,000**	**75,000**
	TOTAL EXCLUDING TAXES			**15,60,000**		**75,000**
2	GST Extra @ 18%	18%				**Extra At Actual**
3	P&F Charges	3%				**Extra At Actual**
4	Transportation Charges					**Extra At Actual**
5	Insurance Charges					**Extra At Actual**
6	Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Truck Loader/Unloader Conveyor

Sr. No.	Parameters	Specification
1	Material to be conveyed	Bags
2	Dimension of Bags(LxB)	750 mm x 500 mm
3	Weight of box	Max.50 Kg
4	Capacity	15-20 bags/min
5	Belt Width	600 mm
6	Belt Type	2 Ply 3.2 mm PVC
7	Belt Speed	15-30 mtr/min
8	Telescopic Speed	8-10 mtr/min
9	Conveyor Type	Collapsible boom type hinged Telescopic belt conveyor
10	Length Of Conveyor	Fixed Length :5500 mm Telescopic (Expanded) : 9000 mm Total Length : 14500 mm
11	Main Body Of Conveyor	MS Powder coated
12	Direction	Both Forward and Reverse direction
13	Working height	Min.850 mm and max. 1100 mm
14	Inclination Height	Max. 1200 mm
15	Speed adjustment	VFD (Schneider / Allen Bradley/Delta)
16	Gear Box	Bonfiglioli
17	Driven Motor Make	Bonfiglioli /CG/BBL , IE2
18	Movement	Movable (wheels provision)
19	Spot light	In front of the conveyor

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an additional cost which will be 8-9% of total project amount.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8-9 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch

Validity : Validity of Offer is 15days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Vijay Tarak on 85510 93333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd