NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune :

NIHVA Sales Quotation

IKEA India Private Limited
10th Floor, Greenheart - Phase IV
Mfar Manyata Tech Park, Nagawara
Bangalore, Karnataka – 560045, INDIA

Date : 08.05.2021
Quote NO : AS_20.21.0008R
Kind Attn : Pavan Kumar B S
Email Id : pavan.kumar2@ingka.ikea.com
Contact No: 9535500991

Project Name & Location: Mumbai

Subject : Quotation for Manual Mobile Scissor Table

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR	
		(Nos)	Unit Price	Total Amount
1	**Manual Mobile Scissor Lift** Platform Size - 1500 mm L X 1500 mm W Capacity - 800 KGS Close height – 300mm Lift Height -1500 mm Hand pump for lifting operation Wheels : Nylon Color : Golden Yellow OR Ultra Marin Blue Complete safety enclosure (L X W X H)1500 mm x 1500 mm x 1500 mm	1	1,90,000	1,90,000
		Total		**1,90,000**
	P&F Charges on Total Supply Value	3%		**5,700**
	Total Without Taxes			**1,95,700**
	GST Extra @ 18%	18%		**35,226**
	Total With Taxes			**2,30,926**
2	Transportation Charges			**Extra At Actual**
3	Unloading Charges @ Site			**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification -

Manual Mobile Scissor Lift

Sr. No	Description	Specifications
1	Capacity	800 KG
2	Platform size	1500 mm L X 1500 mm W
3	Closing height	300 mm
4	Lift height	1500 mm
5	Wheel	Nylon
6	Operation	Hydraulic Hand Pump
7	Safety Enclosure (L x W x H)	Complete Safety Enclosure 1500 mm x 1500 mm x 1500 mm

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune :

C) General Conditions

1. Installation will start after receiving of Site Readyness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	
3	Electrical Supply on the site single phase/three phase points at different places.	
4	Any civil / masonry/structural work required	
5	All structure support required	
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	
7	Conduits, Cables required	

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with purchase order and Balance against material dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Vijay Tarak on 8551093333**

With Best Regards
Prtaibha Mete
8530872333
For NIHVA Technologies Pvt Ltd