NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

CREATIVE CARVE PVT. LTD.
308, Sector 7, PCNTDA, Bhosari, Pune 411026.

Project, Location : Bhosari, Pune

Date : 15.1.2021
Quote NO : SQT.20.21.2921R1
Kind Attn : Harshvardhan Saraf
Email Id : saraf.hp@creativecarve.com
Contact No: 9822049981

Subject : Revised Quotation for Sectional Door Horizontal Lift

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Sectional Door Horizontal Lift**	4650	6000	1	477,000	477,000	20,000	20,000
2	**Uninstallation Charges**			1		-	25,000	25,000
	Total			**2**		**477,000**		**45,000**
3	P&F Charges			0%		-		
	Total Without Taxes					477,000		45,000
	GST Extra @ 18%			18%		85,860.00		8,100
	Total With Taxes					**562,860**		**53,100**
4	Transportation Charges					Extra at atcual		
5	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sectional Door - Horizontal Lift (Standard)

Sr. No	Specification	Sectional Door
1	**Vision Windows**	central panel
2	**Opening Direction & Mounting**	Horizontal lift (Standard)
3	**Opening/Closing Speed**	CDM9 0,28 m/s
4	**Door Material**	GI Steel
5	**Panel Thickness**	42 mm Square Grid, steel sheet
6	**Filling**	CFC-free polyurethane
7	**Panel colour**	RAL 9002 Grey White Powder coated
8	**Door sealent**	All door sealants made of EPDM rubber, temperature resistant - 30/+70
9	**Panel Flame Retardent standrad**	Flame retardant polyurethane foam according DIN4102-class B2.
10	**Water Penetration**	EN 12425 class 3
11	**Air Permealibity**	EN12426 class 3
12	**Wind Load**	EN21424 class 3
13	**Thermal Transittance**	EN 12428 1.10W /m2K
14	**Bottom sealing**	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
15	**Door saftey**	Doors equiped with spring break device
16	**Incase of Power failuer**	Doors to be equiped with quick release fuction
17	**Operator power conumption**	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
18	**Drive Unit & Mounting Type**	Single phase 230V direct drive on shaft
19	**Emergency Operation**	by Disengagement rope manual
20	**Operating Switch**	Up/Down Keypad + stopbutton
21	**Locks : Lock bolt**	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible from the outside.
22	**Environmental Green Product Declaration Certification**	As per ISO 14025 and EN 15804

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	NIHVA
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 40% Advance along with Confirmed Purchase Order & 55% Balance before dispatch and 5% after Installation.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Bhavin Jain on 8551092333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd