Sales Quotation

NIHVA TECHNOLOGIES PVT. LTD.

Quotation No - SQT/19-20/1844 **Date :23.07.2019**

Moët Hennessy India Private Limited
Gat No 652 & 653
Village & Taluka - Dindori
District - Nashik 422202

Kind Attn : Ms. Bhoopendra Upadhyay.
Email : bhoopendra.upadhyay@moethennessy.com
Contact : 7276828858

Project Name & Location: Moët Hennessy India Private Limited, Nashik .

Subject : Quotation for Motorised Rolling Shutter

Dear Sir
Thank you for the opportunity and trust shown on "NIHVA", your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; Please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Total Amount INR
A	**Motorized Rolling Shutter** **Technical Specifications:** **• MS Slat : 1.0 mm Thick** **• Profile : Curved Type Profile with heavy duty Shaft** **• Guide : 3 mm Thick MS Guide** **• Hood Cover : 1.2 mm Thick GI material** **• Direct Drive** **• Brackets** **• With Painting**				
1	**Size :** (W) 3600 mm x (H) 5000 mm (Supply + Installation + Loading + Unloading + scaffolding + Transportation)	1	No	300,000	300,000
2	**Size :** (W) 5000 mm x (H) 5100 mm ((Supply + Installation + Loading + Unloading + scaffolding + Transportation))	1	No	398,000	398,000
	Total				**698,000**
B	**Motorized Rolling Shutter** **Technical Specifications:** **• MS Slat : 1.0 mm Thick** **• Profile : Curved Type Profile with heavy duty Shaft** **• Guide : 3 mm Thick MS Guide** **• Hood Cover : 1.2 mm Thick GI material** **• Indirect Drive** **• Brackets** **• With Painting**				
1	**Size :** (W) 8920 mm x (H) 6950 mm (Grill) (Supply + Installation + Loading + Unloading + scaffolding + Transportation)	1	No	427,000	427,000
	Total				**427,000**
C	**Removing and Reinstallation of Existing Motorized Rolling Shutter**				
1	**Size :** (W) 4600 mm x (H) 5000 mm (Installation)	1	No	25,000	25,000
2	**Size :** (W) 4600 mm x (H) 5000 mm (MS Structure made of 100X50mm)	1	No	35,000	35,000
	Total				**60,000**

GST Pune	27AAECN0437H1ZM	**Total**	**1,185,000**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1. **Price** : Ex Works @ Site
2. **P & F Charges** : @3% of Total Supply Value
3. **Freight Notes** :Extra as applicable
4. **Delivery** : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
5. **Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6. **Insurance** : Extra As applicable
7. **Tax** : GST Extra @ actual
8. **Validity** : Validity of Offer is 15 days from the date of quotation
9. **Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr.Swapnil Kulat** on **7219207333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd