NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

3D Concept Analysis & Development (I) Pvt Ltd
Pune

Date : 20.06.2022
Quote NO : **MHE_22.23.0013**
Kind Attn : Mr. Sandip S. Ingle
Email Id : sandip.i@3dcad-global.com
Contact No: 7420868486

Project Name & Location: 3D Concept Analysis & Development (I) Pvt Ltd, Pune

Subject : Quotation for Flat Belt Conveyor & Bowl feeder

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	General Conditions	2
C.	Terms & Conditions	2

A) Commercial Offer

Sr. No.	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Flat Belt Conveyor** • Conveyor Length - 2000mm • Belt width - 800mm • Height - 800+/- 25mm •Belt Type- 2mm / Green / PVC • Motor - 0.5Hp • Speed - 15 Meters/min - Constant (No VFD) • Structure - 40x40x2.5mm thick • Support Plate - 2mm thick • MOC-MS powder Coated	**1**	**2,40,000**	**2,40,000**		**In Client Scope**
2	**Vibratory Bowl Feeder (Metal shop, Nut and Base Valve)** **A) Bowl Feeder** • Inside treatment-PU coating • C.E. Approved load cell controller **B) Linera Feeder (Length as per NIHVA std)** • Guide length-400-500mm • Linear feeder per stand • Bowl feeder stand • Bowl low level sensor arrangement • FRP enclosure for reducing sound • Sensor Arrangement	**3**	**5,46,000**	**16,38,000**		**In Client Scope**
3	**Ball screw operated scissor lift** • Close height: 300 mm • Lifting height: 750mm • Platform size: 800 W x 1800 L mm • Capacity: 300 Kg • Lifting time for up & down: 5 sec • Push button facility: On/Off/Stop/Emergency	**1**	**4,85,000**	**4,85,000**		**In Client Scope**
		Total		**23,63,000**		
4	GST Extra @ 18%	18%				**Extra At Actual**
5	P&F Charges @ 3%	3%				**Extra At Actual**
6	Transportation Charges					**In Client Scope**
7	Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 After 1 year warranty, Non comprehensive AMC will be provided by NIHVA which is at an additional cost.

Note: Please find below List which are in Client Scope.

Sr. No	
1	Secured and fully covered Store area to keep the material.
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required.
5	All structure support required.
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required.

C) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8-10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 70% Advance along with Confirmed Purchase Order.
25% Along with Approval of Drawing and before start a Production.
5% Against completion of Installation, Testing and Commissioning.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd