Sales Quotation

Quotation No - SQT/19-20/1699 **Date :11.06.2019**

Akums
Plot#26A, 27, 28, 29 & 30,
Sector - 8A, IIE, SIDCUL, Haridwar(UK)

Kind Attn: Mr. Ashish Pandey.
Email: purchasecoordinator@akums.in
Contact No: 8859000497

Project Name And Location : Hariswar

Subject : Quotation for Telescopic Conveyor.

Dear Sir
Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Telescopic Conveyor** **(Supply + Installation)**				
1	Conveyor Type : Telescopic Length : 9000 mm Width : 900mm Height : 900 mm Capacity: 75 kg / mtr Horizontal movement of conveyor: motor driven Safety Sensor at front with LED Light Operational Flashing lamp Speed : 3mtr / min Include Following - • Mechanical Structure • Machining Components • Mechanical Bought out (Flange mounted Bearings , Ball Bearings , Nylon Rollers , Conveyor belt , Couplings , Rubber rollers , Chain , Sprocket , LM Guides , hydraullic cylinder & power pack) • Electrical Bought out (Geared Motor 1 HP , 2 HP , 3 Hp , VFD Drive , Control Card , Sensors , Limit switch , Flashing lamp , LED Lights) • Control Panel	1	No	1,500,000	1,500,000
				Total	1,500,000

GST Pune	27AAECN0437H1ZM

TOTAL BASIC AMOUNT	**1,500,000**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@3% of Total Supply Value
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order and Balance before Dispatch.
6	**Insurance**	:	Extra As applicable
7	**Taxes**	:	GST Extra as applicable
9	**Validity**	:	Validity of Offer is 15 days from the date of quotation
10	**Warranty**	:	12 months from the date of supply.

Please feel free to contact **Mr.Ravindra Kharat - 7219207333** For any further Clarification /Information in this concern.

With Best Regards

Ulka Auti.
7219206333
For NIHVA Technologies Pvt Ltd