NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Unique Building Solutions
C-8, Chandra Darshan,
Opposite Ghosha society near Udan school,
Thaltej, Ahmedabad-380054.
Gujarat, India.

Date : 30.09.2019
Quote NO : SQT/19-20/2127
Kind Attn : Mr. Jalpan Hathi
Email Id : jalpan@uniquebuilding.in
Contact No: 7567322822

Subject : Quotation for Hermetic Sealed Sliding Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specifications	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Automatic Hermetic Sealed Sliding Door.	1500	2400	6	3,83,071	22,98,426	20,000	1,20,000
2	Mannual Hermetic Sealed Sliding Door.	1500	2400	20	3,07,000	61,40,000	20,000	4,00,000
				Total		**22,98,426**		**1,20,000**
3	P&F Charges			3%		68,953		
	Total Without Taxes					23,67,379		1,20,000
	GST Extra @ 18%			18%		4,26,128.18		21,600
	Total With Taxes					**27,93,507**		**1,41,600**
4	Transportation Charges					In Client Scope		
5	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) **Technical Specifications**

Laminate panel



Sr. No	Description	Specifications
1	Passing space (PL)	1500
2	Passing space (PH)	2400
3	Door thickness	60 mm
4	Door frame	Aluminium door frame
5	Internal panel	Core: extruded polystyrene plate Intermediate layer: MDF Surface cover: HPL laminate or stainless steel
6	Seal	Silicon
7	Window	600 x 400 mm [default dimensions] ø 400 mm [default dimensions]
8	Handle	Fixed handle: MAN 1 - MAN 2 * Mobile handle: MAN A1 - MAN A2 * Flush-fit handle: MAN I **
9	Protection against radiation	1, 2 or 3 mm thick lead strip

Valor HH

Sr. No	Description	Wings with hermetic seal
1	Stroke control	Encoder
2	Power supply	230 V AC / 50-60 Hz
3	Power input	0.041666667
4	Operating temperature	2°C / 55°C (2°C / 50°C with batteries)
5	Protection rating	IP 20
6	Product dimensions (mm)	150 x 300 x L
7	Control panel	EL32 (built-in)

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 - 11 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Vijay Tarak on 8551093333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd