NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

AUFEER DESIGN
s.r.o. | Ptacka 156 | 293 01 Mlada Boleslav
Czech Republic

Date : 06.02.2020
Quote NO : SQT.19.20.2144R
Kind Attn : Mr.MICHAEL LENC
Email Id : michael.lenc@afd.cz
Contact No: +420 734 172 478

Project Name & Location: VW India Pvt.Ltd. Pune

Subject : Quotation for installation of High Speed Door - RP300 USD

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in USD		Installation Charges in USD	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Rapid Roll Up Door RP300 USD**	5000	2200	1			750	750
5	P&F Charges			3%		-		
	Total Without Taxes					**-**		**750**
	Taxes : GST Extra @ 18%			18%		-		135
	Total With Taxes					**-**		**885**
6	Transportation Charges					**Included**		
7	Unloading Charges @ Site					**Included**		

Note : Exchange rate considered are : 1 USD = 70 Rupees

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

A) High Speed Door **RP300 USD**



Sr. No	Description	Specifications
1	Description	Door type Rapid Protect USD, upside down machine protection doors
2	Side frames	Anodized aluminum
3	Wind resistance	Class 1 (EN 12424)
4	Bottom profile	Anodized aluminum
6	Protection	IP 55
7	Control system	MCC Vector Control - frequency converter control system for a dynamic, smooth door movement, located close to the drive unit. Max. Opening Speed 2.2m/s Max. Closing Speed 1.5 m/s
8	Supply voltage	3L(N)PE/380/400/415/440/480V;50/60Hz
9	Safety devices	• Pre running photocells • counter balance
10	Emergency egress	Crank Handle

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10-11 Weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on +91 8551096333**

With Best Regards
Varsha
+91 8551091333
For NIHVA Technologies Pvt Ltd