NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No. SQT/19-20/1343R7 **Date : 3-Apr-19**

Creative Carve Pvt. Ltd.
308/309, Sector No-7,
PCNTDA, Bhosari,
Pune-411026.

Kind Attn : Mr. Mahindra
Email : parashar.mk@creativecarve.com
Contact : 7709849821

Subject :- Revised Quotation for Sectional Door and Sliding Gate

Dear Sir,

Thank you for the opportunity and trust shown on "NIHVA", your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**NIHVA make Motorised Sectional Door** **•2 windows on each door (for each extra window price will be Rs. 15000)** **•Safety Edge** **•Safety Sensor** **•Push button on both sides**				
1	**Size** : (W) 3700 mm X (H) 6200 mm **Standard Lift (Supply)**	1	No	4,25,000	4,25,000
2	**Size** : (W) 3700 mm X (H) 6200 mm **Standard Lift (Installation)**	1	No	12,000	12,000
3	**Size** : (W) 4000 mm X (H) 2500 mm **Standard Lift (Supply)**	1	No	2,69,000	2,69,000
4	**Size** : (W) 4000 mm X (H) 2500 mm **Standard Lift (Installation)**	1	No	12,000	12,000
D	**Single Leaf Motorized Sliding Gate** **• Outer Tube - 72 x 72 x 3.2mm MS SQ. TUBE** **• Inner Tube - (50 x 50 x 3mm) and (25 x 25 x 3mm) MS SQ. TUBE** **• GI sheet- 0.9mm**				
1	Size : (W) 8000 mm X (H) 1800 mm **(Supply)**	1	Nos.	4,27,000	4,27,000
1	Size : (W) 8000 mm X (H) 1800 mm **(Installation)**	1	Nos.	20,000	20,000
	Total				**11,65,000**
GST Pune	**27AAECN0437H1ZM**			**Total amount**	**11,65,000**
				Amount in words: Rupees Eleven Lakhs and Sixty Five Thousand Only.	

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	: @ site
2	**P & F Charges**	: NIL
3	**Freight Notes**	: NIL
4	**Delivery**	: 15-20 days for Sectional Door and 4-5 weeks for Sliding Gate from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	: 60% Advance along with Confirmed Purchase Order, 30% balance before dispatch against readiness & 10% after installation or 100% payment after Delivery and Insallation against 100% PDC chaque.
6	**Insurance**	: Extra As applicable
7	**Tax**	: GST Extra @ 18%
8	**Validity**	: Validity of Offer is 15 days from the of quotation
9	**Warranty**	: 12 months from the date of supply.

Please feel free to Contact **Mr.Bhavin Jain** on **8551092333** For any further Clarification /Information in this Concern.

With Best Regards

Swapnil Kulat

7219207333

For Nihva Technologies Pvt Ltd