NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

CP Consultants
Mohite Paradise, office no.310, 3 floor,
Sinhgad Rd, Manik Baug, Pune- 411051

Date : 07.07.2020
Quote NO : SQT.20-21.2416
Kind Attn : Mr. Ganesh Parkhi
Email Id : cpconsultantspune@gmail.com
Contact No: 9850741099

Project Name & Location: ELECTRO HYDRAULIC GOODS LIFT; Pune,

Subject : Quotation for ELECTRO HYDRAULIC GOODS LIFT.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Depth (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**ELECTRO HYDRAULIC GOODS LIFT**	1500	1500	2	4,67,107	9,34,214	25,000	50,000
				Total		**9,34,214**		**50,000**
2	P&F Charges			3%		**28,026**		
	Total Without Taxes					**9,62,240**		**50,000**
	GST Extra @ 18%			18%		1,73,203		9,000
	Total With Taxes					**11,35,444**		**59,000**
3	Transportation Charges					**In Client Scope**		
4	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr. No	Description	Specifications
1	**TYPE OF ELEVATOR - APPLICATION**	Goods
2	**Capacity**	1 ton
3	**Lift Height**	1500mm
4	**Power Pack**	Suitable 3 HP power pack AC power pack
5	**POWER SUPPLY**	3 Phase, 415 Volts, 50 Hz
6	**Hydraulic Cylinder**	Yes
7	**Hose Pipe**	5m
8	**Limit Switches**	Yes
9	**Collapsible door height**	2100 mm
10	**3 side fix railing**	1000 mm height
11	**Pallet size for loading unloading**	1250 x 1250 mm
12	**Surface Yellow Painted**	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope

3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) **Terms & Conditions**

Price : Ex Works Pune

Delivery : 6-7 Weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat 7410169333.**

With Best Regards
Samruddhi
7410175333
For NIHVA Technologies Pvt Ltd