**NIHVA TECHNOLOGIES**

**WEIGHT ESTIMATION SHEET**

| | | | |
|---|---|---|---|
| CLIENT | Cablex Pvt.Ltd | DATE | 27-04-2024 |
| PROJECT | Dock Leveller Booth for 2m X 2.5 M | LOCATION | Pune |
| | | PREPARED BY | Sumit |

| SR | DESC | DETAILS | MATERIAL GRADE | SP.GRAVITY | DIA | WIDTH | HEIGHT | THICKNESS | LENGTH | UOM | QUANTITY | WEIGHT | REMARK |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | Frame | Tubular SQ.Tube - Outer Frame | MS | 7.85 | | 80 | 80 | 3 | 2500 | mm | 10 | 181 | |
| | | Tubular SQ.Tube - Outer Frame | MS | 7.85 | | 80 | 80 | 3 | 3000 | mm | 4 | 87 | |
| | | A type frame | MS | 7.85 | | 80 | 80 | 4 | 3140 | mm | 8 | 240 | |
| | | Chucker Sheet | MS | 7.85 | | 500 | | 5 | 2500 | mm | 2 | 108 | |
| | | MS hollow Pipe - Railing | MS | 7.85 | 40 | | | 3 | 17 | M | 1 | 37 | |
| 2 | Covering | sheet | En8 | 7.85 | | 2500 | | 1.2 | 3000 | M | 1 | 81 | |
| | | Foundation Plate | MS | 7.85 | | 200 | | 10 | 200 | M | 20 | 69 | |
| | | | | | | | | | | Weight For Required Qty | 1 | 803 | |
| | | | | | | | | | | Weight Including Safety Factor | 1.5 | 1204 | |

Mode Of Operation = Manual

Weight As per Provided Reference Drawing

**REFERENCE IMAGE**

