Balaji Refrigeration Service
THE TRUSTED HVAC EXPERTS

Reg. Office: Plot No: 123, "Balaji House", Opp. Kotak Mahindra Bank,
Nr. Mehta Petrol Pump, Katargam-Amroli Road, Surat - 395004. (Gujarat)
Branch: Block No: 2, Krishna Park Society, Univercity Road, Puskardham Main Road,
Rajkot -360005. (Gujarat)
info@balajirs.com | balajirs2003@gmail.com
www.balajirs.com ☎ 0261 - 2530903 / 2533168

Offer Ref. No.: ATCTPL/0607/2022-23/R0 **Date: 07.06.2022**
GSTIN: 24AKIPS8643P1ZA

ATC TIRES PVT. LTD.
D-3-23 & 23-A, GIDC, PHASE-III, INDUSTRIAL ESTATE,
DAHEJ, VILLAGE, SAMONTPORE,
TALUKA-VAGRA, DISTT.: BHARUCH,
GUJARAT – 392130. (INDIA)

IND ATTN:

OFFER FOR VRF AIR CONDITIONING SYSTEM.

Dear Sir,

Having examined the requirement including all the receipt of which is hereby duly acknowledged, we the undersigned offer to supply, installation and commission in conformity with the said inquiry in accordance with the schedule of prices indicated in the commercial offer and made part of this offer.

Please also find the below mentioned attached annexure as a part of this offer submitted.

- **ANNEXURE I : PRICE BID**
- **ANNEXURE II : TERMS & CONDITION**
- **ANNEXURE III : ITEMS & SERVICES NOT INCLUDED**

We believe our offer is in line with your requirement. However, in case of any clarification please feel free to contact us.

Thanking you and assuring you our best attention all time.

Very Truly Yours
For Balaji Refrigeration Service.

Authorized Signature

ANNEXURE- I

SCHEDULE OF EQUIPMENT / PRICE BID **07-06-2022 12:36**

PROJECT: ATC TIRES PRIVATE LTD., DAHEJ PLANT

SR. NO.	DESCRIPTION - VRF SYSTEM	QTY	UNIT	RATE (INR)	AMOUNT (INR)
*	**Make: LG**				
1.0	**Supply of VRF Outdoor Units**				
*	20 HP (10 HP + 10 HP)	4	Nos.	2,45,024	9,80,096
2.0	**Double Skin Floor Mounted Vertical Type Air Handling Unit**				
*	3400 CFM @ 60 mm St. Pr.	2	Nos.	2,65,000	5,30,000
3.0	**Corded Remote Controller**	2	Nos.	3,500	7,000
4.0	**Ref. Joints for IDU**	RO	Nos.	4,000	-
5.0	**Ref. Joints for ODU**	RO	Nos.	7,000	-
6.0	**EEV Kit + Communication Kit**	4	Nos.	35,000	1,40,000
	SUB TOTAL (A)				**16,57,096**
	GST @ 28% (B)				**4,63,987**
	TOTAL HIGH SIDE (A+B)				**21,21,083**
1.0	**Installation of VRF Outdoor Units**				
*	20 HP (10 HP + 10 HP)	4	Nos.	15,500	62,000
2.0	**Double Skin Compact Type Ceiling Suspended Unit**				
*	3400 CFM @ 60 mm St. Pr.	2	Nos.	12,500	25,000
3.0	**Corded Remote Controller**	2	Nos.	1,000	2,000
4.0	**Ref. Joints for IDU**	RO	Nos.	1,500	-
5.0	**Ref. Joints for ODU**	RO	Nos.	1,500	-
6.0	**EEV Kit + Communication Kit**	4	Nos.	4,000	16,000
7.0	**All refrigerant piping with nitrile rubber insulation between indoor & outdoor units of copper pipes properly supported. (For VRF System)**	90	RMT	2,550	2,29,500
8.0	**Communication Control cables between indoor and outdoor unit laid in PVC conduit pipe and clamped .**	120	RMT	180	21,600
9.0	**Rigid PVC Drain Piping with Nitril Rubber Insulation.**	20	RMT	350	7,000
10.0	**Testing & Commisioning charges alongwith topping-up of R-410A Refrigerant Gas.**	2	Lot.	33,000	66,000
11.0	**Galvanized Rectangular Ducting**				
*	24 G	120	Sq. Mtr.	1,450	1,74,000
*	22 G	80	Sq. Mtr.	1,560	1,24,800
12.0	**Thermal Insulation with Class "O" Nitrile Rubber with Factory Laminated Alu. Foil**	280	Sq. Mtr.	800	2,24,000
13.0	**Acoustic Insulation with Open Cell Nitrial Rubber Insulation**	RO	Sq. Mtr.	1,350	-
14.0	**Duct Flexible Canvas Connection**	4	Nos.	4,500	18,000
15.0	**Aluminium Powder Coated Grill**	1.5	Sq. Mtr.	10,500	15,750
16.0	**Aluminium Powder Coated VCD**	1	Sq. Mtr.	7,500	7,500
17.0	**Electrical Control Panel for AHU, Veriable Frequency Drive for AHU Operations with Bypass Starter, HMI Display, Heater Operations etc.**	2	Nos.	2,00,000	4,00,000
18.0	**All Electrical Cabling from AC Equipment to Electrical Panel up to 5 Meter (Main Incoming Cable to Electrical Panel will be in Client's Scope.)**	2	Lot.	50,000	1,00,000
	SUB TOTAL (A)				**14,93,150**
	GST @ 18% (B)				**2,68,767**
	TOTAL LOW SIDE (A+B)				**17,61,917**
	TOTAL PROJECT COST				**38,83,000**

Special Note:

1. **Above mentioned quantity is approximate. Final quatity will be billed as per actual site installation / Measurment.**
2. **MS Fabricated Stand for ODU will be in Client's Scope.**



Balaji Refrigeration Service
THE TRUSTED HVAC EXPERTS

Reg. Office: Plot No: 123, "Balaji House", Opp. Kotak Mahindra Bank,
Nr. Mehta Petrol Pump, Katargam-Amroli Road, Surat - 395004. (Gujarat)
Branch: Block No: 2, Krishna Park Society, Univercity Road, Puskardham Main Road, Rajkot -360005. (Gujarat)
info@balajirs.com | balajirs2003@gmail.com
www.balajirs.com ☎ 0261 - 2530903 / 2533168

ANNEXTURE – II - TERMS & CONDITIONS

Terms of Payment:

100% Advance for Equipment with techno commercial Purchase Order.
50% Advance for Low Side with techno commercial Purchase Order.
40% After Installation of Equipment and Material at site.
Remaining 10% for Low Side after Commissioning of Job.

Taxes & Duties:

All Taxes are included in the provided offer.

Scope of Supply:

All kind of material described in the priced offer to supply will be in our scope. If any other to supply will be charged extra as actual.

Freight: -

Freight charge is inclusive.

Delivery:

High Side Equipment material will be delivered after 8-10 week after techno commercial clearance of purchase order with advance.

Offer Validity:

Above offer is valid for 7 Days.

Billing:

Mentioned quantity in BOQ is approximate, final billing will be made as per actual installation made on site.

Order to be placed on:

You have to issue an order with the following Name & Address.

Balaji Refrigeration Service
Plot No: 123, "Balaji House", 1F, Opp. Mehta Petrol Pump,
Nr. Kotak Mahindra Bank, Katargam, Surat – 395004.

Thanking you,

Yours Sincerely,
For Balaji Refrigeration Service

BALAJI REFRIGERATION SERVICE SURAT

Balaji Refrigeration Service
THE TRUSTED HVAC EXPERTS

Reg. Office: Plot No: 123, "Balaji House", Opp. Kotak Mahindra Bank,
Nr. Mehta Petrol Pump, Katargam-Amroli Road, Surat - 395004. (Gujarat)
Branch: Block No: 2, Krishna Park Society, Univercity Road, Puskardham Main Road,
Rajkot -360005. (Gujarat)
info@balajirs.com | balajirs2003@gmail.com
www.balajirs.com ☎ 0261 - 2530903 / 2533168

ANNEXUTRE – III - ITEMS / SERVICES NOT INCLUDED

1. Insulation of exposed roof with 2" thick Thermocole.
2. Electrical main incoming cable terminating on individual of all A/C units, together with earth. Main incoming Copper Armored Cable, ELCB, MCB, MCCB etc.
3. All civil works viz. breaking & making of walls, holes & passages for Duct if any.
4. Safe custody and lockable storage space at site.
5. Free electricity for erection & commissioning.
6. Wooden frames for fixing of grills & diffusers.
7. Wooden Boxing or Trap door required for all indoor unit.
8. Any Other Wooden Modification work will be in customer's scope.
9. Provision of drain points within vicinity of indoor unit.
10. Any modification in the existing false ceiling and making of new false ceiling.
11. Any items not specifically mentioned in the scope of work.
12. Water Supply for any work at site will be in customer's scope.
13. Authorized Work Permit to do work at site will be in customer's scope.
14. Any revision/changes in a work done as per approved drawing. If any will be charged extra as actual.

