NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Proarch Design Pvt.Ltd.
No.105, 1st Floor, Chinar Heights, Model Colony
Deep Bangla Chowk, Shivajinagar, Pune-16

Date : 24.10.2020
Quote NO : SQT.20-21.2789
Kind Attn : Ajaykumar Maske
Email Id : maskeajay@gmail.com
Contact No: 9767555186

Subject : Quotation for Motorised Single Leaf Sliding Gate and Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Motorised Sliding Gate	6000	2000	1	350,000	350,000	20,000	20,000
2	Motorised Rolling Shutter	4500	5000	3	167,000	501,000	20,000	60,000
				Total		**851,000**		**20,000**
3	P&F Charges			3%		25,530		
	Total Without Taxes					876,530		20,000
	GST Extra @ 18%			18%		157,775.40		3,600
	Total With Taxes					**1,034,305**		**23,600**
4	Transportation Charges					In Client Scope		
5	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA make – Motorized Sliding Gate	
Door type	**Single Leaf Sliding Gate**
Clear Opening gate dimension	(W) 6000 x (H) 2000…in mm
Opening Direction	**Horizontal - from left to right or reverse**
Mounting Location area	Inside area
Design Pattern	Standard Tubular Design Pattern
Outer Frame Tube Sizes	72x72x3.2mm SS- 304 SQ. TUBE
INNEAR TUBE	25x25x3.2 mm SS - 304 SQ. TUBE
Gap Between Tubes	125mm
Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
Guide Rollers supporter during Gate movement	**Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate**
Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
El motor make	BFT – Italy (100% imported)
Emergency Operation	Manual after turn the switch
Operating Switch	Push Button from inside
Safety	Photocells, Flashing Light
Metal Rack	zinc plated metal rack

NIHVA Make Motorised Rolling Shutter

Sr .No.	Specification	MS Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with MS Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	On Concrete /Steel
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.7 mm
12	**Surface finish**	PU paint or Powder coated
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	
3	Electrical Supply on the site single phase/three phase points at different places.	
4	Any civil / masonry/structural work required	
5	All structure support required	
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	
7	Conduits, Cables required	

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd