**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune :**

## NIHVA Sales Quotation

**Conart Engineers Ltd.**
Gujarat

**Project, Location : Gujarat**

**Date :** 28.12.2020
**Quote NO :** SQT.20.21.2899R4
**Kind Attn :** Daxa
**Email Id :** tenders@conartengineers.com
**Contact No:** 0265-2330946

**Subject : Revised Quotation for Motorized Rolling Shutter and Insulated Rolling Shutter**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 2 |
| D. | Terms & Condtions | 3 |

**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **1.25mm MS Motorised Rolling Shutter - Direct Drive** | 4000 | 4000 | 6 | 193,000 | 1,158,000 | 15,000 | 90,000 |
| 2 | **1.25mm MS Motorised Rolling Shutter - Direct Drive** | 3000 | 3000 | 2 | 151,000 | 302,000 | 15,000 | 30,000 |
| 3 | **1.25mm MS Motorised Rolling Shutter - Direct Drive** | 3000 | 2400 | 1 | 145,000 | 145,000 | 15,000 | 15,000 |
| 4 | **1.25mm MS Motorised Rolling Shutter - Direct Drive** | 3000 | 3600 | 1 | 158,000 | 158,000 | 15,000 | 15,000 |
| 5 | **Double Wall MS Motorized Rolling Shutter with PUF Insulated - Direct Drive** | 3000 | 2925 | 1 | 225,000 | 225,000 | 15,000 | 15,000 |
| | **Total** | | | **11** | | **1,988,000** | | **165,000** |
| 6 | P&F Charges | | | 3% | | 59,640 | | |
| | **Total Without Taxes** | | | | | 2,047,640 | | 165,000 |
| | GST Extra @ 18% | | | 18% | | 368,575.20 | | 29,700 |
| | **Total With Taxes** | | | | | **2,416,215** | | **194,700** |
| 7 | Transportation Charges | | | | | Inclusive | | |
| 8 | Unloading Charges @ Site | | | | | In Client Scope | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune :**

**B) Technical Specification**

**Motorized Rolling Shutter**

| Sr .No. | Specification | MS Motorized Rolling Shutter - Direct Drive |
|---|---|---|
| 1 | **Description:** | Motorised Rolling Shutter with MS Slats with thickness of 1.25 mm. |
| 2 | **Mounting Location area** | Inside area / Outside area |
| 3 | **Mounting Surface** | Side Brackets: Optional = On Concrete /Steel & Side |
| 4 | **Curtain Panel** | The panel made of 1.0mm thick GI. |
| 5 | **Curtain panel size** | 75mm wide |
| 6 | **Curtain Profile** | Curved |
| 7 | **Bottom Profile** | M. S. Plate 100 mm x 2.5 mm thick with angle stiffener |
| 8 | **Side Guide Profile** | M.S." T" Shaped profile. |
| 9 | **Roller Shaft** | M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h |
| 10 | **Side Brackets** | MS Plate 3 mm to 10 mm thick, as per the opening dimension. |
| 11 | **Hood Cover** | Made of GI Sheet Thickness 0.9 mm GF mm |
| 12 | **Control Panel** | Push button on both side |
| 12 | **Surface finish** | Primer |
| 13 | **Drive Unit & Mounting Type** | Electric Motor - Direct Mounting - Sprocket chain arrangement – IP54 Protection(European Make ) |

**Double Wall Rolling Shutter (NIHVA Make)**



| Double Wall Rolling Shutter |
|---|
| • Thermal Insulation : Shutter infill of 20 mm PU rigid foam ensuring excellent thermal insulation |
| • Side guide Protection : Black plastic strips on the edge of the side guides protect against abrasion and ensure longevity of shutters |
| • Closing edge Safety device (only for Motorized) : Sensor controlled safety devices to monitor the bottom edge of the door. Instant stoppage and reversing on encountering any obstruction while closing . |
| • Sealing : Rubber seals are provided to reduce friction and sound, thereby ensuring a smooth door travel |
| • Accessories (Optional) : Vision panels for better visibility and light can be provided at extra cost |
| • Door Curtain : Aluminium curved slats |
| • Support Brackets : Galvanized steel |
| • Space Requirement (in mm) : Head room (S) = 675, minimum fitting depth for operator and support brackets (ET) = 450 (Space reqd for removal of cover is 2 times of cover) , Side space requirment (PS) = 210 |
| • Minimum requirement for Building Structure : Concrete = 140 mm (Min strength M10) , Steel = 5 mm, Brick work = 240 mm (Min strength 100 $kg/cm^2$ |
| • Side Guides : FS 160 A - moulded aluminium guide rails with guide channel, black plastic runner |
| • Bottom Profile : Extruded aluminium, Double skinned |
| • Seals : Lintel seal, Bottom seal made of EPDM profile |
| • Fixing Material : Tested and approved for steel, concrete, brickwork |
| • Operator : Shaft operator, Ready to fit shaft operator, Power Input - 1 phase current 0.25 kW, Protection category IP65 (jet water protected ) |
| • Control : Integrated microprocessor control along with operator, Adjustable force limit and connection cable with CEE male plug in protection category IP 44, Push button on both side. |
| • Standard accessories : Chain Hoist and Shoot Bolt - for manual door |
| • Push Button : For Automatic Door |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune :**

**C) General Conditions**

1. Installation will start after receiving of Site Readyness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr. Bhavin Jain on 8551092333** For any further Clarification /Information in this Concern.

**With Best Regards**
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd