NIHVA

NIHVA TECHNOLOGIES PVT. LTD.







Project : DRAL at Nagpur



Quotation

ASSA ABLOY

ASSA ABLOY Entrance Systems

The global leader in
door opening solutions

Quotation reference: **SQT/20-21/2880**

Date: 10th Dec 2020

SUROJ BUILDCON PVT. LTD
Bungalow No. 3, Liberty Society Phase-I
North Main Road, Koregaon Park, Pune 411 001

Kind Attn: Ms. Reema Asar
Contact No: 9810267360
Email: rasar@suroj.in

Project : DRAL at Nagpur

Dear Sir/ Ma'am,

We have the pleasure to offer you the following solution for your requirement at Nagpur for Project DRAL.

ASSA ABLOY VL3190 Megadoor with 3 sections and 2 swing up mullion

- **Hangar FAL 3: 40000 x 9400 (CWxCH) clear opening – 2 nos VL 3190**
- **Hangar MIX 4: 40000 x 9400 (CWxCH) clear opening – 1 nos VL 3190**

A. <u>OPTION : 1 PRICING – for Standard Fabric</u>

<u>Supply Price Including of Custom Duty, custom clearance and Local Transport.</u>

Sr. No	Description	Location	Price/Each in Rs	Qty in No	Total Price in INR
1	Supply & Installation of Vertical Lifting Hangar Door **40000 x 9400 mm (CW x CH)**	Hangar FAL 3	265,00,000	2	530,00,000
2	Supply of Vertical Lifting Hangar Door **40000 x 9400 mm (CW x CH)**	Hangar MIX 4	265,00,000	1	265,00,000

B. OPTION : 2 PRICING – for Insulated Fabric

Supply Price Including of Custom Duty, custom clearance and Local Transport.

Sr. No	Description	Location	Price/Each in Rs	Qty in No	Total Price in INR
1	Supply & Installation of Vertical Lifting Hangar Door **40000 x 9400 mm (CW x CH)**	Hangar FAL 3	330,00,000	2	660,00,000
2	Supply of Vertical Lifting Hangar Door **40000 x 9400 mm (CW x CH)**	Hangar MIX 4	330,00,000	1	330,00,000

General conditions of Aircraft Hangar Door :

1. Continuous uninterrupted access to any single door section or as agreed separately.
2. A clear floor area of 4 metres each side of the door leaf must be available during the curtain fitting process. The floor should be finished or if this is not possible, adequate temporary protection be made available to prevent damage to the curtain material.
3. 400 volt / 50Hz 3 phase isolator to be fitted to within 1 metre of the door main control panel. If not available at the start of installation, a temporary supply is acceptable. Any return visits to commission the doors due to permanent power not being available will be charged as appropriate.
4. A suitable structure should be available together with mullion floor pits (multiple section doors only) designed in accordance with final approval drawings issued by ASSAABLOY. Tolerances/deflections of the support structure to be in accordance with the drawings.
5. Provision of 230 Volt power supply (by others) for hand tools.
6. A dry and secure area, not in direct sunlight, is to be provided for storage of the door components.
7. Access to site between 7 am to 6 pm six days per week. If this is not possible the installation programme may require amending.

8. Any storage costs for materials due to delays outside of Mega door's control will be charged to the maincontractor.

9. The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practices. We reserve the right to extend the period accordingly.

10. Any passes required for the project, are the responsibility of the Customer and Contractor and must be available, before commencement of the installation. Any delays caused by the non-availability of passes, will be charged accordingly.

Inclusions :

1. Our proposal includes **sea freight from Sweden to Mumbai Nava Seva, Custom duty, Custom clearance, Local Transport and installation of the door leaf, guide rails, weather seals, motors, control panel.** (Please refer Exclusion)

2. A pre-installation inspection will be carried out, by our Project Manager, before our installers travel to site, so as to verify that the structural steelwork and electrical installation are as per our requirements. Our Project Manager will also check that the installation equipment and facilities are ready for installers.

Exclusions :

The following items are not within our scope of works and are to be provided by others at no cost to NIHVA - ASSAABLOY.

1. A compliance statement, with supporting documentation, which states that the building deflections are in accordance with the criteria, as agreed between our design department and the steelwork contractor (to be done by main contractor).

2. A load test on all points in the door opening, as specified by our design department. A load test report is to be submitted to our Project Manager after the test is completed (to be done by main contractor).

3. Any civil work required for Structural Support (to be done by civil contractor)

4. Mullion pits, Mullion Hoists, Mullion pit frame, Mullion plates, Wind Brase, Mullion support plates with holes as per our design (to be done by civil contractor).

5. Conduits and Cable trays from the control panel locations to the door distribution boxes, mullion hoist units and door hoist units be provided. (to be done by electrical contractor).These are to be installed prior to the commencement of door installation.

6. Any passes required for the project, are the responsibility of the Contractor and must be available, before commencement of the installation. Any delays caused by the non-availability of passes, will be charged accordingly.

7. Litfing equipments required during Installation will be in Client Scope.

8. The structural support steel for the door head, jambs, motor plates, mullion wind bracing, and mullion motors.

9. A 400/230 power supply (permanent or temporary) must be provided (FOC) by the main Contractor during the installation of the door for power tools and testing of the door sections during erection.

10. A safe storage / pre-assembly area for the door materials (by main contractor).

11. Any additional tests or certification, which are not within our scope of works but may be required by the Consultant or Client, these will be carried out or provided, subject to the actual requirements but will be at additional cost (by main contractor).

12. Please note that the control panels, motors and electrical wiring are in full compliance with Swedish regulations and specifications, any variations due to specific requirements for India must be notified to us at the time of ordering and may be subject to an increase in the price. Any variations notified to us, after material procurement, will be charged accordingly and may lead to production delays.

Terms &Conditions:

Price : Ex works Nagpur

Payment : 80% advance along with Confirmed Purchase Order and Balance before Dispatch.
OR 100% Irrovacable LC along with confirm purchase order.

P & F Charges : @3% of Total Value

Transport : Extra at Actual

GST : @18% extra on Supply & installation

Validity : 45 days

Delivery : 22-23 weeks from the date of receipt of confirmed order, advance payment, drawing approval

Insurance : Extra as applicable

Warranty : 12 months from date of Supply

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

Compensation clause

Please note that in the event the buyer cancels an order, after the order is confirmed to us, it is binding to the buyer to pay NIHVA - ASSAABLOY a compensation of 25% of order value.

ASSA ABLOY Entrance Systems

One partner for all your automatic entrances

ASSA ABLOY Entrance Systems comprise world-leading products, maintenance programs and modernization services, ensuring total solutions for efficient flow of people, goods and vehicles. With comprehensive entrance solutions for the front, back and interior of your building, we put every automatic door equipment or service you need under one roof.

The perfect match for your building
ASSA ABLOY Entrance Systems' extensive product range, expert application knowledge and maintenance programs provide optimal entrance solutions for all needs and any demands in manufacturing, distribution & logistics, retail, healthcare, transportation, hospitality, private services, public services, mining and air & sea, and more.

Sustainable Solutions
We design, manufacture and service automatic entrance solutions that help you reach your sustainability goals for energy savings and minimal environmental impact.

Leading product brands backed by dedicated specialists
With our three specialized business areas; Pedestrian Door Solutions, Industrial Door & Docking Solutions and High-Performance Door Solutions, we offer market-leading product brands and a global service organization. With more than a century of aggregated engineering experience and application expertise ASSA ABLOY Entrance Systems is your ideal business partner to provide, maintain and modernize all of your automatic entrances.



Pedestrian Door Solutions

- swing doors
- sliding doors
- revolving doors



Industrial Door and Docking Solutions

- industrial doors
- complete docking systems
- hangar doors



High-Performance Door Solutions

- high speed roll doors
- doors for special applications such as clean rooms, machine protection and food processing