


* All sizes / dimensions shown in drawings to be verified by vendor at site prior to proceeding for production.
* All materials / finishes shown in shop drawings are subject to MAS / sample approved by DIAL.






Detail not clear




Detail not clear




Add Title of Detail and mention Scale

Door leaf is not shown for clarification

Add title for part plan scale?





Detail not clear
Add title with callout

NOT INCLUDED IN DOOR SUPPLY:

1. Design and supply of all door supporting structural components.
2. Design and supply of all closure between door and adjacent steel.
3. Door jambs adjustable for overall door width and true to plumb.
4. Paint job after completed door installation.
5. Any frameworks being provided by ASSA ABLOY will be clearly indicated as "by ASSA ABLOY".

REQUIREMENTS ON BUILDING:

6. Door head support must be straight within 1/600 of span in the in/out direction and free from protrusions of any kind.
7. For a single door leaf, door head support should be horizontal and straight within 1/600 of span at distributed full door load.
8. Door side jambs must be smooth, straight and parallel, out of plumb must not exceed 2mm/m (total deviation at full length 5 mm) in any direction.
9. Any footings at bottom of jamb columns must not interfere with installation of guide rails at floor level.
10. At time of installation, finished floor, free from obstructions, out to a distance of 2 m on each side of door centreline must be available.
11. Header box must be accessible from both sides during installation.

DOOR PROPERTIES:

12. The door is designed to withstand a differential pressure of 1.15kPa x 1.5 FOS.
13. Color of door fabric: Please specify
14. Side profiles
15. Metal trim: motor side


ELECTRICAL:


16. One main control panel provided of PLC type.
17. Audible and visual alarm
18. Back-up power switch
19. Safety edge
20. Approx. size of main control panel: WxHxD (500mm x 600mmx250 mm),
21. Power: 2.7kW
22. Nom. current: 6.4A
23. (max. allowed voltage drop at start: 5%)

BELT HOIST UNITS:


SK 873.1-100L/4 Z dual brake

* Add callout for all details to identify location of detail.
* Mention scale for all details shown in shop drawings
* Add cross section for both (ope and closed condition on roll up fabric.
* specify all materials shown in drawings





Force by differential pressure transferred to guide rail at each intermediate position.
F=4.7 kN



Load on header box attachment (each screw), due to wind load and door weight

ELECTRICAL:

① GA drawing along with wiring diagram/SLD for proposed Rolling shutter control panel and push button to be furnished by vendor.

② Location of Rolling shutter control box, remote push button station, limit switch etc shall be marked in approved Architectural Plan & Elevation drawings for all high speed rolling shutter.

Add key plan of building for location marking.

KEY PLAN (NOT TO SCALE)

NOTE:
1. 340 MM RCC COLUMN REQUIRED FOR GUIDE MOUNTING.
IF RCC COLUMN NOT AVAILABLE THEN WE WILL REQUIRE MS STRUCTURE FOR THE SAME.

Add Architectural drawing reference number

LEGENDS :

DOOR DRAWING

SHOP DRAWING

REV.NO.	DESCRIPTION	DESIGNED	DRAWN	CHECKED	APPROVED
A	Issued for approval				


CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE
ARCHITECTURE			HVAC			CIVIL		
CIVIL & STRUCTURAL			FPS			GEOTECH.		
ELECTRICAL			PIPING			ASPHALT DESIGN		
ELV SYSTEM			PHE			INTERFACE		

CLIENT : DELHI INTERNATIONAL AIRPORT LIMITED
PROJECT : DIAL AIRPORT DEVELOPMENT WORKS
CONCEPT :
PROJECT CONSULTANT : Engineering Design and Research Center L&T Construction
INSTALLED AND SUPPLIED BY : ASSA TECHNOLOGIES PVT LTD


JOB No : JOBNO.	NAME	SIGN	DATE
DSGN	G.J.P		02.10.2021
DRWN	G.J.P		02.10.2021
CHKD	A.K.		02.10.2021
APPD	V.Z.		02.10.2021


TITLE: ARFF4 MEGADOOR 8760 X 5400 (RS7)
SCALE 1:1
DRAWING No. NIHVA/21-22/0244/MD/74147
PROJECTION FIRST ANGLE
SIZE A3
REV. A
RELEASED FOR: ☐ PRELIMINARY ☐ TENDER ☐ INFORMATION ☑ APPROVAL ☐ CONSTRUCTION


Take shop drawing number and mention




Interior view, Door closed








Force by differential pressure transferred to guide rail at each intermediate position.
F= 2.7 kN



Load on header box attachment (each screw), due to wind load and door weight



Detail not clear

NOT INCLUDED IN DOOR SUPPLY:

1. Design and supply of all door supporting structural components.
2. Design and supply of all closure between door and adjacent steel.
3. Door jambs adjustable for overall door width and true to plumb.
4. Paint job after completed door installation.
5. Any frameworks being provided by ASSA ABLOY will be clearly indicated as "by ASSA ABLOY".

REQUIREMENTS ON BUILDING:

6. Door head support must be straight within 1/600 of span in the in/out direction and free from protrusions of any kind.
7. For a single door leaf, door head support should be horizontal and straight within 1/600 of span at distributed full door load.
8. Door side jambs must be smooth, straight and parallel, out of plumb must not exceed 2mm/m (total deviation at full length 5 mm) in any direction.
9. Any footings at bottom of jamb columns must not interfere with installation of guide rails at floor level.
10. At time of installation, finished floor, free from obstructions, out to a distance of 2 m on each side of door centreline must be available.
11. Header box must be accessible from both sides during installation.

DOOR PROPERTIES:

12. The door is designed to withstand a differential pressure of 1.15kPa X 1.5 FOS.
13. Metal trim: motor side
14. Side profiles
15. Fabric colour: Please specify

ELECTRICAL:


14. One main control panel provided of PLC type.
15. Audible and visual alarm
16. Safety edge
17. Back-up power switch
18. Approx. size of main control panel: WxHxD (500mm x 600mmx250 mm),
19. Power: 1.4kW
20. Nom. current: 3.3A
21. (max. allowed voltage drop at start: 5%)


BELT HOIST UNITS:
Sk 773.1-90S/4 Z dual brake

ELECTRICAL:

(3) Vendor shop drawing shall include the conduit / containment routing for power and control cables from Rolling shutter control panel to Motor units, push buttons and other field devices.

(4) One no. 16A 4P isolator has been proposed for each high speed rolling shutter by electrical team. for mains power. Vendor to confirm incomer isolator/breaker rating and the max. incoming cable size from isolator to Rolling shutter control panel.





Refer general comments provided on first drawing.

KEY PLAN (NOT TO SCALE)

NOTE:
1. 275 MM RCC COLUMN REQUIRED FOR GUIDE MOUNTING.
IF RCC COLUMN NOT AVAILABLE THEN WE WILL REQUIRE MS STRUCTURE FOR THE SAME.

LEGENDS :

DOOR DRAWING

REVISIONS							
REVNO.	DESCRIPTION			DESIGNED	DRAWN	CHECKED	APPROVED

CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE
ARCHITECTURE			HVAC			GIS		
CIVIL & STRUCTURAL			FPS			SECURITY		
ELECTRICAL			PPHO			AIRPORT SYSTEMS		
ELV SYSTEM			PHE			INTERFACE		

DELHI INDIRA GANDHI INTERNATIONAL AIRPORT | GMR | L&T Construction

CLIENT : DELHI INTERNATIONAL AIRPORT LIMITED

PROJECT : DIAL GMIA REDEVELOPMENT AIRPORT PHASE-3A DEVELOPMENT WORKS

CONCEPT :

PROJECT CONSULTANT: Engineering Design and Research Center L&T Construction (EDRC)

DETAILED AND SUPPLIED BY: GMR TECHNOLOGIES PVT LTD

JOB No : JOBNO.

	NAME	SIGN	DATE
DRGN	G.L.P		02.10.2021
DRWN	G.L.P		02.10.2021
CHKD	A.K.		02.10.2021
APPD	V.Z.		02.10.2021

TITLE: ARFF4 MEGADOOR 5800 X 5400 (RS 6)


SCALE: NTS

DRAWING No. NIHVA/21-22/0243/MD/74148


PROJECTION: FIRST ANGLE


SIZE: A3 | REV: 0


RELEASED FOR: ☐ PRELIMINARY ☐ TENDER ☐ INFORMATION ☑ APPROVAL ☐ CONSTRUCTION




Interior view, Door closed










Door leaf is not shown for clarification










Force by differential pressure transferred to guide rail at each intermediate position.
F=4.7 kN



Load on header box attachment (each screw), due to wind load and door weight

NOT INCLUDED IN DOOR SUPPLY:

1. Design and supply of all door supporting structural components.
2. Design and supply of all closure between door and adjacent steel.
3. Door jambs adjustable for overall door width and true to plumb.
4. Paint job after completed door installation.
5. Any frameworks being provided by ASSA ABLOY will be clearly indicated as "by ASSA ABLOY".

REQUIREMENTS ON BUILDING:

6. Door head support must be straight within 1/600 of span in the in/out direction and free from protrusions of any kind.
7. For a single door leaf, door head support should be horizontal and straight within 1/600 of span at distributed full door load.
8. Door side jambs must be smooth, straight and parallel, out of plumb must not exceed 2mm/m (total deviation at full length 5 mm) in any direction.
9. Any footings at bottom of jamb columns must not interfere with installation of guide rails at floor level.
10. At time of installation, finished floor, free from obstructions, out to a distance of 2 m on each side of door centreline must be available.
11. Header box must be accessible from both sides during installation.

DOOR PROPERTIES:

12. The door is designed to withstand a differential pressure of 1.15kPa x 1.5 fos.
13. Color of door fabric: Please specify
14. Side profiles
15. Metal trim: motor side

ELECTRICAL:

16. One main control panel provided of PLC type.
17. Audible and visual alarm
18. Back-up power switch
19. Safety edge
20. Approx. size of main control panel: WxHxD (500mm x 600mmx250 mm),
21. Power: 2.7kW
22. Nom. current: 6.4A
23. (max. allowed voltage drop at start: 5%)

BELT HOIST UNITS:

SK 873.1-100L/4 Z dual brake

Refer general comments provided on first drawing.

KEY PLAN (NOT TO SCALE)

NOTE:
1. 340 MM RCC COLUMN REQUIRED FOR GUIDE MOUNTING.
IF RCC COLUMN NOT AVAILABLE THEN WE WILL REQUIRE MS STRUCTURE FOR THE SAME.

LEGENDS :

~~DOOR DRAWING~~

REV.NO.	DESCRIPTION	DESIGNED	DRAWN	CHECKED	APPROVED

CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE
ARCHITECTURE			HVAC			C&S		
CIVIL & STRUCTURAL			FPS			MECHANICAL		
ELECTRICAL			PIPING			AIRPORT SYSTEMS		
ELV SYSTEM			PHE			INTERFACE		

DELHI INDIRA GANDHI INTERNATIONAL AIRPORT · GMR · L&T Construction

CLIENT : DELHI INTERNATIONAL AIRPORT LIMITED.

PROJECT : NEW DOMESTIC AIRPORT PHASE-3A DEVELOPMENT WORKS

CONCEPT :

PROJECT CONSULTANT: Engineering Design and Research Center L&T Construction (EDRC)

DESIGNED AND SUPPLIED BY: NIHVA TECHNOLOGIES PVT LTD

JOB No : JOBNO.

	NAME	SIGN	DATE
DSGN	G.L.P		02.10.2021
DRWN	G.L.P		02.10.2021
CHKD	A.K.		02.10.2021
APPD	V.Z.		02.10.2021

TITLE: ARFF5 MEGADOOR 8760 X 4988 (RS7)

SCALE: 1:1

DRAWING No. NIHVA/21-22/0244/MD/74414


SHEET

PROJECTION: FIRST ANGLE


SIZE: A3


REV: 0

RELEASED FOR: ☐ PRELIMINARY ☐ TENDER ☐ INFORMATION ☑ APPROVAL ☐ CONSTRUCTION



Interior view, Door closed





NOT INCLUDED IN DOOR SUPPLY:

1. Design and supply of all door supporting structural components.
2. Design and supply of all closure between door and adjacent steel.
3. Door jambs adjustable for overall door width and true to plumb.
4. Paint job after completed door installation.
5. Any frameworks being provided by ASSA ABLOY will be clearly indicated as "by ASSA ABLOY".

REQUIREMENTS ON BUILDING:

6. Door head support must be straight within 1/600 of span in the in/out direction and free from protrusions of any kind.
7. For a single door leaf, door head support should be horizontal and straight within 1/600 of span at distributed full door load.
8. Door side jambs must be smooth, straight and parallel, out of plumb must not exceed 2mm/m (total deviation at full length 5 mm) in any direction.
9. Any footings at bottom of jamb columns must not interfere with installation of guide rails at floor level.
10. At time of installation, finished floor, free from obstructions, out to a distance of 2 m on each side of door centreline must be available.
11. Header box must be accessible from both sides during installation.


DOOR PROPERTIES:

12. The door is designed to withstand a differential pressure of 1.15kPa x 1.5 fos.
13. Metal trim: motor side
14. Side profiles
15. Fabric colour: Please specify


ELECTRICAL:

14. One main control panel provided of PLC type.
15. Audible and visual alarm
16. Safety edge
17. Back-up power switch
18. Approx. size of main control panel: WxHxD (500mm x 600mm x 250 mm),
19. Power: 1.4kW
20. Nom. current: 3.3A
21. (max. allowed voltage drop at start: 5%)


BELT HOIST UNITS:
Sk 773.1-90S/4 Z dual brake




Force by differential pressure transferred to guide rail at each intermediate position.
F= 2.7 kN



Load on header box attachment (each screw), due to wind load and door weight





Refer general comments provided on first drawing.

KEY PLAN (NOT TO SCALE)

NOTE:
1. 275 MM RCC COLUMN REQUIRED FOR GUIDE MOUNTING.
IF RCC COLUMN NOT AVAILABLE THEN WE WILL REQUIRE MS STRUCTURE FOR THE SAME.

LEGENDS :

DOOR DRAWING

REV.NO.	DESCRIPTION	DESIGNED	DRAWN	CHECKED	APPROVED

CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE
ARCHITECTURE			HVAC			CSS		
CIVIL & STRUCTURAL			FPS			GEOTECH.		
ELECTRICAL			PHE			ARCHIT. REVIEW		
ELV SYSTEM						INTERFACE		

DELHI INDIRA GANDHI INTERNATIONAL AIRPORT — GMR — L&T Construction

CLIENT : M/S HERRENKNECHT AIRPORT GMBH.

PROJECT : M/S GMR HERRENKNECHT AIRPORT PHASE-3A DEVELOPMENT WORKS

CONCEPT :

PROJECT CONSULTANT: Engineering Design and Research Center (EDRC), L&T Construction

DESIGNED AND SUPPLIED BY: GMR TECHNOLOGIES PVT LTD

JOB No : JOBNO.

	NAME	SIGN	DATE
DSGN	G.L.P		02.10.2021
DRWN	G.L.P		02.10.2021
CHKD	A.K.		02.10.2021
APPD	V.Z.		02.10.2021

TITLE: ARFF5 MEGADOOR 5800 X 5360 (RS6)

SCALE: 1:1

DRAWING No. NIHVA/21-22/0245/MD/74413

PROJECTION: FIRST ANGLE

SIZE: A3 REV: 0

RELEASED FOR: ☐ PRELIMINARY ☐ TENDER ☐ INFORMATION ☑ APPROVAL ☐ CONSTRUCTION