NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

AAK Kamani Pvt. Ltd.
Honad Village, Post Sajgaon,
Takai Aadoshi Road, Tal. Khalapur
Khopoli, Dist. Raigad-410203

Date : 26.06.2021
Quote NO : SQT.20.21.2651R
Kind Attn : Mr. Ajay Mahadik
Email Id : ajay.mahadik@aakkamani.com
Contact No: 9619852142

Subject : Revised Quotation for Sectional Door, High Speed Door & Dock Shelter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2, 3, 4
C.	General Conditions	5
D.	Terms & Condtions	5

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	High Speed Door (NIHVA Make)	3000	2800	2	325,000	650,000	15,000	30,000
2	Sectional Door	2500	3000	1	195,000	195,000	15,000	15,000
3	Dock Shelter	3400	4000	2	95,000	190,000	15,000	30,000
			Total	**5**		**1,035,000**		**75,000**
			P&F Charges	3%		**31,050**		
			Total Without Taxes			**1,066,050**		**75,000**
			GST Extra @ 18%	18%		191,889		13,500
			Total With Taxes			**1,257,939**		**88,500**
			Total Supply + Installation with Taxes					**1,346,439**
4	Transportation Charges					**Extra at actual**		
5	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA Sectional Door

Sr. No	Description	Specification
1	Model No	ASSA ABLOY OH1042P
2	Opening Direction & Mounting	Standard
3	Opening/Closing Speed	CDM9 0,28 m/s
4	Door Material	Steel
5	Panel Thickness	42 mm Square Grid, steel sheet
6	Filling	CFC-free polyurethane
7	Door sealent	All door sealants made of EPDM rubber, temperature resistant -30/+70
8	Water Penetration	EN 12425 class 3
9	Air Permealibity	EN12426 class 3
10	Thermal Transittance	EN 12428 1.10W /m2K
11	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
12	Door saftey	Doors equiped with spring break device
13	Incase of Power failuer	Doors to be equiped with quick release fuction
14	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
15	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft
16	Emergency Operation	by Disengagement rope manual
17	Operating Switch	Up/Down Keypad + stopbutton
18	Locks : Lock bolt	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible from the outside.
19	Environmental Green Product Declaration Certification	As per ISO 14025 and EN 15804

HIGH SPEED PVC ROLL UP DOOR

- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing
- Can be equipped with full vision PVC curtain
- Modular Interchaegable panels permit to replace worn & damged panels

Sr. No	Description	Specifications
1	Use	External Door
2	Speed	Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking
3	Opening speed	3 m/s
4	Closing speed	0.8 m/s
5	Control Panel	4 Push Button operated
6	Security Features	EN 13241-1 Standard
7	Resistance to wind load	EN12424 upto class 2
8	Curtain	Fabric Transparent PVC section
9	Guide Material	Aluminum
10	Hood Cover	GI
11	Motor Cover	GI
12	Operator & Control	German Make Motor , VFD
13	Connecting Voltage	220V , 1Ph , N
14	Open-Stop-Close Button	Standarad
15	Protection Category	IP 54 / IP 65
16	Power Consumption	0.75 kw Motor
17	Emergency Off Button	Standard
18	Closing Zone Monitoring	Optical Safety edge
19	External Route Monitoring	Photocell
20	Emergency Opening	Crank Handle
21	Pulll cord Cable and Vision Window	Included

Dock Shelter

Sr .No.	Specification	Dock Shelter
1	**Top Curtain**	1000 mm
2	**Side Curtain**	600 mm
3	**Curtain colour**	Black
4	**Parking Guides**	White, Yellow
5	**Wall Fixings**	Concrete, Sandwich light Concrete, Load house cavity, insulated panel
6	**Top & Side Curtains**	Double Layer High Quality Polyester
7	**Thickness**	3.0 mm
8	**Weight**	Approx 3400 g/m2

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope
8	Steel structure for Dock House & Sectional Door	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9 - 10 weeks for High Speed Doors & 4-5 weeks for Dock shelter ,sectional door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Shrikant Mirkute on 8551098333**

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd