WORK ORDER

Client:			**PO Number:**	22PO0000432	**W. O. No-**	SO/22-23/006
PARC Robotic Systems Pvt.Ltd			**PO Dated :**	20-04-2022	**W. O. Date**	21-04-2022
Address:			**PO Received Date:**	21-04-2022	**Sales Co ordinator**	Shailesh Bhoir
Phase 4, Plot No. PAP-A-9/2, Chakan Industrial Area, NIGHOJE,Taluka Khed, Pune Pune MH 410501			**Ref. Quotation:**	SQA.21.22.0474R1	**Front Sales Person**	Yogesh Kulkarni

Dispatch Address:

Phase 4, Plot No. PAP-A-9/2, Chakan Industrial Area,
NIGHOJE,Taluka Khed, Pune Pune MH 410501

A	**Technical Terms:**							
Sr. No	**Description of Goods**	**Technical Details**	**UOM**	**Qty.**	**Supply Rate**	**Installation Rate**	**Total Amount**	**Dwg. Approval Status**
1	**ASSA ABLOY Machine Protection Door RP300 - Without MCC Vector Control (W) 1500 mm X (H) 1900 mm**	**Door version: Vertical Rapid Roller Door for machine protection. Side Frames : Aluminum anodized two parts, to have easy access to switches and service. Door blade : PVC material transparent with reinforcement stripes silicone-free in red (RAL 3002). Bottom beam : Aluminium anodized. Drive unit : Drive unit IP 55, either RH or LH as an option, with control cable (standard length = height of door) Opening / closing speed : Approx. max. 2,0 / 1,2 m/s Control system : (Not required as per client request) Power suppy : 3L(N)PE 380/400/415/440/460 and 480 V, 50/60 Hz Safety features : Safety edge with cable chain integrated in side frames, door line photocell (Transmitter / Receiver) inside side frames, emergency crank and mechanical drop-down protection. Safety limit switch : 1 Schmersal safety limit switch PL e EN ISO 13849-1, SIL 3 EN 62061 on drive side integrated in the side frame to save space.**	**Nos**	**2**				**Pending**
						Total		**-**

Non standard items/extra requirement, if any:	**Material Test Certificates, Pre Dispatch Inspection Reports**

B	**Commerical Terms:**			
1	**Payment Terms:**	**20% Advance+70 % Along with Taxes At The Time of Dispatch+10 % Before Commissioning At PARC/Customer**		
2A	**Delivery Date as per PO:**	**10 - 12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.**	**2B. Required Delivery Date:**	
3A	**Transportation Scope:**	**In Client Scope**	**3B. Transportation Charges:**	
4	**P&F Charges:**	**NIL**		
5A	**Loading Scope:**	**In NIHVA Scope**	**5B. Loading Charges:**	
6A	**Unloading Scope:**	**In Client Scope**	**6B. Unloading Charges:**	
7A	**Lifting Equipments Scope:**	**In Client Scope**	**7B. Available Lifting Equipments:**	
8	**Warranty:**	**12 Months from date of Supply**		
9A	**Height arrangement Scope:**	**In Client Scope**	**9B. Available Equipments for working at Site:**	
10	**Electricity Supply:**	**In Client Scope**		
11	**GST:**	**18%**		
12A	**Installation Scope:**	**In Client Scope**	**12B. Installation required date:**	
13	**Mode of import:**	**NA**		
14	**HSS:**	**NA**		
15	**Documentation Required:**	**Standard Handover Documents**		
16A	**Total site visits required:**		**16B. Site visit charges:**	

Certified that the above work order finalised in presence of:

AGM	SALES		Operation	PROJECT	DESIGN	Date & Time
A.K.	V.T.		KBM	S.M.	Sujata B.	21-04-2022