NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Ferrero India Pvt Ltd
IMSOFER Division (Unit I) ,Plot No. F-13,
M.I.D.C., Baramati,
Maharashtra, India

Date : 08.05.2021
Quote NO : SQT.20.21.2978R6
Kind Attn : Mr.Narayan jahagirdar
Email Id : narayan.jahagirdar@ferrero.com
Contact No: 02112662427

Subject : Revised Quotation for Assa Abloy Make HSD RR300+ALU (High Sea Sale)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer -Price is High Sea Sale (Custom Duty + Custom Clearance + Local Transport will be in Ferrero Scope)

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	ASSA ABLOY Make RR300+Alu_Way to molding line 3 process area	1950	3912	1	632,000	632,000	20,000	20,000
2	ASSA ABLOY Make RR300+Alu_Kinder joy tunnel	2504	3995	1	646,000	646,000	20,000	20,000
3	ASSA ABLOY Make RR300+Alu_KSBC Packing	2997	3915	1	656,000	656,000	20,000	20,000
4	ASSA ABLOY Make RR300+Alu_Rocher Packing	1960	2515	1	618,000	618,000	20,000	20,000
5	ASSA ABLOY Make RR300+Alu_Kinder joy Packing	2848	3683	1	656,000	656,000	20,000	20,000
6	ASSA ABLOY Make RR300+Alu_Scrap tunnel	2194	3481	1	632,000	632,000	20,000	20,000
7	ASSA ABLOY Make RR300+Alu_Tunnel way to time office	2400	2615	1	627,000	627,000	20,000	20,000
	Total			**7**		**4,467,000**		**140,000**
	P&F Charges			3%		**134,010**		
	Total Without Taxes					**4,601,010**		**140,000**
	GST Extra @ 18%			0%		-		-
	Total With Taxes					**4,601,010**		**140,000**
	Transportation Charges					**Extra at actual**		
	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

ASSA ABLOY Make RR300+Alu

Sr. No	Specification	ASSA ABLOY Make Rapid Roll Up Door RR300+Alu
1	**Description**	Flexiable High Performance Door , Opening in vertical direction for interior use in wind protected area
2	**Side Frames**	Made of Aluminium
3	**Door Curtain**	Made of transparent PVC with Fabric reinforcement stripes ultramarine(similar to RAL 5002) or red (similar to RAL 3002).
4	**Top Roll**	Made of Anodized Aluminium
5	**Opening / Closing Speed**	up to max. 1.2 / 1.2 m/s.
6	**Wind load resistance**	class 1 (EN 12424) up to DH = 3500 mm, class 0 (EN 12424 at DH> 3500 mm
7	**Control System**	MCC Vector Control
8	**Drive unit:**	Hollow shaft gear motor.
9	**Bottom profile**	anodized aluminium.
10	**Protection**	IP 55
11	**Hood Cover**	Included
12	**Motor Cover**	Included
13	**Push Button for the both side**	Included
14	**Safety:**	Electrical safety contact edge
		Evaluation via integrated cable chain
		Door line photocell in the side frames
		Drop down protection by integrated balancing system
15	**Additional Safety**	Additional Safety Box & Button for Control Panel

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

5 Price is High Sea Sale (Custom Duty + Custom Clearance + Local Transport will be in Ferrero Scope)

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : CIF Mumbai

Delivery : 10 - 12 Weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Vijay Tarak on 8551093333**

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd