NIHVA TECHNOLOGIES

Weight Estimation Sheet

CLIENT	Unipack-Supa							DATE	1/8/2024
PROJECT	Sliding Gate							LOCATION-	Pune
FINISH SIZE	3.05M*2.13M								
	Sizes (In mm)								
Description	Material Grade	Sp.Gravity	Dia	Width	Height	Thickness	Length	QUANTITY	WEIGHT (KG)
A.Tube-Outer Frame	MS	7.85		100	50	2	13560	1	62.2
B.Tube- Vertical Support	MS	7.85		100	50	2	2030	3	27.9
C.Tube- Vertical Support	MS	7.85		50	50	1.5	2030	21	97.4
D. Sheet (at front side only)	MS	7.85			550	1	4650	1	22.0
Post ISMC 100	MS	7.85					2400	10	240.0
MS BAR (in metre)	MS	7.85	16				9.5	1	15.3
IF ISMC 125 IN OUR SCOPE THEN(in metre)	MS	7.85					9.5	1	120.7
							Weight For Single Quantity		585.4
							Weight For Required Quantity	1	585.4
							Weight Including Safety Factor	1.2	702.5

Motor=600/1000 kg

Prepared by
Jayesh Shinde

NIHVA TECHNOLOGIES

Weight Estimation Sheet

CLIENT	Unipack-Supa							DATE	1/8/2024
PROJECT	Sliding Gate							LOCATION-	Pune
FINISH SIZE	9.15M*2.13M								
	Sizes (In mm)								
Description	Material Grade	Sp.Gravity	Dia	Width	Height	Thickness	Length	QUANTITY	WEIGHT (KG)
A.Tube-Outer Frame	MS	7.85		100	50	2	25760	1	118.1
B.Tube- Vertical Support	MS	7.85		100	50	2	2030	6	55.8
C.Tube- Vertical Support	MS	7.85		50	50	1.5	2030	53	245.8
D. Sheet(At front side only)	MS	7.85			550	1	10750	1	32.0
Post ISMC 100	MS	7.85					2400	10	240.0
MS BAR (in metre)	MS	7.85	16				22	1	34.0
IF ISMC 125 IN OUR SCOPE THEN(in metre)	MS	7.85					22	1	279.4
							Weight For Single Quantity		1005.1
							Weight For Required Quantity	1	1005.1
							Weight Including Safety Factor	1.2	1206.1

Motor= 1000 kg

Prepared by
Jayesh Shinde