PHP SOLUTIONS

TECHNICAL REQUIREMENTS SHEET - NIHVA - RICE PACKAGING MACHINE				
SR NO	ITEMS	Nihva	PHP Remark	
1	CONTROL VALVE	SS316	SS316 OK	OK
2	WEIGHING HOPPER	SS316	SS316 OK	OK
3	DISCHARGE HOPPER	SS316	SS316 OK	OK
4	BAG CLAMPING PNEUMATICS	ALUMINIUM	ALUMINIUM OK	OK
5	Load Cells	Alluminium	Alluminium OK	OK
6	SUPPORT STRUCTURE	MS POWDER COATED	MS POWDER COATED OK	OK
7	2 NEEDLE 4 THREAD STTITCHING MACHINE	MS - GABBAR MAKE	OK	OK
8	Belt make	DERCO	OK	OK
9	Belt type	PVC BELT food grade	OK	OK
10	Gear motor	Bonfiglioli	OK	OK
11	Idler Rollers	Nihva	OK	ok
12	Transmission Chain	TI – Diamond	OK	N/A
13	Transmission 'V' Belts	Fenner/Gates	OK	N/A
14	Drive & Tail Pulley	Should be Crowned	OK	N/A
15	Bearing/Pillow Blocks	SKF/NTN/FAG	SKF Food Grade	OK
16	Modular Belts	Eurobelt/Intralox	Intralox	N/A
17	Belt conveyor rollers	MS plated	OK	OK
18	Aux. Relay/24V DC relay	Siemens	Siemens only	OK
19	Power Cables	Finolex, Polycab, Lapp	Polycab	OK
20	Control Panel, Boxes, Consoles	Local make MS powder coated	OK	OK
21	MCB & MCCB	SCHNEIDER	Siemens only	OK

NIHVA TECHNOLOGIES PVT. LTD. ★ PUNE ★

PHP Solutions NASHIK

Flat No.:501,Yashlaxmi Blossom Apartment,
Balwant Nagar, Anandwali, Gangapur Road,
Nashik-422013, Maharashtra (India)

M : +91 9823144624 | +91 8600426262
W : www.phpsolutions.in | E : info@phpsolutions.in

22	Over Load Relay	SCHNEIDER	Siemens only	ok
23	Power Contractor	SCHNEIDER	Siemens only	ok
24	MCCB/ Main Incomer	SCHNEIDER	Siemens only	ok
25	Terminals	COONECTWELL	OK	ok
26	Pushbuttons illuminated	Tecknic	Siemens OK	ok
27	Emergency Push button	Tecknic	Siemens OK	ok
28	16 port Ethernet switch	D-Link	OK	N/A
29	Profibus cable	Siemens	Siemens only	N/A
30	Ethernet cable	Finolex / Polycab / Lapp	Polycab	N/A
31	PLC	Siemens	Siemens only	ok
32	Sensors	P&F	OK	ok
33	Load Cells	Thames side i.e Thames	OK	ok
34	Actuators	Techno/SMC/FESTO	SMC/Festo only	ok
35	Control Panel Accessories	Schneider	Siemens only	ok
36	Belt type	PVC BELT food grade	Jointless Belt PVC Food Grade is required	ok
37	Finishing	Mirror/Matte	OK	ok
38	Main Units of the machine	Simplex Bagging Machine, Stitching Conveyor, Telescopic Stitching stand & Heavy duty gabbar machine, Bag Gripper Unit, Printer Stand	OK	ok

Additional Note: 'Nihva' will be solely responsible for the performance of the machine with the changed parameters like height, internal design, pneumatic slide gates, etc. of the machine from your end.

PHP Solutions NASHIK

NIHVA TECHNOLOGIES PVT. LTD. * PUNE *

General Documentation and Regulatory Requirements

A. STATUTORY / REGULATORY REQUIREMENT & STANDARD

1. The process equipment design, fabrication, assembly, installation and operation shall be in accordance with cGMP standards and shall be equipped with all the necessary documentation files for FDA/FSSAI and Indian regulatory authority inspection suitable for the Pharmaceutical and Natural Product industry. N/A

2. Pressure based equipment's shall conform to ASME and Indian regulatory requirements N/A

3. Final product equipment's shall comply with ASME BPE 2016 please specify

4. All elastomers & gaskets shall be made up of FDA/FSSAI approved material. ok

5. The design must be hygienic and suitable for cleaning, maintenance & operationally Feasible. ok

B. DOCUMENTATION

Supplier shall provide the following documentation in Soft Copy & Hard Copy whichever is applicable to the equipment:

1. GA Drawings in AutoCAD, PDF ok

2. Design Specifications What specification required.

3. FAT/SAT Protocols ok

4. As built of equipment drawings with technical specifications (Material, surface finish, wall thickness, pressure rating, etc.) in DWG format ok

5. General manufacturing and maintenance file Maintenance Manual will provide

6. Pressure and temperature profile test N/A

7. Material certificates, Food grade certificates in Vendor & Sub Vendor's letter head, MOC be suitable for CIP, Caustic Chemicals, etc., Food Contact Surface List ok

8. Shelf Life Certificate of material, Filters' Certificates along with rating & shelf life, cleaning procedure of filters N/A

9. COA Report & MSDS of lubricants N/A

10. Calibration certificates for Pressure, Temperature, proximity sensors/ probes/ gauges N/A

11. Passivation report N/A

12. Welder Qualifications N/A

13. Weld standard (ASTM etc.) N/A

NIHVA TECHNOLOGIES PVT. LTD. * PUNE *

PHP Solutions NASHIK

14. Electric motor catalogue ok

15. Recommended spare parts list ok

16. List of bought out items ok

17. Maintenance & Operation manual, Troubleshoot manuals, Sub vendor's machine manuals, maintenance checklists, Lubrication checklists and details, ok

18. Utility details ok

19. Safety precautions during installing, handling & transit ok

20. Prohibited chemicals & maximum allowed concentrations of usable chemicals, with NSF Certificate N/A

21. No of hours of continuous / intermittent working per day ok

22. SOP for operating the all equipment ok

23. Particulars / Testing parameters: Machine Units / Parts, Speed, Power Consumption, ok

Maximum Operating Pressure, Operating temperature, Mass Flow Rate, Maximum

Current, Nominal Input Voltage, Dimensions, etc.

24. At the time of FAT, supplier shall be ready with an engineering file which includes all the above mentioned documents and certificates / reports for piping, complete spray dryer with chamber, cyclone separator, coupled fluid bed dryer etc. with utility details, electrical loads, piping connections, passivation, MOC, flushing, electro-polishing, welding, calibration, etc. ok

25. Installation/Commissioning/Handover/Validation/Testing Report etc. are required. ok

26. Validation report Design Vs Actual ok

27. Software Validation, DQ, IQ, OQ, PQ, etc. ok

28. Day to Day installation & commissioning activities & Training Forms are to be filled ok

C. INSPECTION AND TESTING

1. Component Verification and Dimension verification as per approved GA drawing ok

2. Nozzle size and orientation verification N/A

3. MOC test (Molybdenum test) N/A

4. Pressure and temperature profile test (if any) with spray or atomizer testing. N/A

5. Factory Acceptance Tests will be done. ok

6. Verification of all test and calibration certification of all instruments used during FAT. ~~N/A~~ ok

7. Ra Test for surface measurement Capacity verification N/A

NIHVA TECHNOLOGIES PVT. LTD. * PUNE * NIHVA

PHP Solutions NASHIK

D. SCOPE OF SUPPLY

1. The scope of supply shall include the following, comprising of all the components described in this specifications:

2. Design ok

3. Manufacturing ok

4. Supply ok

5. Supervision of installation ok

6. Commissioning ok

7. Qualification documents for equipment installed in clean/production and analytical rooms please spec

8. Post installation support ok

9. The transportation shall be seal packed, following all safety and common practices to avoid undesirable Consequences. ok

10. Equipment shall be packed and sealed in such a way as to minimize the possibility of:

a. Mechanical damage from loading and unloading, ok

b. Surface scratching or denting on the outside of the equipment, ok

c. Intrusion of foreign external bodies into the equipment's interior. ok.

PHP Solutions NASHIK

NIHVA TECHNOLOGIES PVT. LTD. PUNE