NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax
chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

PCE Ltd
Chennai

Date : 09.06.2020
Quote NO : SQT.19.20.2554
Kind Attn : Mr. R.Annamalai
Email Id : annamalai.r@plantengtech.com
Contact No:

Subject : Quotation for Telescopic Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description
A.	Commercial Offer
B.	Technical Specification
C.	General Conditions
D.	Terms & Condtions

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Total length of conveyor (mm)	Width Of Conveyor (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Telescopic Conveyor	10800	1350	1	14,00,000	14,00,000	55,000	55,000
				Total		**14,00,000**		**55,000**
2			P&F Charges	3%		**42,000**		
			Total Without Taxes			**14,42,000**		**55,000**
			GST Extra @ 18%	18%		2,59,560		9,900
			Total With Taxes			**17,01,560**		**64,900**
3			Transportation Charges			**Extra at actual**		
4			Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Description	Specification
Total length of conveyor	10800 mm
Collapsed length	4800 mm
Telescopic Length	6000 mm
Width Of Conveyor	1350 mm
Width Of Conveyor Belt	600 mm
Conveyor Capacity	40 kg/mtr
Speed	20 mtr/min (Variable Speed)
Drive Type :	
Conveying	Auto/Manual
Telescopic	Auto/Manual
Hydraillic Lifting Support	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1. Installation will start after receiving of Site Readyness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd