NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

PSP Projects Ltd.
PSP House, Opp. Celesta Courtyard, Opp. Lane of Vikramnagar Colony,
ISCON-Ambli Road, Ahmedabad – 380058.

Date : 13.12.2019
Quote NO : SQT.19.20.2304
Kind Attn : Mr. Hardik Sukhadia
Email Id : hardik.sukhadia@pspprojects.com
Contact No: **97250 50727**

Project Name & Location: Surat Diamond Bourse

Subject : Quotation for Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	GI Rolling Shutter Motorised Grill at eye level	3000	3000	11	92,000	1,012,000	20,000	220,000
2	GI Rolling Shutter Motorised Grill at eye level	5000	3000	2	125,000	250,000	20,000	40,000
3	GI Rolling Shutter Motorised Grill at eye level	3500	3000	16	100,000	1,600,000	20,000	320,000
4	GI Rolling Shutter Motorised Grill at eye level	4000	5000	10	156,000	1,560,000	20,000	200,000
5	GI Rolling Shutter Gear Operated Grill at eye level	3000	3000	11	73,000	803,000	20,000	220,000
6	GI Rolling Shutter Gear Operated Grill at eye level	5000	3000	2	107,000	214,000	20,000	40,000
7	GI Rolling Shutter Gear Operated Grill at eye level	3500	3000	16	81,000	1,296,000	20,000	320,000
8	GI Rolling Shutter Gear Operated Grill at eye level	4000	5000	10	130,000	1,300,000	20,000	200,000
1	GI Rolling Shutter Motorised Grilled Shutter	3000	3000	11	109,000	1,199,000	20,000	220,000
2	GI Rolling Shutter Motorised Grilled Shutter	5000	3000	2	150,000	300,000	20,000	40,000
3	GI Rolling Shutter Motorised Grilled Shutter	3500	3000	16	119,000	1,904,000	20,000	320,000
4	GI Rolling Shutter Motorised Grilled Shutter	4000	5000	10	192,000	1,920,000	20,000	200,000
5	GI Rolling Shutter Gear Operated Grilled Shutter	3000	3000	11	90,000	990,000	20,000	220,000
6	GI Rolling Shutter Gear Operated Grilled Shutter	5000	3000	2	131,000	262,000	20,000	40,000
7	GI Rolling Shutter Gear Operated Grilled Shutter	3500	3000	16	100,000	1,600,000	20,000	320,000
8	GI Rolling Shutter Gear Operated Grilled Shutter	4000	5000	10	165,000	1,650,000	20,000	200,000
5	P&F Charges			3%				
	Total Without Taxes							
	GST Extra @ 18%			18%		-		-
	Total With Taxes					-		-
6	Transportation Charges					**In Client Scope**		
7	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA Rolling Shutter

Sr. No	Description	Specifications
1	Model No	NRS00123
2	Rolling Shutter	Motorised Rolling Shutter with Mild Steel of thickness of 1 mm.
3	Mounting Location area	Inside area / Outside area
4	Curtain Panel	The panel made of 1.0mm thick MS steel
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Grill	At eye level
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension
11	Hood Cover	Made of GI Sheet Thickness 0.9 mm GI mm with 25x25x3mm angle stiffener
12	Surface finish	PU paint or Powder coated
13	Drive Unit & Mounting Type	Electric Motor - Indirect Mounting -Jielong

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd