NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

AZAD ROLLING SHUTTER AND CONSTRUCTION
MOHAN CINEMA ROAD, OPP. J. P. MARKET
KOTA - 324 006 (RAJASTHAN)

Date : 18.10.2019
Quote NO : SQT.19.20.2179
Kind Attn : **Mr. Mohammed Imran**
Email Id : azadrollingshutter@yahoo.co.in
Contact No: **9828137864**

Project Name & Location: Amazon, Bangalore

Subject : Quotation for Cold Storage Door, Dock Shelter, Sectional Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2 & 3
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Nihva Make Dock Leveler 9 Ton	2200	3000	1	210,000	210,000	20,000	20,000
2	Sectional Door Vertical Lift	2200	3000	1	232,000	232,000	20,000	20,000
3	Double Wall GI Rolling Shutter	4000	5000	1	274,000	274,000	20,000	20,000
			Total			**716,000**		**60,000**
4	P&F Charges			3%		**21,480**		
	Total Without Taxes					**737,480**		**60,000**
	GST Extra @ 18%			18%		132,746		10,800
	Total With Taxes					**870,226**		**70,800**
5	Transportation Charges					**In Client Scope**		
6	Unloading Charges @ Site					**In Client Scope**		

NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Dock Leveler		
Sr. No.	**Description**	**Specifications**
1	Capacity	9Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 300 / (-) 250 mm
7	Platform Size (W x L)	2200 mm x 3000 mm
8	Lip size (W x L)	2200 x 400 mm
9	Shut Height	480 mm
10	Overall length	2200mm x 3000mm + Lip Length (400mm)
11	Maximum slope can be achieved	10%
12	Clear Pit dimensions (W x L x D)	(W) 2250mm x (L) 3000 mm x (D)485 mm
13	Hydraulic power pack	Standard
14	Driver type	Direct by electric Motor
15	Motor Ratings	1 H.P
16	Pump design flow	2.5 LPM
17	Pump pressure	120 bar Operating 200 bar Max.
18	Safety valve set pressure	120 Kg/cm²
19	Pump Type	Gear
20	Volume of oil receiver	7 Lit
21	No Of Deck cylinder	2 No
22	Lip Cylinder	1 No
23	Dock Bumper	Pair of Dock Bumper

Double Wall Rolling Shutter		
Sr. No.	**Description**	**Specification**
1	Rolling Shutter	Motorised GI Double wall Rolling Shutter
2	Curtain	Made of double skinned galvanised steel laths with PUF Insulation
3	Surface	Precoated in RAL 9006
4	Painting	Pressed galvanised steel hood & motor cover with two coats of Polyurethane spray paint similar to RAL 9006 over one coat of epoxy primer
5	Motor	Compact Gear Jielong Make Indirect Drive Operator
6	Push Button	Three station push button with deadman control
7	Slat	GI Slat 19 mm Thick
8	Profile	Curved Type Profile with heavy duty Shaft
9	Guide	2.5 mm Thick MS Guide
10	Motor & Hood Cover	Hood Cover & Motor Cover 0.9 mm Thick GI material

Sectional Door		
Sr. No.	**Description**	**Specification**
1	ASSA ABLOY	Sectional door (100% Imported products from Europe) OH 1042P
2	Lift Type	Vertical Lift
3	Vision Window	Double acrylic vision panels
4	Vertical Track	Made Up of Galvanised steel
5	Thermal transmittance(EN 12428)	1.1 W / (m^2 K)
6	Water penetration (EN 12425)	Class 3, 70 PA
7	Air permeability (EN 12426)	Class 3
8	Surface Color	Exterior RAL 9002 and interior natural aluminum finish
9	Operating voltage	230 V AC, 50/60 HZ
10	Temperature range	: - 20°C to 60°C
11	Output	0.37 kW
12	Input	1 x 230 V

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 7 - 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333**

With Best Regards
Vivek
8530370333
For NIHVA Technologies Pvt Ltd