NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/18-19/1446 **Date : 09-04-2019**

Deepak Khurana
Delhi

Kind Attention :
Email : deepakkhurana@indecampus.com
Contact No : 9911447800

Project Name And Location : Deharadun

Subject : Quotation for Automatic Revolving Door

Dear Sir
Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer :-

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
Option - 1					
A	**Automatic Revolving Door (Besam - ASSA Abloy)** **(100% Imported Besam Drive – made in Europe)**				
1	1 .**General Details** : -Internal Diameter - 2100 mm -Internal Height - 2200 mm -Total Height -2400 mm -Fascia Height - 200 mm -Revolving Doorset - 3 Door Leaves -Emergency Break Out - None. Rigid Doorset with Fixed Leaves -Design - Door Leaves: Besam "frame" profile feature soft edge rubber nosing & brush carrier - Design - Outer walls (& NCD if Included) : Besam Frame Profile **2. Outer Wall :** -Finish - Outer walls (& NCD if Included) -RAL : 9006 white Alu - Glass type Outer wall : 8.76 mm Class 1B1 clear laminated safety glass to EN12600 **3. Rotating Section :** - Finish - Rotating Section RAL 9006 white Alu -Glass Type Door Leaves : Standard Clear Laminated **4. Accessories :** - Ceiling: Standard white melamine radially segmented inner ceiling -Lighting : LED Spot lights 12V (White Bezel) -Dust Protection Roof : Standard white Melamine dust cover -White resistant cover : no water resistant cover -Emergency Stock : 1 stop button flush mounted -Activation: PIR motion sensor flush fixed under the canopy fascia -Remote Locking : Electro Mechanical Lock operated via the PCD secures the rotating section -Programme Control Device : Flush mounted PCD with digital function & Diagnostic display Outer wall Leading mullion : Monitored pressure senisitve protective edge in rubber safety nosing				
1	(RD3 -21) Size : (W)2400 x (H)2400 mm	1	No.	19,75,000	19,75,000
	(Supply + Installation)				
	Total Amount				**19,75,000**

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@3% supply value
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	14 - 15 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order and balance before delivery
6	**Insurance**	:	Extra As applicable
7	**Taxes**	:	Extra @ Actual
8	**Validity**	:	15 days from the date of quotation.
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr.Arjun o**n **08551096333** For any further Clarification /Information in this Concern.

With Best Regards

Smita Khare
9637991333
For Nihva Technologies Pvt Ltd