RAHUL ENGINEERING GLOBAL PVT LTD

Quotation

PLOT NO 6, GAT NO 627/2/2/6, PUNE NASHIK HIGHWAY
KURULI, CHAKAN, PUNE 410501, MAHARASHTRA, INDIA
Phone Email 9890087871 rahul@recpune.com

DATE May 11, 2021
Quotation # **REGPL269**
Customer ID NTPL

Bill To:
NIHVA TECHNOLOGIES PVT LTD
MIDC, CHINCHWAD
PUNE 411019

Quotation valid until: May 26, 2021
Prepared by: RAHUL CHHAJED

Comments or special instructions:
YOUR INQUIRY VIA EMAIL DATED 08-12-2021 & SUBSEQUENT DISCUSSION VIA TELECON
KIND ATTN: MR MILIND

Description	REGPL PRICE / UNIT
3000L Mixing Vessel with Agitator Assembly - GMP MOC of Contact Parts - SS316L, NonContact Parts - SS304, Lantern Assembly in MS Size 1460 Dia x 1875L x 5thk with Top Dishend and Bottom Dishend 6Thk in SS316L Baffles - 4 nos with suitable supports Lug supported - 4 Nos in SS304; Manhole 450NB with Dished Cover & 100NB Sight Glass Inside finish 320Grit mirror polish and outside finish matt polish Agitator Baby Anchor + 2Blade PBT, Single Mech Seal, Motor 15HP, GB, Shaft Dia 80, RPM~60 Light Glass 100NB with Lamp; Inlet 40NB with Valve, Breather Valve 40NB; CIP with SprayBall Spare 25NB with Valve - 2 Nos; Phase Inlet 40NB; Recirculation 50NB; Outlet 50NB Electrical Panel for Agitator *Pipeline, Load Cells, Electronic weighing system not considered*	Rs 13,05,000
3000L Storage Vessel with Agitator Assembly - GMP MOC of Contact Parts - SS316L, NonContact Parts - SS304, Lantern Assembly in MS Size 1575 Dia x 1500L x 4thk with Top Dishend and Bottom Dishend 4Thk in SS316L Baffles - 4 nos with suitable supports Lug supported - 4 Nos in SS304; Manhole 450NB with Dished Cover Inside finish 320Grit mirror polish and outside finish matt polish Agitator Baby Anchor + 2Blade PBT, Single Mech Seal, Motor 15HP, GB, Shaft Dia 80, RPM~60 Outlet Ball Valve 25NB; Outlet 50NB Electrical Panel for Agitator *Pipeline, Load Cells, Electronic weighing system not considered*	Rs 11,85,000
DELIVERY TIME: 14 WEEKS	
TOTAL	**Rs 24,90,000**

CONSIDERATIONS & ASSUMPTIONS:
01. ALL WELDING IS CONSIDERED BY TIG PROCESS WITH SUITABLE FILLER WIRE
02. RADIOGRAPHY 10% CONSIDERED
03: THIRD PARTY WILL BE ARRANGED BY YOU IF REQUIRED
04. GASKETS, HARDWARE WILL BE FOOD GRADE
05. INSTRUMENTATION ARE NOT CONSIDERED

TERMS & CONDITIONS
01. PRICE IS EX-WORKS, KURULI, CHAKAN
02. GST @18% IS APPLICABLE
03. QUOTE IS MADE AS PER SPECIFICATIONS ABOVE
04. PAYMENT WILL BE 50% ADVANCE, BALANCE BEFORE DELIVERY

If you have any questions concerning this quotation, contact Name, Phone Number, E-mail

THANK YOU FOR YOUR BUSINESS!