NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Narsi & Associates
522, Laxmi Mall, Bldg. No. 5, Laxmi Ind. Estate,
New Link Road, Andheri (W), Mumbai – 400 053.

Project, Location :

Date : 26.02.2021
Quote NO : SQT.20.21.3056R
Kind Attn : Gaurangi Kawali
Email Id : procurement@narsi.in
Contact No: 022-42505555 ext.529

Subject : Quotation for Manual Gate, High Speed Doors, Dock Shelter and Fire Rated Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**NIHVA Make - High Speed Doors - Self-repair door**	3000	2100	3	371,000	1,113,000	15,000	45,000
2	**Fire Rated Rolling Shutter**	2930	4725	1	294,000	294,000	15,000	15,000
3	**Manual Single Leaf Sliding Gate**	1200	2100	2	45,000	90,000	10,000	20,000
4	**Retractable Dock Shelter**	3400	4500	1	125,000	125,000	10,000	10,000
	Total			**7**		**1,622,000**		**90,000**
5	P&F Charges			3%		48,660		
	Total Without Taxes					1,670,660		90,000
	GST Extra @ 18%			18%		300,718.80		16,200
	Total With Taxes					**1,971,379**		**106,200**
6	Transportation Charges					Extra at atcual		
7	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

2 Hrs. Fire Rated Rolling Shutters

Sr .No.	Specification	2 Hour Fire Rated Rolling Shutter
1	Certification	BS 476 Part 22 & MS 1073 Part 3 1988 Tested in Warrington Fire Reasearch Centre UK & Sirim Malasiya
2	Test	UL - 10B Tested
3	Shutter Slats	Zinc coated steel solid slats
4	Shutter Curtain	Roll formed from 1st grade BHP Zincalume steel SKB-A7 curve slat curtain
5	Guide Rail	Fabricated from hot-dipped galvanised steel of 3.0 mm with one piece design surface mounted type.
6	Bottom Bar	Assembled of 2 Pieces of 38 x 38 x 3 mm galvanised steel angle bolted 800 mm pitch with galvanised bolts and nuts or 2 pieces of 40 x 40 x 6 mm steel flat bar.
7	Shutter Enclosure Box	Pressed Galvanised steel sheet to suite box size comply to fire test approved thickness.
8	Operation Control	Gear motor with Thermal protector, limit switches, manual overide, c/w push button switch with keys lockable.
9	Motor Drive Unit	Power Source: 110v 60Hz 1 phase 220v 6OHz 1 phase 230v 50Hz 1 phase 400v 50Hz 3 phase Manual Chain Override One unit push button switch Gravity drop level Auto close by relay switch after receive of 24vdc fire signal
10	Fire Mode	Fire Shutter will auto close via upon receiving of 24VDC fire signal

Wicket Gate

Sr .No.	Specification	Wicket Gate
1	Door type	Manual Single Leaf Wicket Gate
2	Size considered	Clear opening - (W)1200 mm x (H)1800 mm
3	Mounting Location area	Inside area
4	Design Pattern	Standard Tubular Design Pattern
5	Outer Frame Tube Sizes	80 x 80 x 3.2 mm
6	Internal Vertical Tube Sizes	40 x 40 x 2 mm
7	Gap Between Tubes	100 mm C/C
8	Painting	2 Coats of EPOXY polyamide based enamel finish of approved Colour
9	Operation	Manually Opening

NIHVA Make - High Speed Doors - Self-repair door

Metallic frame made of galvanised steel and it can be also paintedwith any RAL colour
Rolling-up tube made of aluminium. Self-lubricated vertical guides, assembled with an absorption springs system.
Flexible curtain made of high resistance polyester, self-extinguish M2 fire class, with a zipper system and a high wind resistance.
Security photocells for automatic reopening if an obstacle is detected during closing.
Our Self-repair includes the most advanced security systems as concern high performance doors and therefore it is in accordance with Obligatory European Rule EN-13241-1.

Sr .No.	Specification	NIHVA Make - High Speed Doors - Self-repair door
1	Interior door	suitable
2	Wind resistance EN 12424	class 2
3	Opening direction	vertical
4	Top roll cover	standard
5	Drive unit / Control system	electrical / TS-970 GFA
6	Safety	Door line photocell on the top and Lateral parts
7	Open/close up to max.	0.9 m/s
8	Fuse protection	10_A
9	Control voltage	24 V DC
10	Protection I	IP 55
11	Motor power / kW	0,45 Kw
12	Potential free contacts max. 250 V	standard

Retractable Dock Shelter

Sr .No.	Specification	Dock Shelter
1	**Top Curtain**	1000 mm
2	**Side Curtain**	600 mm
3	**Curtain colour**	Black
4	**Parking Guides**	White, Yellow
5	**Wall Fixings**	Concrete, Sandwich light Concrete, Load house cavity, insulated panel
6	**Top & Side Curtains**	Double Layer High Quality Polyester
7	**Thickness**	3.0 mm
8	**Weight**	Approx 3400 g/m2

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 - 12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd