NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Huhtamaki PPL Ltd
Village Ransai, KM.16,
Khopoli - Pen Road,
Taluka : Khalapur, Dist - Raigad; 402107

Date : 28.02.2020
Quote NO : SQT.19.20.2450R
Kind Attn : Mr. Bapu Gawali
Email Id : bapu.gavali@huhtamaki.com
Contact No: 8879068207

Project Name & Location: Huhtamaki PPL Ltd

Subject : Phase 2 : Quotation for Sectional Door, High Speed Door, Dock Leveler, Dock Shelter, Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Location	Size		Qty	Supply Charges in INR		Installation Charges in INR	
			Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
	Phase 2 - Unit no 2 :								
1	High Speed Doors - RR300+ Alu	Tube FG Entrance from battery charging raea	3000	3000	1	632,000	632,000	15,000	15,000
2	High Speed Doors - RR300+ Alu	Tube Slitting	2500	2900	1	619,000	619,000	15,000	15,000
3	High Speed Doors - RR300+ Alu	Lamination Entrance	3000	3000	1	632,000	632,000	15,000	15,000
4	High Speed Doors - RR300+ Alu	Painting Entrance	2500	2500	1	612,000	612,000	15,000	15,000
5	High Speed Doors - RR300+ Alu	Opposite to Painting Entrance	2500	2500	1	612,000	612,000	15,000	15,000
6	High Speed Doors - RR300+ Alu	RMS exists near to BFL	2500	2500	1	612,000	612,000	15,000	15,000
7	High Speed Doors - RR300+ Alu	BFL	3000	3000	1	632,000	632,000	15,000	15,000
8	High Speed Doors - RR300+ Alu	Cylinder Side Production Entry	3000	3000	1	632,000	632,000	15,000	15,000
9	High Speed Doors - RR300+ Alu	Slitting Entry 1	3100	3000	1	639,000	639,000	15,000	15,000
10	High Speed Doors - RR300+ Alu	Slitting Entry 2	3100	3000	1	639,000	639,000	15,000	15,000
11	High Speed Doors - RR300+ Alu	Packing Area	2200	2700	1	616,000	616,000	15,000	15,000
12	High Speed Doors - RR300+ Alu	Dispatch	3000	4000	1	649,000	649,000	15,000	15,000
13	High Speed Doors - RR300+ Alu	Dispatch	3000	4000	1	649,000	649,000	15,000	15,000
14	High Speed Doors - RR300+ Alu	Dispatch	3000	4000	1	649,000	649,000	15,000	15,000
15	High Speed Doors - RR300+ Alu	Dispatch	3000	4000	1	649,000	649,000	15,000	15,000
16	High Speed Doors - RR300+ Alu	Dispatch	3000	4000	1	649,000	649,000	15,000	15,000
17	Motorised Rolling Shutter with Grill	Pouching Scissor Lift Door	2500	2000	1	96,000	96,000	15,000	15,000
18	High Speed Doors - RR300+ Alu	Metaliser	3000	3000	1	632,000	632,000	15,000	15,000
19	High Speed Doors - RR300+ Alu	Metaliser	3000	3000	1	632,000	632,000	15,000	15,000
					Total		**11,482,000**		**285,000**
20				P&F Charges	3%		**344,460**		
				Total Without Taxes			**11,826,460**		**285,000**
				GST Extra @ 18%	18%		2,128,763		51,300
				Total With Taxes			**13,955,223**		**336,300**
21				Transportation Charges			**Extra at Actual**		
22				Unloading Charges @ Site			**Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

High Speed Door - ASSA ABLOY RR300+ Alu

Sr. No	Description	Specifications
1	Door panel:	Transparent PVC with Red (RAL 3002) reinforcement stripes.
2	Barrel:	Aluminium, anodized with shafts made of galvanized steel
3	Wind Reinforcement:	Door Panel wind tabs for improved wind resistance
4	Wind Speed	Class 1
5	Side Frames:	Aluminium profiles, anodised
6	Drive Unit:	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)
7	Self-opening:	Standard - the door can be opened partially up to 1,8 m by releasing the brake manually.
8	Bottom beam:	Anodized extruded aluminium.
9	Control system:	MCC Vector Control - frequency converter control system for a dynamic, smooth door movement, located close to the drive unit Max. Opening Speed 2.2m/s Max. Closing Speed 0.9 m/s
10	Safety features:	Safety edge, safety photocell (Transmitter/Receiver) inside side columns
11	Loop Detector	Considered (Both Sides)
12	Push Button	Considered (Both Sides)
13	Motor Cover	Included
14	Hood Cover	Included

Motorised Rolling Shutter - NIHVA Make

Sr. No	**Description**	**Specification**
1	Mounting Location area	Inside area / Outside area
2	Mounting Surface	Side Brackets: Optional = On Concrete
3	Curtain Panel	The panel made of 1.0mm thick MS.
4	Curtain panel size	75mm wide
5	Curtain Profile	Curved
6	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
7	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
8	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
9	Hood Cover	Made of GI Sheet Thickness 1 mm
10	Surface finish	Two Coats of Primer and two coast of Synthetic Enamel
11	Motor	Indirect Drive - Jielong Make Motor

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10-12 weeks for Scissor lift from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd