SHILCHAR TECHNOLOGIES LIMITED

August 24th , 2017

Purchase Order

Mr.Mallikarjun Patil,
NIHVA Technologies Pvt. Ltd.
187, G-Block, Thermax chowk, MIDC
Chinchwad, Pune – 411019.

Subject: PO for Rolling shutters, Main gate, wicket gate, boom barrier & dock leveler for manufacturing plant of Shilchar Technologies Limited at Gavasad - Vadodara

Dear Mr. Mallikarjun Patil,

As per your discussion with our management and quotation number SQT/16-17/0382R7 dated 11.08.17, we are pleased to award you this work for supply and installation of Rolling shutters,Main gate, wicket gate, boom barrier & dock leveler as per below details:-

Sr	Detail	Qty	Unit Price supply	Total Price supply	Unit price of installation	Total price of installation
1	Motorized sliding gate 9 M X 1.8 M	1	272,000	272,000	15,000	15,000
2	Motorized sliding gate 6 M X 1.8 M	1	213,000	213,000	15,000	15,000
3	Wicket gate 1.2 M X 1.8 M	2	30,000	60,000	5,000	10,000
4	Motorized rolling shutter 8.4M X 5M	1	216,000	216,000	12,000	12,000
5	Motorized rolling shutter 5.5M X 5M	1	150,000	150,000	12,000	12,000
6	Motorized rolling shutter 6.3M X 5M	2	150,000	300,000	12,000	24,000
7	Motorized rolling shutter 3.7M X 5M	1	108,000	108,000	12,000	12,000
8	Motorized rolling shutter 6.0M X 5M	1	150,000	150,000	12,000	12,000
9	Motorized rolling shutter 4.3M X 5M	1	108,000	108,000	12,000	12,000
10	Boom barrier 7.5 M	1	140,000	140,000	12,000	12,000
11	Dock leveler 10 T 3M X 2 M	1	170,000	170,000	12,000	12,000

TOTAL			1,887,000		148,000
GST @ 18 % extra on serial number 1 to 9			283,860		
GST @ 28 % extra on serial number 10 & 11			86,800	GST 18%	26,640

Grand Total of inclusive GST			**2,432,300**

Total price of above items including supply, transportation,insurance,unloading,erection & commissioning, applicable GST will be INR – 24,32,300/-. (Twenty four lacs thirty two thousands three hundreds only.)

REGD. OFFICE & WORKS : BIL ROAD, BIL, VADODARA- 391 410, GUJARAT, INDIA.
PHONE : (0265) 2680466, 268 0566 • **FAX :** (0265) 268 0611
E-MAIL : info@shilchargroup.com • **Website :** shilchargroup.com
CIN: L29308GJ1986PLC008387

Payment Terms:-

Supply part:-

20% advance against ABG valid for 3 months.
70% against Performa invoice and successful inspection.
10% on completion and against PBG of 15% of total value valid for 2 years from date of commissioning.

Erection part:-

100% after successful erection and commissioning.

Warranty:-

It shall be of two years unconditional comprehensive warranty for all product and parts.

Scope of supply:-

1. Supply equipment as per approved drawing and technical specification.
2. Transportation of equipments at our new plant.
3. Unloading of equipments at our new plant.
4. Storage till equipment gets installed.
5. Internal movement of equipment at our new plant.
6. Installation of all equipment
7. Scaffolding, tools and tackles require for installation.
8. All require PPEs for manpower involved in installation.
9. Insurance of manpower involved in installation.
10. Cleaning of site after installation.
11. Successful testing and demonstration of operation.
12. Providing operation and maintenance training to Shilchar team.
13. All drawings including electrical & hydraulics layout in hard and soft copies.
14. Operation and maintenance manual along with list of spare parts.

Delivery:-

Delivery of all items including erection & commissioning shall not be later than 30.09.17.

Note:-

1. Motor of Serial No-1 & 2 will be shilchar scope. (If require we will buy from you at price of 50,000/- & 40,000/- respectively).
2. Your engineer shall measure all require dimension at actual site and submit us drawing for approval. He has to consider all site condition.
3. Apart from given size if there will be any minor changes in dimensions specially in shutter Nihva shall consider same without any price implication.
4. Color of all equipment shall be as per shade defined by Shilchar.
5. During execution Nihva team shall take care of other property/infrastructure present at site and do not damage it.
6. During installation NIHVA' supervisor/engineer shall be present.
7. After installation if require there shall be touch up painting to be done.
8. Nihva shall closely co-ordinate with Shilchar team during execution of entire project.
9. In rolling shutter wherever require by Shilchar, mechanical stopper shall be provided
10. All electrical junction box and panel shall be insulation class of IP-55.

REGD. OFFICE & WORKS : BIL ROAD, BIL, VADODARA- 391 410, GUJARAT, INDIA.
PHONE : (0265) 2680466, 268 0566 • **FAX :** (0265) 268 0611
E-MAIL : info@shilchargroup.com • **Website :** shilchargroup.com
CIN: L29308GJ1986PLC008387

Technical Detail:-

1. **Rolling Shutter:-**

   A. Single skin GI slat motorized shutter. Thickness of GI shall be minimum 1 mm.
   B. Operation of shutter – Minimum nos of shutter shall be possible per hour are 3 Nos.
   C. Guide – shall be of MS material and of size 75 mm to 100 mm.
   D. Bottom profile shall be of MS with rubber seal.
   E. Electrical motor – 0.71 KW for up to 4.5 meter shutter, 1.013 kW for up to 6.5 meter and 1.768 kW for up to 8.5 meter shutter.
   F. Speed of shutter – 0.1 meter/second.
   G. Safety photo sensor shall be there for safety of shutter and person passing below shutter.
   H. There shall be emergency stop.
   I. Shutter shall be design for wind load up to 90 km/hr.
   J. In case of electrical failure there shall be provision for manual chain drive
   K. After installation there shall not be any gap between building and shutter.
   L. Noise during operation shall not be more than 75 dB.
   M. Color of gate shall be PU with DFT of minimum 150 microns. 40 mm red oxide (primer) + 50 mm MIO + 60 mm PU paint. Make of paint shall be Jotun/Hampel/Akzonoble
   N. GI sheet hood as cover for rolling element at top. Thickness of hood shall be minimum 0.8 mm.
   O. There shall be window type provision in shutter 3.7M X 5M (item no -7).

2. **Main gate & wicket gate:-**

   A. Main gate shall be as per drawing provided by us and motorized
   B. Size of main gate is 9 meter X 1.8 meter – 01 no & 6 meter X 1.8 meter – 01 no.
   C. Color of gate shall be PU with DFT of minimum 150 microns. 40 mm redoxide (primer) + 50 mm MIO + 60 mm PU paint. Make of paint shall be Jotun/Hampel/Akzonoble.
   D. It shall be motorized. Only motor will be provided by Shilchar. All other required electrical and electronics is in scope of Nihva. (If require we will buy from you at additional price of 50,000/- & 40,000/- respectively of make BFT-Italy).
   E. Speed of door – it shall be 14 meter/min.
   F. Safety sensor- There shall be safety photo sensors for main gate and person/vehicle passing across it.
   G. Operation of door shall be through push button panel and location of it decided by Shilchar.
   H. Weight of main door shall be minimum 1400 kg for 9 M gate, minimum 950 kg for 6 M gate and minimum 100 kg for wicket gates.
   I. All require rollers, bright bar, guide are scope of Nihva.
   J. Wicket gates are swing type and shall be as per drawing submitted by Shilchar.
   K. Size of wicket gates shall be 1.2 meter X 1.8 meter -02 Nos.
   L. Wicket gates shall be with locking arrangement.
   M. Operation of gates shall be smooth and noise free.
   N. Main gate shall be with emergency stop.
   O. All parts shall be for outdoor applications.

REGD. OFFICE & WORKS : BIL ROAD, BIL, VADODARA- 391 410, GUJARAT, INDIA.
PHONE : (0265) 2680466, 268 0566 • **FAX :** (0265) 268 0611
E-MAIL : info@shilchargroup.com • **Website :** shilchargroup.com
CIN: L29308GJ1986PLC008387

3. **Dock leveler:-**

A. Capacity- 10 Ton. Qty-01 No.
B. Platform Size- 3 meter X 2 meter.
C. Platform plate – checkered plate minimum 8 mm.
D. Lip- split lip MS of 14 mm in thickness and minimum 300 mm in length. Width shall be 2 meter.
E. Lip plate shall be plain plate.
F. Operation Hydraulic operated 2 cylinders for deck and 1 cylinder for lip. Push button station as location decided by Shilchar. Operating panel shall consist of 04 nos push button with emergency stop.
G. Safety – side plate to cover pit when scissor lift fully in up condition. Thickness of plate shall be minimum 3 mm.
H. Color of gate shall be PU with DFT of minimum 150 microns. 40 mm redoxide (primer) + 50 mm MIO + 60 mm PU paint. Make of paint shall be Jotun/Hampel/Akzonoble.
I. Color shall be golden yellow.
J. Bumper- one set of rubber bumper.
K. There shall not be any jerk during operation.
L. While loading in vehicle dock leveler shall cater height adjustment due to loading.
M. In normal close condition platform shall be flushed with our finished shop floor level and Lip plate shall be 90 degree downward.
N. There shall be front stopper and require arrangement so that during course of operation dock leveler shall not move outside pit.

4. **Boom barrier :-**

A. Single boom barrier with effective clear length of 7.5 meter.
B. Motorized with in open condition it shall be 90 degree. Make of drive shall be BFT Italy.
C. Color of gate shall be PU with DFT of minimum 150 microns. 40 mm redoxide (primer) + 50 mm MIO + 60 mm PU paint. Make of paint shall be Jotun/Hampel/Akzonoble.
D. Color shade shall be decided by Shilchar.
E. Material of boom barrier shall be aluminum.
F. Safety sensor photocells.
G. There shall be reflector so it shall visible in night.
H. Opening time 8 seconds.
I. Operation through push button and location will be decided by Shilchar.
J. There shall not be any jerk movement during operation.
K. It shall be for outdoor application.

For Shilchar technologies Ltd

Mr. Alay J Shah
Managing Director

Accepted By:-

M/s Nihva Technologies.

REGD. OFFICE & WORKS : BIL ROAD, BIL, VADODARA- 391 410, GUJARAT, INDIA.
PHONE : (0265) 2680466, 268 0566 • **FAX :** (0265) 268 0611
E-MAIL : info@shilchargroup.com • **Website :** shilchargroup.com
CIN: L29308GJ1986PLC008387

Enclosed:

1. All approved drawings.(Submit by Nihva and approved by us).
2. Main sliding gate drawing of 9 meter, 6 meter & wicket gate.

REGD. OFFICE & WORKS : BIL ROAD, BIL, VADODARA- 391 410, GUJARAT, INDIA.
PHONE : (0265) 2680466, 268 0566 • **FAX :** (0265) 268 0611
E-MAIL : info@shilchargroup.com • **Website :** shilchargroup.com
CIN: L29308GJ1986PLC008387