Quotation reference: **SQT/18-19/1211R3** **Date: 26th September 2019**

Elcom Systems Pvt. Ltd
Plot-39, Institutional Area,
Sector 32, Gurgaon 122001

Kind Attn: Mr. Jaya Kumar
Contact No: 9810870935
Email ID : jayakumar@sungroup-india.com

Project: **Bhiwadi Rajstan**

Subject : Supply & Installation of NIHVA Make Sliding Hangar Door

Dear Sir,

Thank you for giving us an opportunity to participate with our offer on the above project. We enclose herewith our proposal which includes:

A. Requirement
B. Technical Details
C. Terms and Conditions
D. Pricing

We wish you success with your project and hope that we may be part of your current & future projects as a solution provider. We will follow up this quotation with a call to you within the next few days.

If you have any questions after reading this proposal, or if you need more information, please do not hesitate to contact us.

Kind Regards,

Ms. Varsha
NIHVA Technologies Pvt. Ltd
187/G Block, 1st Floor, Thermax Chowk,
Above Renault showroom, Chinchwad,
PUNE - 411019
Mob: +91 8551091333

A. Requirement Hangar Door:

Clear opening Width (M)	Clear Opening Height (M)	Qty
Total :38.76	Max :07	2

1. **Size of each door Clear Opening – 38.76M (W) x 07 M (H)**
2. **Quantity of Doors – 2 Set**
3. **Type of Door – Motorised Multi-leaf**
4. **Leaves per door – 8 + 8 Nos (RH + LH)**

B. PRICING –

Sr no	Description	Price/Each in Rs	Qty No	Total Price in INR
Hanger Door: Size – (W) 38.76 Mtr x (H) 07 Mtr				
1	Supply + Installation Hanger Door	93,10,000	2	**1,86,20,000**

General Pre-Requisites Required at Site

Prerequisites:

a) Finished Flooring after curing (Without Water)
b) Electrical Supply on the site single phase/three phase points at different places.
c) Provide electrical cables near to the installation machinery.

Terms & Conditions:

Payment : 80% along with confirmed purchase order & balance before dispatch.

P & F Charges : NIL

Transport : NIL

GST : Extra 18%

Delivery : 16-18 weeks from the date of receipt of confirmed order, drawing approval.
Warranty :12 months from date of Supply.

General conditions of Aircraft Hangar Door

1. Continuous uninterrupted access to any single door section or as agreed separately.

2. 400 volt / 50Hz 3 phase isolator to be fitted to within 1 mtr of the door main control panel. If not available at the start of installation, a temporary supply is acceptable. Any return visits to commission the doors due to permanent power not being available will be charged as appropriate.

3. Provision of 230 Volt power supply (by others) for hand tools.

4. A dry & secure area, not in direct sunlight, is to be provided for storage of the door components.

5. Access to site between 7 am to 6 pm six days per week. If this is not possible the installation programme may require amending.

6. The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practices. We reserve the right to extend the period accordingly.

7. Any passes required for the project, are the responsibility of the Customer must be available, before commencement of the installation. Any delays caused by the non-availability of passes, will be charged accordingly.

Inclusions

1. A pre-installation inspection will be carried out, by our Project Manager, before our installers travel to site, so as to verify that the structural steelwork and electrical installation are as per our requirements. Our Project Manager will also check that the installation equipment and facilities are ready for installers.

Exclusions

The following items are not within our scope of works and are to be provided by others at no cost to NIHVA.

1. A compliance statement, with supporting documentation, which states that the building deflections are in accordance with the criteria, as agreed between our design department and the steelwork contractor (to be done by main contractor).

2. Any passes required for the project, are the responsibility of the Customer and must be available, before commencement of the installation. Any delays caused by the non-availability of passes, will be charged accordingly.

3. Power supply and isolators adjacent to the control panels (to be done by electrical contractor).

4. A 400/230 power supply (permanent or temporary) must be provided by client during the installation of the door for power tools and testing of the door sections during erection.

5. A safe storage / pre-assembly area for the door materials

6. Any additional tests or certification, which are not within our scope of works but may be required by the Consultant or Client, these will be carried out or provided, subject to the actual requirements but will be at additional cost.

7. Any Additional Civil Work Required other than Door will be in Client Scope.

Please feel free to Contact Mr. Arjun Patil on 08551096333 For any further Clarification /Information in this Concern.