NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Pradman Services
Odissa

Date : 08.06.2024
Quote NO : RR_24.25.0033R
Kind Attn : **Mr. Sadanand Shetty**
Email Id : shettys@pradmanservices.com
Contact No: 9594085279

Project Name & Location: Pradman Services, Odissa

Subject : Techno - Commercial Offer for Rectractable Roof/High Speed Door

Dear Sir ,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr. No.	Description	Specifications	Qty	Supply & Installation Charges in INR	
				Unit Price	Total Amount
1	MS Structure + Rectractable Roof	As per drawing provided by you	1	205,00,000	₹ 205,00,000
2	NIVHA Make High Speed Door	1- 3385H X4750W – 1 nos 2- 3385H X3250W – 1 nos 3- 3385H X2350W – 1 nos 4- 2300H X1000W – 1 nos 5- 2300H X1000W – 1 nos 6- 2300H X1000W – 1 nos	1 Set	13,05,000	₹ 13,05,000
3	Installation of above both			16,50,000	₹ 16,50,000
		Total without Taxes			234,55,000
4		GST Extra @ 18%	18%		Extra At Actual
5		P&F Charges @ 3%	3%		Extra At Actual
6		Transportation Charges			In client Scope
7		Lifting Equipment required @ desired floor			In NIHVA Scope
9		Unloading Charges @ Site			In NIHVA Scope

B) Technical Specification

1. PVC sheet
2. Profile :MS Painted
3. Guide : MS
4. Interlocking
5. MS Fastners

NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA MAKE - High Speed Door

Sr. No	Description	Specifications
1	Use	Internal Door
	CURTAIN DETAILS	
1	European Make- Most Innovative & Superior PVC Coated Fabrics for High Speed Doors	
2	Longer Life Span • High Tear Strength • Dimensional Stability • UV Resistant • Very Flexible	
3	Flame Retardant (Chemically Treated to Self-Extinguish)	
4	Resistant to Humid Environment	
5	Simplified Maintenance (Easy To Clean & Maintain) • Reduces Energy Cost • 100% Recyclable	
6	Working Temperature Range: From -30°C to +85°C	
	DOOR STRUCTURE	
1	Front guide columns of the doors are made of Aluminium Matt finished clear Anodized of size 125 mm x 105 with wall thickness 5 mm.	
2	The curtain along with heavy bottom side is made by aluminium profile of 90 mm x 25 mm thick for better support & curtain movement.	
3	Door columns are with dual brush sealing which seals door columns and stops movement of air and pollutants positive wind resistance class - Din en 12424 - Class 3 with standard pressure difference - Delta 10 pascals.	
	Operation & Accessaries	
1	Basic Operation on Push Buttons from both the sides.	
2	Auto Close Function is Inbuilt	
3	Auto Close with variable hold open timer range can be set in between 1sec - 500 sec	
	Motor and Controller	
1	Motor	High Speed Servo Motor Make IDER, manufactured under European Standards, CE certified.
2	Speed	Normal Factory Set Speed is in between 500 mm / sec opening & closing. With Programming can be changed up to 2000 mm / sec.
3	Protective Function	Over-current Protection, Over-voltage Protection Under-voltage Protection, Overheating Protection and Overloading Protection.
4	Power Supply	3*AC 220V
5	Manual Release	Hand Crank
6	IP Rating	lp65
7	Use Environment	-20°C To +45 °C
	Safety Features & Accessories	
1	Photocell (Safety Sensor) - Dual Safety PE Sensor (Working range of 6m) is included.	
2	LED indication for identification of alignment of emitter and receiver is included.	
3	Flashing Light	
4	The Safety edge sensor, installed inside the bottom rubber, will reverse the door in case of any feather touch obstruction occurred between the door and floor is included.	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Continuous uninterrupted access to installation section or as agreed seperately.
2 Provision of 230 V power supply for hand tools.
3 A dry and secure area, not in direct sunlight is to be provided for storage of product component
4 Access to site between 7 am to 8 pm should be provided.
5 Any storage costs for material due to delay outside of NIHVA, will be in client scope.
6 The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practice. We reserve
7 Installation will start after receiving of Site Readiness Photographs or written Email communication.
8 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation.
9 For any reason if we need to stop our installation and demobilize the team without completing the work, then extra cost will be applicable for
10 If any change in dimension on actual site, quoted price will affect accordingly which will be in client scope.
11 After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an additional cost.

Note: Please find below List which are in Client Scope

Sr. No		Remark
1	Secured and fully covered Store area to keep the material.	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site.	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different	In Client Scope
4	Any civil / masonry/structural work required.	In Client Scope
5	All structure support required.	In Client Scope
6	In Case of any changes in the layout as per site requirements after the	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune.
Delivery : 10-12 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing Approval.
Payment : 70% Advance along with Confirmed Purchase Order.
25% After material Delivery at site.
5% After Installation.
Validity : Validity of offer is 15 days from the date of quotation.
Warranty : 12 months from the date of supply. It only covers damage caused due to mechanical system not due to natural calamity.

With Best Regards
Vijayshri J
8530872333
NIHVA Technologies Pvt Ltd