NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/17-18/0511R3 **Date : 19.05.2018**

GBRN Projects India Pvt. Ltd
202. II Floor, Konark Epitome, Survey No: 230
Before Konark Campus, VimanNagar
Pune-411014
Maharashtra, India

Kind Attention : Mr. D Shukla
Email ID : dhananjay@gbrn.in
Contact No : 7066304044

Project Name And Location :

Subject : Revised Quotation for Rolling Shutter & Fire Door

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.

This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Motorised Rolling Shutter** **Shutter GI Slat: 1 mm Thk, Curved Type Profile with heavy duty Shaft, Guide - 75 mm, Hood Cover - 0.9mm, Motor - Indirect Drive with Painting**				
1	Size : (W)3000 x (H)3000 mm	1	Nos	70,000.00	70,000.00
2	Installation charges for above shutter	1	Nos	10,000.00	10,000.00
	Total				**80,000.00**
B	**2 Hrs Fire Rated Door** **2 Hrs (120 Min.) Fire rated Door with Rockwool Infill .GI Sheet Doors panel with 46mm thk & 1.2mm Face Sheet.Frame 1.5mm thk. and 100X57mm Jamb depth & width**				
1	**Single Leaf Door** **Size : (W)1200 x (H)2400 mm**	3	No's	19,500.00	58,500.00
Specifications	SS Ball Bearing Hinge 102X76X3mm - Make Dorma	12	No's	375.00	4,500.00
	Dorma Closer TS 68 with Standard Arm Silver Finish	3	No's	2,000.00	6,000.00
	Panic bar- Single Point- Dorma PHCR 1000 (9121502)	3	No's	6,500.00	19,500.00
	External Trim- Dorma PHCRT 2905 (9121512)	3	No's	5,000.00	15,000.00
	Vision Panel- 300 x 200 mm- Schoot	3	No's	3,500.00	10,500.00
	Automatic door bottom RP8si Seal, Finish-CA 1220 mm length	3	No's	4,900.00	14,700.00
	RP48 weather strip closed sponge self adhesive EPDM bulb seal (In RMT)	3	RMT	3,500.00	10,500.00
	Anchor Fastener	30	No's	90.00	2,700.00
2	Installation charges for above Door	3	No's	6,000.00	18,000.00
	Total				**1,59,900.00**

GST Pune	**27AAECN0437H1ZM**	**Total Basic Amount (A) + (B)**	**2,39,900.00**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex Works Pune
2	**P & F Charges**	:	NIL
3	**Freight Notes**	:	Extra Rs. 10,000/-
4	**Delivery**	:	4-5 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	25% Advance along with Confirmed Purchase Order, 65% Against Delivery Immediate and balance 10% After Installation Immediately.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST for Supply & Installation is 18%
8	**Validity**	:	15 days from the date of quotation.
9	**Warranty**	:	12 months from the date of supply.

With Best Regards

Arjun Patil

8551096333

For Nihva Technologies Pvt Ltd