NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Ferrero India Pvt Ltd
IMSOFER Division (Unit I) ,Plot No. F-13,
M.I.D.C., Baramati,
Maharashtra, India

Date : 01.03.2021
Quote NO : SQT.20.21.2978R1
Kind Attn : Mr Tausif Shaikh
Email Id : tousif.shaikh@ferrero.com
Contact No: 7722023571

Subject : Revised Quotation for Assa Abloy Make HSD RR300+ALU (High Sea Sale)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer -Price is High Sea Sale (Custom Duty + Custom Clearance + Local Transport will be in Ferrero Scope)

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**ASSA ABLOY Make RR300+Alu_Way to molding line 3 process area**	1950	3912	1	672,500	672,500	20,000	20,000
2	**ASSA ABLOY Make RR300+Alu_Kinder joy tunnel**	2504	3995	1	687,500	687,500	20,000	20,000
3	**ASSA ABLOY Make RR300+Alu_KSBC Packing**	2997	3915	1	702,500	702,500	20,000	20,000
4	**ASSA ABLOY Make RR300+Alu_Rocher Packing**	1960	2515	1	652,500	652,500	20,000	20,000
5	**ASSA ABLOY Make RR300+Alu_Kinder joy Packing**	2848	3683	1	697,500	697,500	20,000	20,000
6	**ASSA ABLOY Make RR300+Alu_Scrap tunnel**	2194	3481	1	672,500	672,500	20,000	20,000
7	**ASSA ABLOY Make RR300+Alu_Tunnel way to time office**	2400	2615	1	667,500	667,500	20,000	20,000
				Total		**4,752,500**		**140,000**
			P&F Charges	3%		**142,575**		
				Total Without Taxes		**4,895,075**		**140,000**
			GST Extra @ 18%	18%		881,114		25,200
				Total With Taxes		**5,776,189**		**165,200**
				Transportation Charges		**Extra at actual**		
				Unloading Charges @ Site		**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

ASSA ABLOY Make RR300+Alu

Sr. No	Specification	ASSA ABLOY Make Rapid Roll Up Door RR300+Alu
1	**Description**	Flexiable High Performance Door , Opening in vertical direction for interior use in wind protected area
2	**Side Frames**	Made of Aluminium
3	**Door Curtain**	Made of transparent PVC with Fabric reinforcement stripes ultramarine(similar to RAL 5002) or red (similar to RAL 3002).
4	**Top Roll**	Made of Anodized Aluminium
5	**Opening / Closing Speed**	up to max. 1.2 / 1.2 m/s.
6	**Wind load resistance**	class 1 (EN 12424) up to DH = 3500 mm, class 0 (EN 12424 at DH> 3500 mm
7	**Control System**	MCC Vector Control
8	**Drive unit:**	Hollow shaft gear motor.
9	**Bottom profile**	anodized aluminium.
10	**Protection**	IP 55
11	**Hood Cover**	Included
12	**Motor Cover**	Included
13	**Push Button for the both side**	Included
14	**Safety:**	Electrical safety contact edge
		Evaluation via integrated cable chain
		Door line photocell in the side frames
		Drop down protection by integrated balancing system

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 12-13 Weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Amol Gaware on 7758820333**

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd