Supply & Installtion of Telescopic belt conveyor		**Supplier Name**	**NIHVA Technologies**
Technical Specifcations - Telescopic Belt conveyor		**Contact No**	**Vijay 8551093333**
DOC REF	**STD-LE-BQ-R0-RFP-TELESCOPIC BELT CONVEYOR**	**Address**	**Pune maharashtra**
DRG NO	**LT000025**	**Manufacturer name**	**NIHVA Technologies**

TECH SPECS-SYSTEM COMPNENTS- SUGGESTED BY CLIENT

Sl no.	Type	Technical Specifications	Customer specification			Supplier Remarks
			UOM	Ref	Specs.	
CA-TS-1	General	Description	yes/no		Telescopic belt Conveyor for movement of irregular Bags of size 1000 x 500 x 500 mm into and out of the trucks .Max - 32 feet truck	OK
CA-TS-2		Technical Detail Drawing Provided	yes/no		NA	After PO reciept
CA-TS-3		Deviation Sheet Duly Populated - Declare Yes or No	yes/no		yes	Supplier to indicate Deviations with Full Clarity in the Deviation Template provided.
CA-TS-4		Safety Precautions Acceptable	yes/no		yes	EHS document to be referred.(Will refer seperatly)
CA-TS-5		Compliance to Safety Standards, Laws & Regulations Incl. the EHS Guidelines of Customer	yes/no		yes	EHS document to be referred.(Will refer seperatly)
CA-TS-6	Shipment Size & Typ	Shipment Min Size	mm		300mm x 100mm x 200mm Poly Bags & Carton Boxes	Ok
CA-TS-7		Shipment Max Size	mm		1016 mm x 508 mm x 508 mm Poly Bags & Carton Boxes	Ok
CA-TS-8		Shipment Min Weight	kg		1 kg (Poly Bags & Carton Boxes)	Ok
CA-TS-9		Shipment Max Weight	kg		25 (Poly Bags & Carton Boxes)	Ok
CA-TS-10		Shipment Type	Typ		Irregular shaped Nylon Bags / Regular Shaped Carton Boxes	Ok
CA-TS-11	Telescopic Belt Conveyor	Manufacturer Name	Name		Supplier to Specify	NIHVA Technologies
CA-TS-12		Nominal width	mm		1000	800 mm belt width we connsidered
CA-TS-13		Overall Height (Max) Exc Guide	mm		450 - 500 Max	850 mm total height from ground to belt top .
CA-TS-14		Collabsed Length	mm		5000	Ok
CA-TS-15		Extended Lebgth	mm		15000 (5000 + 10000mm extension)	Ok
CA-TS-16		Drive Power Rating- Belt Drive	kW		2.2- 3	Depend on design
CA-TS-17		Drive Power Rating - Conveyor Extension	kW		0.55-0.75	Depend on design
CA-TS-18		Drive Power Rating - Elevation	kW		NA	NA
CA-TS-19		Rated Voltage (Nom)	V		415	Ok
CA-TS-20		Drive Control	Typ		VFD	Ok
CA-TS-21		Type of Drive System	Typ		Geared Motor (Non Worm Type)	worm type
CA-TS-22		Geared Motor Make	Name		SEW Euro drive Geared Motor - Hollow Shaft with Torque Arm Only	Ok
CA-TS-23		Stand Design	Typ		Fixed	Stand is grouted to earth
CA-TS-24		Belt Type	Typ		PVC / PVK - Rought top	PVC black belt is ok for this ,
CA-TS-25		Belt Spec	Typ		Habasit or Forbo	Forbo make we use
CA-TS-26		Belt Joints	Typ		Mechanical	Ok
CA-TS-27		Bed Type	Typ		Slider Bed with Prepainted/Coated Galvalume	We use skid plate below the belt with powder coated
CA-TS-28		Actuation / Switch	Typ		Required at Panel and and at the front of the conveyor	Joystick type at the front (Ok)
CA-TS-29		Roller Support			NA	Na
CA-TS-30		Conveyor Speed (Nom)	m/s		0.4	Ok
CA-TS-31		Conveyor Speed (Max)	m/s		0.5	Ok
CA-TS-32		Conveyor Speed (Min)	m/s		0.3	Ok
CA-TS-33		Load capacity per unit length of Conveyor	kg/m		50	Ok
CA-TS-34		Belt Thickness (Nom)	mm		3	2.3 mm to 3 mm

NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Supply & Installtion of Telescopic belt conveyor

Technical Specifcations - Telescopic Belt conveyor

DOC REF STD-LE-BQ-R0-RFP-TELESCOPIC BELT CONVEYOR

DRG NO LT000025

LOGIC DOC NA

CA-TS-35		Manufacturer Name	Typ		Supplier to Specify	Forbo make belt
CA-TS-36		Tension Surface	Typ		Top	NA
CA-TS-37		Type of Conveyor Frame	Typ		Mild Steel	Mild steel with powder coated/painted
CA-TS-38		Section Dims - Conveyor Frame Section	mm		Supplier to Specify	As per design
CA-TS-39		Type of Slider Bed	mm		Pre-Coated ; Cold Formed Steel	Mild steel with powder coated/painted
CA-TS-40		Max Angle of Inclination	Degree		NA	NA
CA-TS-41		Section Dims - Conveyor Slider Bed Width	mm		1200 Max	As per design
CA-TS-42		Section Dims - Conveyor Slider Bed Section	mm		First Bend 40; Second Bend 15; Thk 2	As per design
CA-TS-43		Slider Bed - Length b/w Lap Joints (Nom)	mm		2400	As per design
CA-TS-44		Legs for Frame	Typ		Cold Formed Mild Steel	Mild steel with powder coated/painted
CA-TS-45		Length of Leg	mm		Supplier to Specify	As per design
CA-TS-46		Section Dims - Conveyor Legs	mm		Supplier to Specify	As per design
CA-TS-47		Section Dims - Conveyor Legs-Cross Support	mm		Supplier to Specify	As per design
CA-TS-48		No of Cross Supports/Leg Assy	#		Supplier to Specify	As per design
CA-TS-49		No of Leg per Assy	#		3	As per design
CA-TS-50		No of Feet / Leg Assy	#		2	As per design
CA-TS-51		Spacing of Legs over Conveyor Length	mm		2400	As per design
CA-TS-52		Max Angle of Inclination	Degree		Upto 7 Degree Adjustable	4 degree of inclination is ok ,
CA-TS-53		Belt Direction	Typ		Bi Directional	Ok
CA-TS-54	Availabilty Test	Availability Test Applicable	yes/no		Entire System as per FEM 9.222	**User Acceptance after commissioning of TBC**
CA-TS-55		Time for Availability Test	Typ		60 days post commissioning	Max 30-45 days
CA-TS-56		Tenure of Availability Test	Hrs		40	Ok
CA-TS-57		Initial Availability (During Testing)	%		> 90%	90%
CA-TS-58		Complete System Availability	%		> 99%	99%
CA-TS-59	Noise	Default (measuring procedure in accordance with advertisement)	dB		60	Noise of machine will be below 60 dB
CA-TS-60	Warranties	Warranty Period of 24 Months	yes/no		Vendor to Confirm	24 month Warranty Period begins after the Client Issues a Certificate of Completion of Commissioning
CA-TS-61		Consumables List Provided	yes/no		Vendor to provide	Ok after PO approval
CA-TS-62		Frequency of Periodic Maintenance Offered within the Warranty Period	Weeks		Vendor to provide	Ok after PO approval
CA-TS-63	Mainteance Arrangements					
CA-TS-64						
CA-TS-65		Frequency of Periodic Maintenance Offered in the AMC	Weeks		Vendor to specify	We will let you know after PO approval
CA-TS-66		Necessity for maintenance (e.g. lubrication) between Periodic maintenance	yes/no		Vendor to specify	We will let you know after PO approval
CA-TS-67		Future Expansion for Conveyors Considered	yes/no		yes	Please specify future expansion plan

Supplier Name NIHVA Technologies

Contact No Vijay 8551093333

Address Pune maharashtra

Manufacturer name NIHVA Technologies

NIHVA TECHNOLOGIES PVT. LTD.

Supply & Installtion of Telescopic belt conveyor

Technical Specifcations - Telescopic Belt conveyor

DOC REF STD-LE-BQ-R0-RFP-TELESCOPIC BELT CONVEYOR

DRG NO LT000025

LOGIC DOC NA

Supplier Name					**NIHVA Technologies**	
Contact No					**Vijay 8551093333**	
Address					**Pune maharashtra**	
Manufacturer name					**NIHVA Technologies**	
CA-TS-68	**Bought Out Parts**	Drive Motors & VFDs	Name		SEW Euro drive	All Drives need to be suitable for Network
CA-TS-69		Starters / Contactors	Name		SEW/Siemens	Siemens/Schiender
CA-TS-70		Switchgear Cabinet	Name		Rittal	Ok IP54
CA-TS-71		Terminal Boxes	Name		Rittal	Ok
CA-TS-72		Control Panel Cabinet	Name		Rittal (Model supplied to conform to IP 64)	We considered IP 54
CA-TS-73		Ingress Protection	Class		IP54	OK
CA-TS-74		PLC's	Name		Siemens / Mitsubishi	Siemens 4 " HMI
CA-TS-75	**Safety Guidelines**	Chain/Belt Guards	yes/no		yes	All Moving / Rotating members should have suitable & adequate Safety Guards / Rails as necessary to avoid ingress
CA-TS-76		Auto Stop Safety Guard	yes/no		yes	Ok
CA-TS-77		Conveyor / Load Unit Guides	yes/no		NA	NA
CA-TS-78		Safety Railings around the System	yes/no		Yes required	Ok MS powder coated/ painted
CA-TS-79		Access Ladders to the Maintenance Platforms	yes/no		NA	NA
CA-TS-80		Emergency Pull Cord along the Length of the Conveyor	yes/no		NA	NA
CA-TS-81		Focus Lights	yes/no		2 nos at front of the conveyor	2 no, focus light / 1 tube light
CA-TS-82		E-Stop Buttons at regular intervals	yes/no		At conveyor front & middle of system & Panels	1 at front , one at rear and one on panel
IMPORTANT NOTES						

1	ANY DEVIATIONS FROM THE SPECIFICATIONS MENTIONED IN THE TECH SPECS SHEET SHOULD BE HIGHLIGHTED TO US AND RECORDED IN DEVIAION TEMPLATE ONLY.
2	ANY DEVIAIOTN WILL NOT BE ACCEPTED AT ANY STAGE OF THIS PROJECT UNLESS ARE OTHERWISE DISCUSSED AND APPROVED BY US.
3	VENDOR SHOULD ENSURE ALL THE REQUIREMENTS MENTIONED IN DESIGN MANDATORY POINTS ARE STRICTLY FOLLOWED. DEVIATIONS WILL NOT BE ACCEPTED.
4	Electrical power drop will be given only to one drop point. Distribution within the overall system is in the scope of Vendor.
5	All the Rotating parts throughout the conveyor to be 100% covered to avoid finger ingress. (Shafts, End sections, Conveyor Bottom, Dirve units)
6	All Control panels to be provided with barrications for all the 4 sides upto 1800mm with Front door, rubber mat,earth protection device, arc flash boundary.warning signs etc.
7	The Gaps between the conveyors is indicative. Supplier to ensure that the Gaps have to be suitably designed for seamless movement of Load Units
8	Widths mentioned are as per the Drawing. However, the same need to be as per the Design Requirement based on the Load
9	All Pick-up & Drop Points to have necessary Safety Guards & Bumpers
10	The Lengths mentioned here have been rounded off and are for the purpose of proposal only. On the event of being awarded the contract, the Supplier is responsible for Detail Engineering to the exact Millimeters as required
11	Supplier is responsible for the Detailed Design / Manufacture / Supply / Implementation of the Overall System
12	The Transfer from belt conveyor to roller conveyors shall be smooth and roller conveyors shall have rough/rubberized surface for efficient transfer
13	Quoted cost shall include all the costs for all the provisions/accessories unless specified as 'Optional'
14	Availability Tests shall be after a min. period of 2 Months after issue of Completion of Commissioning Certificate
15	In the case of repeatation of Availability Tests due to Conveyor Vendor, Conveyor Vendor shall bear the costs of the remaining Vendors & Consultants for Repeat test
16	Supplier to ensure that all key Makes mentioned are available in India
17	Supplier shall indicate in detail along with specifications, all the facilities required from other Suppliers / Contractors along with their proposal. For instance, Pit for Lift etc

NIHVA TECHNOLOGIES PVT. LTD.

Supply & Installtion of Telescopic belt conveyor		**Supplier Name**	**NIHVA Technologies**
Technical Specifcations - Telescopic Belt conveyor		**Contact No**	**Vijay 8551093333**
DOC REF	**STD-LE-BQ-R0-RFP-TELESCOPIC BELT CONVEYOR**	**Address**	**Pune maharashtra**
DRG NO	**LT000025**	**Manufacturer name**	**NIHVA Technologies**
LOGIC DOC	**NA**		

CMT POINTS- SUGGESTED BY CLIENT

#	Category	Description	Supplier Remark	Suggestion by supplier
1	General	Vendor to consider one set of spares(Refer annexure) in commercials. This is to be delivered along with machine.		
2	General	List of items to be covered in commercials is given in the annexure		
3	General	Vendor to commit the TAT in hours in case of breakdown calls unresolved by Customer. Time taken from complaint raising to technical resource on site to be 24 hours max		
4	General	Part replacement under warranty incase of part failure to be done within 7 days from the date of occurrence	OK	
5	General	Motor make SEW eurodrive	Ok	
6	General	Belt Forbo preferrable	Ok	
7	General	Siemen's PLC preferrable	Ok	
8	General	Quality certificate or equivalent report for own manufactured items like Rollers	Ok	
9	Control	HMI is required to identify the problems.	Ok 4 " HMI considered	
11	Control	Siemen's VFD preferrable	Ok 3 phase VFD considered	If we go for single phase VFD cost will reduce
12	General	Along with technical proposal, vendor to share the functional logics of the system		
13	Monitoring	Tower ligth with buzzer to be used for indicating device status (ready, stop or emergency stop)		

	SPARE ANNEXURE (Related to Pt.no.1)		**Supplier Remark**	
	ITEMS	**ORDER QUANTITY DETAILS**		
1	MOTORS +GEARBOX	1 nos per motor type	We will provide after PO approval	
2	CHAIN	Min length as installed in a TBC		
3	ROLLERS / SHAFTS	2 nos per roller type		
4	BEARINGS	5% of total installed quantities (min qty 1 nos)		
5	BELT	1 nos belt per type. If same type of belt with different lengths are available consider them as a separate line item		
6	PANEL ITEMS	1 nos all the panel components including but not limited to current protection devices, voltage protection devices, PLC and its accessories, drives , relays, push bottons, switches, HMIetc		
7	FIELD DEVICES	5% of total installed quantities (sensors, reflecting plates or stickers, emergency push buttons, emergency pull cords, isolater switches)		

Supply & Installtion of Telescopic belt conveyor		Supplier Name	NIHVA Technologies
Technical Specifcations - Telescopic Belt conveyor		Contact No	Vijay 8551093333
DOC REF	STD-LE-BQ-R0-RFP-TELESCOPIC BELT CONVEYOR	Address	Pune maharashtra
DRG NO	LT000025	Manufacturer name	NIHVA Technologies
LOGIC DOC	NA		

EHS CHECK POINTS- SUGGESTED BY CLIENT

S.no	Telescopic belt Conveyor	Supplier Remark
1	Pop out rollers shall be provisioned between the belt & roller conveyors to avoid the trap points	Ok
2	All control switches of the TBC should design basis on the "Hold to Run effect"	Ok but steel need to clarify by customer
3	Sping-loaded extension bar shall be fitted in front of the boom to prevent the person get trapped in-between telescopic belt conveyor & truck.	Ok
4	Bottom guards shall be designed & installed for the belt conveyor.	Maximum possible bottom guards will provide
5	Brush strips shall be installed between each moving stage of the conveyor to prevent debris / hand being drawn into the machine during retraction.	Gap between two booms are not more than 15-20 mm , so brush may not be required.
6	Boom end lights shall be considered in the design	Ok Tube light or Focus light
7	Fixed guards shall be mounted for all sprockets, chains rollers, belts and other moving parts.	For exposed sprocket and moving parts we will provide gaurds.
S.no	**General Points**	
1	LOTO provision shall be ensured on the isolation switches. Energy isolation switch shall be provisioned for module wise to ensure local isolation.	Ok , For each motor you need at near to motor or in control panel only please confirm
2	Double earthing for the machine & equipments, electrical drives, control panel & body of the machine shall be ensured	Ok
3	All electrical panels should be provisioned with rubber mat / earth protection device / arc flash boundary / warning signs etc.	Ok
4	Energy isolation placard/ safety device mapping etc. shall be part of the vendor scope.	Ok
5	Location of the machine & equipment should not block access to any fire protection system / electrical panel/ emergency exits / aisle etc.	Ok
6	Lifting plan / method statement / risk assessment shall be shared with EHS for perusal	Ok after PO approval we will provide
7	Machinery & Equipments and its components shall be free from sharp edges.	Ok
8	Lifting position from the conveyors shall not be more than1.2m	Ok as per design we will provide
9	Design risk assessment as per ISO 12100, OEM Manual & inventory of safety devices shall be shared by Adverb team.	Ok after PO approval we will provide
10	E-stop shall be provisioned at every 15 m intervals at both sides of the tote conveyor system. Category 0 & 1 only to be used for emergency stop as per the conveyor application.	Either 0 or 1 category can be used
11	Entire conveyor system shall be designed on fail safe architecture and all safety devices must meet performance level d & category 3 as per Functional safety requirements.	Ok
12	HMI / SCADA with necessary backup history shall be provisioned.	**Only HMI along with control panel will be provided**
13	Anti-fatigue floor mat shall be ensured.	NA
14	C02 & DCP type FEs 1 nos/panel shall be considered	Ok
15	LOTO accessories in required nos shall be included.	Ok

Supply & Installtion of Telescopic belt conveyor		Supplier Name	NIHVA Technologies
Technical Specifcations - Telescopic Belt conveyor		Contact No	Vijay 8551093333
DOC REF	STD-LE-BQ-R0-RFP-TELESCOPIC BELT CONVEYOR	Address	Pune Maharashtra
DRG NO	LT000025	Manufacturer name	NIHVA Technologies
LOGIC DOC	NA		

MAKES- SUGGESTED BY CLIENT

#	ITEM DESCRIPTION	MAKE	Supplier remark
1	PVC Top Nylon Fabric Straight Belt	Forbo/Habasit	Forbo PVC black
2	Friction(Rubber) Top Nylon Fabric Inclined Belt	Forbo/Habasit	
3	Idler Rollers	Itoh Denki/Interrol	Interroll
4	Transmission Chain	TI – Diamond	Diamond
5	Transmission 'V' Belts	Fenner/Gates	Gates
6	Geared Motors for Modules	SEW	SEW
7	Gearbox	SEW	SEW
8	Drive & Tail Pulley	Should be Crowned	Ok
9	Bearing/Pillow Blocks	NTN/FAG/SKF	NTN/FAG/SKF
10	Modular Belts	Eurobelt/Intralox	NA
11	Aux. Relay/24V DC relay	Siemens / L&T / Telemecanique	Siemens / L&T / Telemecanique/Schiender
12	Power Cables	Finolex, Polycab, Lapp	Ok
13	Control Panel, Boxes, Consoles	Rittal	Ok Only control panel rittal
14	MCB & MCCB	Siemens / L&T / ABB	Siemens / L&T / ABB/Schiender
15	Over Load Relay	Siemens / L&T / Telemecanique	Siemens / L&T / Telemecanique/Schiender
16	Power Contractor	Siemens/L&T/BCH/ABB	Siemens/L&T/BCH/ABB/Schiender
17	MCCB/ Main incomer	Siemens / L&T / ABB/Renu	Siemens / L&T / ABB/Renu/Schiender
18	Terminals	Wago (Germany)/Connectwel/Phoenix(Germany)	Ok
19	Pushbuttons illuminated	Tecknic	Ok
20	Emergency Push button	Tecknic	Ok
21	16 port Ethernet switch	D-Link	Ok
22	Profibus cable	Lapp / Siemens	Length of the cable?? And for what??
23	Ethernet cable	Finolex / Polycab / Lapp	Length of the cable?? And for what??
24	Micro PLC	Siemens(Germany) / MITSUBISHI	Ok
25	Sensors	P&F	P&F/Omron

NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Supply & Installtion of Telescopic belt conveyor		**Supplier Name**	**NIHVA Technologies**
Technical Specifcations - Telescopic Belt conveyor		**Contact No**	**Vijay 8551093333**
DOC REF	**E-BQ-R0-RFP-TELESCOPIC BELT CONVEYOR**	**Address**	**Pune Maharashtra**
DRG NO	**LT000025**	**Manufacturer Name**	**NIHVA Technologies**
LOGIC DOC	**NA**		

DEVIATION TEMPLATE- SUGGESTED BY SUPPLIER

	Sl No.	Technical Specifications	Customer Specifications		Supplier Spec
			UOM	Spec.	
	PLEASE MENTION THE SL NO. OF THE SPECIFICATION	**PLEASE MENTION THE EXACT SPECIFICATION THAT HAS BEEN MENTIONED IN THE SPEC SHEET**	**SAME AS SPECIFICATION SHEET**	**SAME AS SPECIFICATION SHEET**	
		Type of Drive System	Geared Motor (Non Worm Type)		worm type
		Nominal width	mm	E2-T1,000	800 mm belt width we connsidered
		Overall Height (Max) Exc Guide	mm	450-500	850 mm total height from ground to belt top .
		Type of Drive System	Typ	Geared Motor (Non Worm Type)	Helical -worm type
		Bed Type	Typ	Slider Bed with Prepainted/Coated Galvalume	We use skid plate below the belt with powder coated
		Slider Bed - Length b/w Lap Joints (Nom)	mm	E2-T2,400	As per design
		Max Angle of Inclination	Degree	Upto 7 Degree Adjustable	4 degree of inclination is ok ,
		Annual Maintenance Contract Offered	yes/no	Vendor to provide	This AMC is only considered beyond Warranty Period. Scope of Work included & the Current Rate for such a contract need to be specified -(Ok but AMC charges extra)
		Nearest Service Location	Location	Vendor to provide	Please specify the Base Location of Trained & Experienced (Min. 1Yr) Service Personnel-- Based on your installation site
			SPARE ANNEXURE (Related to Pt.no.1)		
		MOTORS+GEARBOX	1 nos per motor type		We will provide after PO approval
		CHAIN	Min length as installed in a TBC		
		ROLLERS / SHAFTS	2 nos per roller type		
		BEARINGS	5% of total installed quantities (min qty 1 nos)		
		BELT	1 nos belt per type. If same type of belt with different lengths are		
		PANEL ITEMS	1 nos all the panel components including but not limited to current		
		FIELD DEVICES	5% of total installed quantities (sensors, reflecting plates or stickers,		
		EHS points			
		Fixed guards shall be mounted for all sprockets, chains rollers, belts			For exposed sprocket and moving parts we will provide gaurds.
		LOTO provision shall be ensured on the isolation switches. Energy			Ok , For each motor you need at near to motor or in control panel only please confirm
		E-stop shall be provisioned at every 15 m intervals at both sides of the			Either 0 or 1 category can be used

NOTE

1. Deviations mentioned in this sheet shall be allowed SUBJECT to Client / Consultant Approval in writing

2. Please note that Deviations not mentioned in this sheet will not be accepted at any stage