NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Honda Motorcycle
Bhiwade, Rajasthan

Project, Location :

Date : 27.1.2021
Quote NO : SQT.20.21.2982
Kind Attn : Aseem Gupta
Email Id : agengineer49@yahoo.com
Contact No: 8003296357

Subject : Quotation for motorized rolling shutter puff insulated

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Double Wall Motorized Rolling Shutter**	3000	4000	9	177,000	1,593,000	20,000	180,000
	Total			**9**		**1,593,000**		**180,000**
2	P&F Charges			3%		47,790		
	Total Without Taxes					1,640,790		180,000
	GST Extra @ 18%			18%		295,342.20		32,400
	Total With Taxes					**1,936,132**		**212,400**
3	Transportation Charges					Extra at atcual		
4	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Double Wall Rolling Shutter

Sr .No.	Specification	Double Wall Rolling Shutter
1	**Thermal Insulation**	Shutter infill of 20 mm PU rigid foam ensuring excellent thermal insulation
2	**Side guide Protection**	Black plastic strips on the edge of the side guides protect against abrasion and ensure longevity of shutters
3	**Closing edge Safety device (only for Motorized)**	Sensor controlled safety devices to monitor the bottom edge of the door. Instant stoppage and reversing on encountering any obstruction while closing .
4	**Sealing :**	Rubber seals are provided to reduce friction and sound, thereby ensuring a smooth door travel
5	**Accessories (Optional)**	Vision panels for better visibility and light can be provided at extra cost
6	**Door Curtain**	Aluminium curved slats
7	**Support Brackets**	Galvanized steel
8	**Space Requirement (in mm)**	Head room (S) = 675, minimum fitting depth for operator and support brackets (ET) = 450 (Space reqd for removal of cover is 2 times of cover) , Side space requirment (PS) = 210
9	**Minimum requirement for Building Structure**	Concrete = 140 mm (Min strength M10) , Steel = 5 mm, Brick work = 240 mm (Min strength 100 kg/cm^2
10	**Side Guides**	FS 160 A - moulded aluminium guide rails with guide channel, black plastic runner
11	**Bottom Profile**	Extruded aluminium, Double skinned
12	**Seals**	Lintel seal, Bottom seal made of EPDM profile
13	**Fixing Material**	Tested and approved for steel, concrete, brickwork
14	**Operator**	Shaft operator, Ready to fit shaft operator, Power Input - 1 phase current 0.25 kW, Protection category IP65 (jet water protected)
15	**Control**	Integrated microprocessor control along with operator, Adjustable force limit and connection cable with CEE male plug in protection category IP 44
16	**Standard accessories**	Chain Hoist and Shoot Bolt - for manual door
17	**Push Button**	For Automatic Door

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd