1 mm GI Motorised Single Skin Rolling Shutter - Indirect Drive

Sr .No.	Specification	1 mm GI Motorised Single Skin Rolling Shutter - Indirect Drive
1	**Description:**	Motorised Rolling Shutter with GI Slats with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick GI.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." T" Shaped profile 65 mm -150 mm x 3 mm thick.
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm
12	**Surface finish**	PU paint or Powder coated
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

WORK ORDER

NIHVA TECHNOLOGIES PVT. LTD.

Client:			
Address:			

PO Number:	2570030709	**W. O. No-**	SO/23-24/051
PO Dated :	04.08.2023	**W. O. Date**	28-11-2023
PO Received Date:	08.08.2023	**Sales Co ordinator**	
Ref. Quotation:		**Front Sales Person**	

Contact Details		**Billing Address:**	**Dispatch Address:**
Contact Person:			
Email ID of contact Person:			
Mobile No:			

A **Technical Terms:**

Sr. No	Description of Goods	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	**Motorized Single Skin Rolling Shutter (for Engine Building 1 UPS room) W 2000 mm X H 2600 mm**	Nos	1		-	-	Pending
					Total		-

Non standard items/extra requirement, if any:

B **Commerical Terms:**

1	**Payment Terms:**	Payment on 30 days from GR based on acceptance.		
2A	**Delivery Date as per PO:**		**2B. Required Delivery Date:**	
3A	**Transportation Scope:**	Included	**3B. Transportation Charges:**	
4	**P&F Charges:**	Included		
5A	**Loading Scope:**	NIHVA Scope	**5B. Loading Charges:**	
6A	**Unloading Scope:**	Included	**6B. Unloading Charges:**	
7A	**Lifting Equipments Scope:**	CLIENT Scope	**7B. Available Lifting Equipments:**	
8	**Warranty:**	12 months from the date of supply.		
9A	**Height arrangement Scope:**	CLIENT Scope	**9B. Available Equipments for working at Site:**	
10	**Electricity Supply:**	CLIENT Scope		
11	**GST:**	18%		
12A	**Installation Scope:**	NIHVA Scope	**12B. Installation required date:**	
13	**Mode of import:**	NA		
14	**HSS:**	NA		
15	**Documentation Required:**	Standard Handover Documents		
16A	**Total site visits required:**		**16B. Site visit charges:**	

Certified that the above work order finalised in presence of:

GM	AGM	SALES		Operation	PROJECT	DESIGN	Date & Time