Chakan 38 Acre
ROHAN CITYSCAPE PVT LTD
Building B100
Removing & Stacking of Rolling Shutter

Quote No. **SQT19_20.2393**
Date **03.02.2020**

BOQ Abstract

Sr. No.	BOQ ID	BOQ Name	BOQ Description	Note	Unit	Rate	Quantity	Amount	Remark
1									
1.1			Removing of Gear operating Rolling shutter and stacking at designated place/ store .						
1.1.1			Removing gear operated rolling shutter fabricated from steel laths of minimum thickness 0.9mm with lock plate of 3.15 mm thickness reinforced with 35x35x5 mm angle section fitted with sliding bolts and handles for both sides, deep M.S. Channel section of depth and thickness not less than 65 mm and 3.15 mm respectively with hold fast arrangements, M.S. Bracket plate 300 x 300 x3.15 mm minimum size and shape with square bar suspension shaft minimum 32mm diameter, hood cover of M.S. sheet not less than 0.9 mm thickness and of any size at top and safety device including mechanical gear operation arrangement consisting of worm gear wheels and worm of high grade cast iron or mild steel and one coat of red lead primer and two coats of enamel paint (RAL-7001)etc. complete. (I.S. 6248 - 1979) etc. Vendor to make own arrangements for power,store & security etc as required at site. Removing and stacking properly at designated place/store .						
			Size 2.445 x 3.033 M		Nos	10000	14	1,40,000.00	
			Size 4.000 x 5.000 M		Nos	10000	2	20,000.00	
			Total Amount in Rs.					**1,60,000.00**	