NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

MMC Doortech
Chennai

Date : 20.03.2021
Quote NO : SQT.20.21.3111R
Kind Attn : Mahalakshmi
Email Id : jollybanerji@gmail.com
Contact No: 9884082122

Project, Location : GMR Project, Hyderabad

Subject : Revised Quotation for Motorized Rolling Shutter, Sectional Doors and Sliding Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Motorized Single Skin Rolling Shutter**	4000	5000	1	147,000	147,000	15,000	15,000
2	**Motorized Single Skin Rolling Shutter**	3600	3000	2	103,000	206,000	15,000	30,000
3	**Motorized Single Skin Rolling Shutter**	2400	3000	1	86,000	86,000	15,000	15,000
4	**Sectional Door - Standard Lift**	2400	2400	85	200,000	17,000,000	15,000	1,275,000
5	**Automatic Single Leaf Sliding Gate**	6000	2000	1	389,000	389,000	15,000	15,000
6	**Automatic Single Leaf Sliding Gate**	6000	2400	1	405,000	405,000	15,000	15,000
7	**Wicket Gate**	1200	2100	1	30,000	30,000	10,000	10,000
8	**Dock Leveler 6Ton**	2000	3000	33	190,000	6,270,000	15,000	495,000
	Total			**125**		**24,533,000**		**1,870,000**
9	P&F Charges			3%		735,990		
	Total Without Taxes					25,268,990		1,870,000
	GST Extra @ 18%			18%		4,548,418.20		336,600
	Total With Taxes					**29,817,408**		**2,206,600**
10	Transportation Charges					Extra at atcual		
11	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Rolling Shutter

Sr .No.	Specification	GI Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with GI Slats with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick GI.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." T" Shaped profile 65 mm -150 mm x 3 mm thick.
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm
12	**Surface finish**	PU paint or Powder coated
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

Motorized Single Leaf Sliding Gate

Sr .No.	Specification	Motorized Single Leaf Sliding Gate
1	Door type	Motorized Sliding Gate
2	Opening Direction	Horizontal - from left to right or reverse
3	Mounting Location area	Inside area
4	Design Pattern	Standard Tubular Design Pattern
5	Outer Tube	72 x 72 x 3.2mm MS SQ. TUBE
6	For Post	72 x 72 x 3.2mm MS SQ. TUBE
7	Innear Tube	38x38x3.20mm/40x40x3.2 MS SQ. TUBE
8	Gap Between Tubes	125mm
9	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
13	El motor make	BFT – Italy (100% imported)
14	Emergency Operation	Manual after turn the switch
15	Operating Switch	Push Button from inside
16	Safety	Photocells, Flashing Light

Wicket Gate

Sr .No.	Specification	Wicket Gate
1	Door type	Manual Single Leaf Wicket Gate
2	Size considered	Clear opening - (W)1200 mm x (H)2100 mm
3	Mounting Location area	Inside area
4	Design Pattern	Standard Tubular Design Pattern
5	Outer Frame Tube Sizes	80 x 80 x 3.2 mm
6	Internal Vertical Tube Sizes	40 x 40 x 2 mm
7	Gap Between Tubes	100 mm C/C
8	Painting	2 Coats of EPOXY polyamide based enamel finish of approved Colour
9	Operation	Manually Opening

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

Sectional Door

Sr. No	Description	Specification
1	Model No	ASSA ABLOY OH1042P
2	Opening Direction & Mounting	Standard
3	Opening/Closing Speed	CDM9 0,28 m/s
4	Door Material	Steel
5	Panel Thickness	42 mm
6	Filling	CFC-free polyurethane
7	Door sealent	All door sealants made of EPDM rubber, temperature resistant - 30/+70
8	Water Penetration	EN 12425 class 3
9	Air Permealibity	EN12426 class 3
10	Thermal Transittance	EN 12428 1.10W /m2K
11	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
12	Door saftey	Doors equiped with spring break device
13	Incase of Power failuer	Doors to be equiped with quick release fuction
14	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
15	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft
16	Emergency Operation	by Disengagement rope manual
17	Operating Switch	Up/Down Keypad + stopbutton
18	Locks : Lock bolt	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible from the outside.
19	Environmental Green Product Declaration Certification	As per ISO 14025 and EN 15804

Dock Leveler

Sr .No.	Specification	Specifications
1	**Capacity**	6 Ton
2	**Dock operation mode**	AC power pack hydraulically operated
3	**Lip operation mode**	Hydraulic
4	**Operation control**	Through panel
5	**Loading platform height from road**	1250mm
6	**Travel above & below dock level**	(+) 300 / (-) 250 mm
7	**Platform Size (W x L)**	2000 mm x 3000 mm
8	**Lip size (W x L)**	2000 x 400 mm
9	**Shut Height**	480 mm
10	**Overall length**	2000mm x 3000mm + Lip Length (400mm)
11	**Maximum slope can be achieved**	10%
12	**Clear Pit dimensions (W x L x D)**	(W) 2050mm x (L)3000 mm x (D)485 mm
13	**Hydraulic power pack**	Standard
14	**Driver type**	Direct by electric Motor
15	**Motor Ratings**	1 H.P
16	**Pump design flow**	2.5 LPM
17	**Pump pressure**	120 bar Operating 200 bar Max.
18	**Safety valve set pressure**	120 Kg/cm²
19	**Pump Type**	Gear
20	**Volume of oil receiver**	7 Lit
21	**No Of Deck cylinder**	2 No
22	**Lip Cylinder**	1 No
23	**Yellow and Black Strips for Side Guide**	Included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 - 12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd