NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Mahendra Windoor Solutions
H. No. 7-38, Bapuji Nagar, Nacharam,
Hyderabad - 500 076

Date : 28.08.2019
Quote NO : SQT/19-20/1985
Kind Attn : Mr. Pujesh M. Davda
Email Id : pujesh@mahendrawindoor.com
Contact No: 8978911911

Subject : Quotation for Rolling Shutter.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	GI Push Pull Rolling Shutter	3000	4000	3	74,000	222,000	10,000	30,000
2	GI Push Pull Grill Rolling Shutter	3000	4000	1	85,000	85,000	10,000	10,000
3	GI Push Pull Rolling Shutter	3000	3000	1	61,000	61,000	10,000	10,000
4	GI Push Pull Rolling Shutter	2500	3000	1	54,000	54,000	10,000	10,000
5	GI Gear Grill Operated Rolling Shutter	3500	3500	2	88,000	176,000	15,000	30,000
6	GI Gear Operated Rolling Shutter	4000	4500	2	107,000	214,000	15,000	30,000
7	GI Gear Grill Operated Rolling Shutter	4000	4500	1	114,000	114,000	15,000	15,000
				Total		**926,000**		**135,000**
8	P&F Charges			3%		27,780		
	Total Without Taxes					953,780		135,000
	GST Extra @ 18%			18%		171,680.40		24,300
	Total With Taxes					**1,125,460**		**159,300**
9	Transportation Charges					In Client Scope		
10	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr .No.	Specification	GI Motorized Rolling Shutter
1	GI Slat	1.0 mm Thick
2	Profile	Curved Type Profile with heavy duty Shaft
3	Guide	3 mm Thick MS Guide
4	Hood Cover	1.2 mm Thick GI material
5	Include	With Painting
6	Type	Push Pull

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr.Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd