NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Ratnarup Projects Pvt. Ltd
Pune

Date : 29.03.2021
Quote NO : SQT.20.21.3127
Kind Attn : Nilesh Waghmode
Email Id : purchase@ratnarupprojects.com
Contact No: 9657859393

Project Name & Location: Foton,CHAKAN

Subject : Quotation for Gear Operated Rolling Shutter with Grill

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer -

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**1 mm MS Gear Operated Rolling Shutter with Grill**	6000	6000	1	169,000	169,000	15,000	15,000
2	**1 mm MS Gear Operated Rolling Shutter with Grill**	6000	5000	1	146,000	146,000	15,000	15,000
3	**1 mm MS Gear Operated Rolling Shutter with Grill**	6000	4000	1	122,000	122,000	15,000	15,000
4	**1 mm MS Gear Operated Rolling Shutter with Grill**	5000	4000	1	106,000	106,000	15,000	15,000
5	**1 mm MS Gear Operated Rolling Shutter with Grill**	4500	5000	1	115,000	115,000	15,000	15,000
6	**1 mm MS Gear Operated Rolling Shutter with Grill**	4000	3500	1	82,000	82,000	15,000	15,000
7	**1 mm MS Gear Operated Rolling Shutter with Grill**	3000	4500	1	79,000	79,000	15,000	15,000
8	**1 mm MS Gear Operated Rolling Shutter with Grill**	3000	3500	1	67,000	67,000	15,000	15,000
9	**Uninstallation of Existing Rolling Shutter**			1	25,000	25,000		-
			Total	**9**		**911,000**		**120,000**
			P&F Charges	3%		**27,330**		
			Total Without Taxes			**938,330**		**120,000**
			GST Extra @ 18%	18%		168,899		21,600
			Total With Taxes			**1,107,229**		**141,600**
			Transportation Charges			**Extra at actual**		
			Unloading Charges @ Site			**In client scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

MS Gear Operated Rolling Shutter with Grill





Sr .No.	Specification	MS Gear Operated Rolling Shutter with Grill
1	**Description**	Gear Operated Rolling Shutter with MS slats with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete
4	**Curtain Panel**	The panel made of 1.0mm thick GI.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved with Grill at Centre
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." T" Shaped profile 65 mm -150 mm x 3 mm thick.
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm.
11	**Surface finish**	2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc phosphate primer
12	**Operation**	Gear Assembly.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	In client scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In client scope
3	Electrical Supply on the site single phase/three phase points at different places.	In client scope
4	Any civil / masonry/structural work required	In client scope
5	All structure support required	In client scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In client scope
7	Conduits, Cables required	In client scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333**

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd