NIHVA TECHNOLOGIES

WEIGHT ESTIMATION SHEET

CLIENT						**DATE**	**28-05-2024**	
PROJECT			**Dock Leveller**			**LOCATION**	**Pune**	
FINISH SIZE (Clear Opening)			**2000*2500mm**			**PREPARED BY**	**Bheemappa**	
SR.NO	**DESCRIPTION**	**SIZE**	**MTL**	**MTR**	**NOS**	**WEIGHT MTR/NOS**	**TOTAL WEIGHT**	
1	isa	100 x8	MS	17.4		12.6	218.5	
2	ismb	150 x 80	MS	15		15.0	225.0	
3	ismc	100 x 40	MS	4		10.0	40.0	
4	cyl pl	100 x 16	MS	1.92		12.6	24.1	
5	back pl	100 x 16	MS	1.2		12.6	15.1	
6	cyl front	50 x 16	MS	0.93		6.3	5.8	
7	flp pl	400 x 12	MS	2		37.7	75.4	
8	che pl	2000 x 6	MS	2.5		106.2	265.5	
9	flp pl	30 x 5	MS	2		1.2	2.4	
10	bup pl	50 x 8	MS	0.5		3.1	1.6	
11	ruber	50 x 50	MS	0.5		7.1	3.6	
12	bush	dia45	MS	0.8		12.5	10.0	
13	pin	dia32	EN8	2		7.5	15.1	
14	flp bush	dia 32	MS	2		7.5	15.1	
15	fla pin	dia 20	MS	2		2.5	4.9	
16	pipe	od 50x4	MS	4.4		5.0	22.0	
17	side	250 x 2	MS	8		3.9	31.4	
18	Hydraulic Single acting	Cylinder Bore-63 x Rod 45 x 400 Stroke	ms		2nos			
19	Hydraulic Double acting	Cylinder Bore-40 x Rod 32 x 120 Stroke	ms		1nos			
20	Power pack	2hp, 1Ph, 10ltr tank Capacity Operation - Single acting Cylinder -2nos, operating double acting Cylinder -1nos, operating	ms		1nos			
21	Control Panel	2hp, 1Ph, IP66 With PLC			1nos			
						ACTUL WEIGHT	975.42677	
							97.542677	
						TOTAL WEIGHT	1072.969447	

		WHEEL GUIDE MTL						
1	PLATE	250 X250 X8THK	MS		4	4.0	16	
2	ERW PIPE	50NB X 5THK	MS	5		7	35	
3	ELBOW	50NB 90DEGREE	MS		4	3	12	
4	ANCHOR	ANCHOR FASTNER M16 X150L	MS		16			
						WEIGHT	63	
		BUMPERS						
1	Pair of Mega Bumpers - 250mm (Width) x 100mm (Depth) x 450mm (Height)					1SET		
2	Pair of Floating Bumpers - 150mm (Width) x 80mm (Depth) x 550mm (Height)					1 SET		
3	Pair of Super Bumpers - 150mm (Width) x 80mm (Depth) x 400mm (Height)					1SET		
4	Flashing Light					1nos		
	Articulated Arm; LED Dock Light 60W; IP66.					1nos		
	External Traffic Light - Green & Red					1nos		

