**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**Address**
4m,407,Hrbr,2nd floor, Kalyan nagar
Bangalore

**Date : 03.02.2021**
Quote NO : SQT.20-21.2485
**Kind Attn : Maxiple**
Email Id : sales@maxipleglobal.com
Contact No: 9902065522

**Project Name & Location: Retractable Roof, Bangalore**

**Subject : Quotation for Retractable Roof**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 1 |
| C. | General Conditions | 2 |
| D. | Terms & Condtions | 2 |

### A) Commercial Offer

| Sr No | Description | Size | Qty | Supply and Installation Charges in INR | |
|---|---|---|---|---|---|
| | | | (Nos) | Unit Price | Total Amount |
| 1 | Retractable Roof | 5600 X 5400 X 900 X 3 segment<br>Inclusive Installation | 1 | 5,80,000 | 5,80,000 |
| | | | **Total** | | **5,80,000** |
| | | | **Total Without Taxes** | | **5,80,000** |
| | | | GST Extra @ 18% | 18% | 1,04,400 |
| | | | **Total With Taxes** | | **6,84,400** |
| | | | Transportation Charges | | **In Client Scope** |
| | | | Unloading Charges @ Site | | **In Client Scope** |

### B) Technical Specification

| |
|---|
| **1. Polycarbonate Israel Make compact clear 4.0 mm Thick** |
| **2. Profile : Powder Coated AL Frame (As per RAL colour )** |
| **3. Guide : Annodized AL Guide** |
| **4. Interlocking** |
| **5. Motors with Remote Control**<br>**a) Single Phase Bi-directional Motor**<br>**b) Speed- 09-12m/min**<br>**c) Power- As per Roof Dimension**<br>**d) Mechanical Limit Switch**<br>**e) Rack and Pinion Arrangement -Z16/Molude4/Module6**<br>**f) Italian Make BFT Brand** |
| **6. Control Panel** |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipments are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 30-45 days from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply , 10 years warranty for polycarbonate sheets and 5 years on powder coated AL Profile.

With Best Regards
Pratibha
8530872333
For NIHVA Technologies Pvt Ltd