NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Rajat Vinyl Pvt Ltd
Near Raydi Bus Stop
Rayadi. Tal.Jamkandorana,Dhoraji - 360410

Project, Location : Gujarat

Date : 01.02.2021
Quote NO : SQT.20.21.2745R
Kind Attn : Ajay Dave
Email Id : marketing@rajatvinyls.com
Contact No: 9624578610

Subject : Revised Quotation for Secondary Packaging Machine

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Secondary Packaging Machine with Manual Print Application**			1	24,97,974	24,97,974	1,24,899	1,24,899
	Total			**1**		**24,97,974**		**1,24,899**
2	P&F Charges			3%		74,939		
	Total Without Taxes					25,72,913		1,24,899
	GST Extra @ 18%			18%		4,63,124.38		22,482
	Total With Taxes					**30,36,038**		**1,47,381**
3	Transportation Charges							Extra at atcual
4	Unloading Charges @ Site							Extra at atcual

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr no	Item	Discription
1	Product	PVC roll
2	Box size	390x 390x 550
		390x 390x 140
		260x 260x 550
3	Product size	Dia-390
		Dia-260
4	Product weight	35 kg max
5	Check weigher	Static type
6	Check weigher accuracy (in gram)	(+/- 30 gram)
7	Cycle time	60 sec
8	Belt	Chiorino/Forbo/NTN
9	Belt type	As applicable
10	Roller	Interroll/Excel
11	Bearing	SKF/NTN
12	Foot	Swift
13	Gearmotor	Bonfiglioli/MGM/equivalent
14	Sensors	P&F /Omron/Equivalent
15	Pneumatic	Festo/SMC/Genetic
16	HIMI	Mistubishi/Panasonic/Delta
17	PLC	Mistubishi/Panasonic/Delta
18	Electric item	Schiender/Equivalent
19	Printer	Godex
20	Gantry system	Festo/SMC/Genetic
21	MOC	MS poweder coated

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	3 % Extra as applicable
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	10-12 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	50% Advance along with Confirmed Purchase Order and Balance before Dispatch.
6	**Insurance**	:	Extra As applicable
7	**Taxes**	:	GST Extra as applicable
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to contact **Mr.Vijay Tarak - 8551093333** For any further Clarification /Information in this concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd